



RTML Plans for EDR

PT - NS
SLAC - FNAL



RTML Kick-Off Meeting

- The purpose of the KOM is to understand where we are now

Questions we want to address:

- How complete is the RDR estimate? Are there major holes in the estimate?
 - **Extraction lines in the RTML (3 per side) are not in the current design, so their magnets and pulsed bends are missing and therefore their power supplies are missing (Recent progress in design)**
 - **Anything else? Are there any places where educated guesses were made and additional design refinements would significantly improve the quality of the estimate?**
- What assumptions, specifications, etc, were made in the estimate which significantly impact cost or performance? Things like **extremely tight stability tolerances, redundant power supplies, dual transducers, etc.** Obviously, the decision to give each quad a power supply is one of the assumptions here.
- What are the main opportunities for cost reduction going forward, and how do we make them real?
- What additional work has to be done in the EDR era to improve the quality of cost estimate? What is your judgment about the current quality of the estimate?
- What the most critical areas



Goals of the EDR

- Determine the relevant engineering specs for all components and beamlines
 - **Ensure that a documented path from the physics requirements to the specs exists**
- Value engineering – verify that the design and specs represent the best balance between cost and performance
 - **IE, reduce cost through changing design and/or specs**
- Reduction of cost and cost uncertainty through engineering
 - **IE, keep design and specs the same and reduce costs through better engineering to meet the specs**
- R & D program and EDR design
 - **Complete the R & D program**
 - **Complete an ILC design which incorporates the R & D results and is generally closer to “ready to build” than the RDR design**
- Reduction of risk in the design




Goals of the EDR (2)

- Original RTML EDR plan (developed for ART) had assumed EDR was more like a DOE TDR
 - **Requires ~30% of engineering drawings done**
 - **Consequently, much effort focused on magnet and beamline engineering**
- Did not assume existence of PM Troika
 - **Effort went into planning for construction**
 - Basically doing PM work in this work package
- Current EDR plan changes the emphasis
 - **No urgent need to get detailed engineering drawings done**
 - **RTML leader responsible for developing an execution plan for the area**
 - RTML upstream areas need to be ready for beam early compared to BC, ML, BDS
 - Need to ensure that complete engineering for those areas occurs in a timely manner
 - Should be same time scale as sources and DRs
 - Need to understand timeline requirements from “here are my specs for this magnet / vacuum chamber / BPM”, to, “Here is the first set of magnets / vacuum chambers / BPMs from the vendor”



RTML Cost Distribution

- Total cost xxx MILCU per PHG 2007 March
xxx edited out by PHG
- Of that:
 - **CFS: 42%**
 - **RF, CM, Cryo: 22 %**
 - **Magnets + PS: 20 %**
 - **All the rest: 16 %**



- Instrumentation, vacuum, dumps, collimators, controls

- Best foci for cost reduction efforts:
 - **BCs (RF and CFS)**
 - **Turnaround and Arc (CFS)**
 - **Std beamline cells (Magnets + other)**
- A distant third



Implications of Cost Breakdown

- No point doing design engineering on CFS or RF portions of the cost pie
 - **Already being done in other parts of the WBS**
- *Might* be worth doing design engineering on conventional beamlines
 - **Only 1/3 of RTML total cost ...**
 - **... and RTML total cost is < 1/10 of ILC cost ...**
 - **... and resources are tight**
- Leaving cost aside, execution plan may (and probably will) demand some work on these areas in near term
 - **Engineering beamline design,**
 - **Power, Cooling for CFS**
 - **Remember that RTML upstream area is needed for DR extraction**
 - Implies that DR full-power commissioning cannot occur without RTML upstream area



RTML Risk Areas

- **Single-Bunch Beam Dynamics**
 - **Studies of beam tuning in BC using 2006 optics missed emittance target by a factor of 2**
 - 2007 optics will be worse due to longer DR beam
 - **Effects of dynamic misalignments (GM, vibrations, jitters) not studied yet**
 - **Feedback/Feedforward corrections**
 - **Stray fields in Return line**
 - Looks okay, but more understanding of fields other than dipole needed
 - Is Recycler experience relevant to RTML?
 - More AC dipole fields would also be useful
 - **Annoying collective effects not yet resolved**
 - Space charge incoherent tune spread – could cause some failure of global tuning methods
 - Resistive wakes in the vacuum chamber – not looked at for Return line yet
 - **Cavity fields**
 - Wakefield and RF kick from asymmetric coupler discussed at DESY meeting
 - Scary!



RTML Risk Areas (2)

- Beam-beam collision timing
 - **Need $\sim 0.25^\circ$ RMS stability of RF systems in each RTML wrt common master oscillator for 2% loss in integrated luminosity**
 - For nominal – shorter bunch parameters need correspondingly tighter tolerances
 - $0.25^\circ @ 1.3 \text{ GHz} = 0.53 \text{ psec}$
 - **Time scale of a few seconds**
 - Assume direct measurement of arrival time at IP + feedback to correct drifts which are slower than this
 - **Beam loading compensation**
 - RTML runs far off-crest
 - When beam arrives, need to change phase and power of RF station to compensate beam-induced fields and stay at correct voltage and phase



RTML Risk Areas (3)

- Attainable voltage
 - **BC2 runs at high gradient**
 - 30.2 MV/m for nominal, 31.0 MV/m for LowN
 - **If attainable voltage after R & D program is lower, changes are required**
 - Either more RF units or a lower final energy and consequent poorer emittance performance
- Packing factor of dense areas
 - **Turnaround and DRX arc in particular**
 - **If desired packing factor is impossible, either more beamline length or less optimal optics is needed**
- BC1 Wiggler bend magnets
 - **Very wide (~40 cm) good field region desirable**
 - Allows a wide range of R_{56} values, much flexibility in BC configuration
 - **Haven't fully reviewed this issue since migration to 2007 optics**
 - Do we still need 40 cm? Would 10-20 cm be enough?
 - **Highly unusual magnets may be needed!**



Technical Risks Summary:

If I take the sum of (probability * cost) to be the cost risk of the RTML, then I'm looking at a total cost risk of M\$ 50.

Risk	Probability	Cost, M\$	Prob*cost M\$
Packing Fraction	30%	12	3.6
Beam motion	10%	2?	0.2
Stray field optics	5%	5?	0.25
Space charge	20%?	5?	1.0
Ion instability	10%	5	0.5
CollWake	10%	5?	0.5
Emittance	75%	10?	7.5
Cavity pitches	50%	20	10
Gradient	75%	16	12
Phase stability	25%	60	15



EDR Plan: Working Assumptions

- Concentrate for the work specific for RTML only
- In our EDR plans we don't assume any design/engineering work already being done by other areas, even if their risk and cost impact are significant for RTML, unless our specs are different:
 - **Cavities, Cryomodules, Cryogenic**
 - **HLRF**
 - **LLRF**
 - **Beam diagnostics**
- We will provide specs and will work with technical groups



EDR Plan: Working Assumptions (2)

Use existing designs, where it is possible

- **Revision of existing design**
- **Optimization Performances and Cost**
- **Documentation**
- **Beam dump design**
 - **SLAC Beam Dump East**
 - **Radiation water handling, SLAC/SNS**
- **Pulse kicker, septa, some PS**
 - **SLAC, ...**




Proposed RTML EDR Plan

- Beamline design work
 - **Engineered RTML lattice, geometry-matched RTML lattice, ultra-short BC, magnet envelope estimation**
 - Necessary to really understand what RTML beamline looks like, move towards final design (EDR goal 4)
 - Some value engineering (ultra-short BC is value engineering) (EDR goal 2)
 - Necessary to reduce cost uncertainty, since some uncertainty was associated with design immaturity (EDR goal 3)
 - Addresses risk in areas with a high packing fraction (EDR goal 5)
 - **Work load: about 1.5 FTEs in FY08 and 1.5 FTEs in FY09**
 - Cornell would like to supply many of these (all?)
 - Don't know if they'll get the budget
 - **Ultra-short BC: Kyungpook National Univ., Korea**



Alternative bunch compressor



- Alternative two-stage BC has two rf sections and two chicanes with 4 bending magnets each. Each chicane includes a 34 m lattice of bending.
- Beams with bunch lengths of 6 mm rms and 9 mm rms can be compressed to 0.15 mm rms and 0.3 mm rms in the BC, respectively.
- Dispersion correction, orbit correction and skew-correction were performed for emittance tuning in the alternative BC.
- Horizontal and vertical emittance growths due to conservative machine errors are about ~ 10% (8.9 μm and 9.1 μm due to ISR and ISR+CSR, respectively) and ~4%, respectively.




Review
design
LET meeting
Dec 2007
SLAC



Engineering: Tunnel X-section



RTML_BC2



~0.5km Transferlines



Proposed EDR RTML Plan (2)

- Specifications Development
 - **Go through lattice and document specs on each device, beamline, etc**
 - Including path from physics goals of facility to specs
 - Pre-requisite for overall value engineering effort – understanding which specs drive costs, which are unknown
 - **Probably about 0.2 FTE**
 - **After that, missing specs need to be filled in**
 - Probably done in collaboration with accelerator physics effort. Request to Acc Physics group
 - Maybe another 0.2-0.3 FTE?



Proposed RTML EDR Plan (3)

- Accelerator physics studies
 - Address risks identified on slide 7
 - ART plan budgeted 0.5 FTE in FY08, 0.75 FTE in FY09
 - Probably about right (optimistic)
 - Maybe a little light, but > 1 FTE in either year seems excessive
- Value Engineering of high-value targets
 - Compressors, arcs, and turnarounds
 - Estimate 0.5 FTE for this
- EDR writing
 - Actual effort of typing and etc.
 - Old plan had 0.2 FTE for this
 - Can probably push into FY10 for Jan 1, 2010 EDR draft release
- Implementation Plan
 - ART plan budgeted 0.2 FTE in FY09 for this
 - More sensibly 0.2 FTE in FY08, 0.3 FTE in FY09

- ✓ • Long-range alignment
 - **Spec for initial linac 'straightness' and slow ground motion**
- ✓ • Trajectory control
 - **FB and magnet response times based on GM models**
- Energy control
 - **Measuring the beam energy profile and matching the quad lattice**
 - **Regulation of energy at the end of the linac**
- ✓ • Backgrounds and machine protection
 - **Halo, SR, MP, dark currents, spoilers and beam abort**



CA: ML, Wakefield/Cavity Topics

- Wake offset due to FPC/HOM antennae intrusions
- HOM absorber versus beam pipe losses
- Simulation of multi-cavity trapped modes
- Simulation of first/second band dipole mode properties and dipole mode data analysis
- Design of a lower R, E field and B field cavity with 60 mm irises
- Multipacting simulations in couplers and HOMs
- Surface magnetic field enhancement due to cell-to-cell misalignments



Proposed RTML EDR Plan (4)

- Total is about 2.8 FTE per year for 2 years
 - About k\$ 525 / year at SLAC or FNAL
 - About k\$ 315 / year at LEPP
 - Faculty salaries covered during school year
 - Grad students will work for food
- Far less than plan presented to ART
 - K\$ 625 in FY08 and k\$ 1758 in FY09
 - Leaves out serious magnet engineering from old ART plan
 - Is this OK?



ART WBS x.6 FY 08-09 Budget

Proposed ART work packages WBS x.6 and x.7. Probably needs revision

WBS	WBS(W	Description	Lab	FY08	FY08	FY08	FY09	FY09	FY09	continue	
											Pri
				Range	M&S		M&S				
					K\$	k\$	K\$	k\$			
2.6.1		Acc design									
	2.6.1.1	Engineered RTML lattice	SLAC +	1	0.3	0	55.02	0.45	0	85.48	Y
	2.6.1.2	Ultra-short bunch compressor	LEPP	2	0.5	3	58.83	0.5	3	60.42	N
	2.6.1.3.	Beam tails	LEPP	2	0.5	2	57.24	0.5	2	58.83	N
	2.6.1.4	Lattice design for EDR geometry	LEPP	1	0.5	3	58.83	0.5	2	58.83	Y
	2.6.1.5	EDR Writing	SLAC	1	0.1	0	18.34	0.2	10	39.00	Y
	2.6.1.6	Preparation for Construction	SLAC+	1	0	0	0	0.2	10	49.49	Y
2.6.2		Accelerator component design and engineering									
	2.6.2.1	Magnet envelope estimation	SLAC	1	0.2	0	36.68	0	0	0.00	N
	2.6.2.2	Beamline rough layout	SLAC	1	0.1	0	18.34	0	0	0.00	N
	2.6.2.3	Std quad engineering design	SLAC	1	1.4	0	256.8	0	0	0.00	N
	2.6.2.4	Dummy CavBPM Design	SLAC	2	0.4	0	64.19	0	0	0.00	N
	2.6.2.5	DRX Arc bend engineering design	TBD	1	0	0	0	1.4	0	265.93	N
	2.6.2.6	Std corrector engineering design	TBD	2	0	0	0	0.65	0	123.47	N
	2.6.2.7	Tuning quad engineering design	TBD	2	0	0	0	0.65	0	123.47	N
	2.6.2.8	DRX Arc Half-Cell Integration Design	TBD	2	0	0	0	0.2	0	37.99	N
	2.7.2.9	BC1 Wiggler Bend 1 engineering design	TBD	2	0	0	0	0.65	0	123.47	N
	2.6.2.10	BC1 Wiggler bend 2 engineering design	TBD	2	0	0	0	1.9	0	360.91	N
	2.6.2.11	BC1 wiggler half-cell integration design	TBD	2	0	0	0	0.4	0	75.98	N
	2.6.2.12	Return line quad engineering design	TBD	2	0	0	0	0.65	0	123.47	N
	2.6.2.13	Return Line Quad Pkg Integration Design	TBD	2	0	0	0	0.4	0	75.98	N
	2.6.2.14	DRX Arc In-Tunnel Integration Design	TBD	3	0	0	0	0.5	0	94.975	Y



ART WBS x.7 FY 08-09 Budget

WBS x.7 work packages related to RTML

WB	WBS	/BS (WF)	Description	FY08	FY08	FY08	FY09	FY09	FY09
				FTE	M&S	Total	FTE	M&S	Total
					k\$	k\$		k\$	k\$
2.7			Acc. Design						
		2.7.2.1	Wakefields studies at SLAC	1.5	0	275	1	0	190
		2.7.2.2	Wakefields studies at FNAL	0.5	0	90	1	0	190
	2.7.3		Acc. Physics						
		2.7.3.3	RTML Emitance preserv study	0.50	0	92	0.75	0	142
		2.7.3.4	RTML Emitance tuning - LEPP	1.00	3	109	1.00	3	112
		2.7.3.5	Start-to-end simulations - FNAL	0.75	0	135	1.00	0	190
	2.7.5	2.7.3.6	Start-to-end simulations - SLAC	0.50	0	92	0.75	0	142
		2.7.3.7	Dark current and MPS	0.00	0	0	0.35	0	66
3.7			R&D						
		3.7.2.1	L-band BPM design and test	1.25	50	238	1.4	110	393
	3.7.1		Quad package test						
		3.7.1.1	SC Quad prototype and tests	1.25	40	272	1.8	80	434
		3.7.1.2	SC Corrector prototype and tests	1	30	215	0.8	37	180



Proposed RTML EDR Plan (5)

- Magnet packages
 - **Design of the all magnets**
 - EM parameters, field quality
 - Dimensions for lattice engineering design
 - Power and Cooling requirements.
 - Integrated Correctors ? (build-in vs. separate)
 - **Prototyping of the most critical or costing components to prove performance/technology or better cost estimation (?)**
 - SC solenoid in spin rotators: $B=5$ T. → Short (0.5m) section to demonstrate technology
 - SC quad/corrector for RTML cryomodules, → demonstrate center stability, prove technology (in WBS x.7)
 - Q20L200 – (~1500 magnets in RTML) → cost impact
 - D25L900V3 - Wide aperture (40cm) bends in BC



RTML Magnets (PT Rev. July, 2007)

BENDS Family	Leff [m]	Max IntB [T.m]	Min IntB [T.m]	Gap height[m]	Count (e+e-)	Cost %	Notes
D25L100	0.1	0.028302246	0.028302246	0.0254	32	0.3	
D25L900V1	0.9	1.059074088	0.162887521	0.0254	128	3.1	
D25L900V2	0.9	0.90473627	0.025859524	0.0254	144	10.9	Req. ~40 cm wide good field region
D25L900V3	0.9	0.647594332	0.068687319	0.0254	144	8.4	Req. ~10 cm wide good field region
D25L1600	1.6	1.794199563	0.572341349	0.0254	76	6.3	
D25L2300	2.3	1.823498432	0.067196487	0.0254	180	16.6	
Total Bends					704		
QUADS Family	Leff [m]	Max IntG [T]	Min IntG [T]	Full apert. [m]	Count (e+ e-)		Notes
Q20L100	0.1	0.4	0.050000000	0.020	16	0.2	
Q50L100	0.1	0.15	0.002500000	0.050	32	1	
Q20L200	0.2	17.72946193	0.209329715	0.020	1474	20	Prototype
Q60L200	0.2	3.714074761	1.815746779	0.060	4	0.2	
QSC75L200	0.2	2.444561947	0.659891993	0.075	36	3.6	SC Quad in Cryomodule
Total Quads					1562		
DC Correct Family	Leff [m]	Max IntB [T.m]	Min IntB [T.m]	Full apert. [m]	Count (e+e-)		Notes
D20L50	.05	0.05318839	0.000627989	0.020	2240	23	separated or build-in? Need R&D
DSC75L200	0.2	0.00733369	0.001979676	0.075	54	2.2	SC Corrector in Cryomodule
Total Correct					2294		



Magnets (Cont.)

<i>FEED-FORWARD CORRECTORS</i>						
Family	L_{eff} [m]	Max IntB [T,m]	Min IntB [T,m]	Full apert. [m]	Count (e+ & e-)	Notes
D20LXXX	TBD	0.00063	0.00002168	0.02	8	
Total FF Correctors					8	~3.2% cost
<i>SOLENOIDS</i>						
Family	L_{eff} [m]	Max IntB [T,m]	Min IntB [T,m]	Full apert. [m]	Count (e+ & e-)	Notes
SLSC50L2600	2.6	13.0990313	13.0990313	0.05	8	SC Solenoid
Total Solenoids					8	

+ Magnets in 3 extraction lines per side (Dumps)

	L_{eff}	Max B		Apert. [m]		Notes
Pulsed Abort Kickers	2m	70 Gs		0.025	24	100 nsec, P= 0.5 MW
Fast Bends	1m	280 Gs		0.025	6	1msec, train-by-train
Septum magnets	1m	0.1 T		0.03	24	5Hz, >1.5ms flat-top
Bends	1m	2T		0.04	24	
Quads	0.8 m	0.9T		0.04	24	



RTML Magnets R&D (V.Kashikhin)

- All RTML magnets are feasible for design and fabrication.
- Total number of magnets 4576.
- Number of magnet styles: **Dipoles**- 6, **Quadrupoles** – 4 plus 1 –SC, **Correctors** – 2 plus 1 SC, 1 **SC solenoid**, plus **septums, bumps** and **kickers**.
- Time frame for the magnet design depends on many factors (region, firm, institution, salary range, experience, supporting structure, etc.) and better use bidding process to resolve this issue.
- Magnets for R&D and prototyping: 1- conventional dipole, 1- conventional quadrupole, 1- corrector, 1- superconducting quadrupole package including correctors, 1- superconducting solenoid 0.5 m model.
- Goals for R&D: prove chosen magnet technology, reliability, investigate magnetic center stability in quadrupoles at BBA, hysteresis effects in dipoles, prove the chosen magnetic measurement technique. Investigate coupling effects between main magnet and correctors. Investigate the magnets long term behavior.





Proposed RTML EDR Plan (6)

- Studies of Beam-beam collision timing
 - **Need $\sim 0.25^\circ$ RMS stability of RF systems in each RTML wrt common master oscillator for 2% loss in integrated luminosity**
 - **One or two RF systems (1 or 2 CMs)**
 - **Study stability of RF system, when beam**
 - **Experiment at TTF/DESY or NML/FNAL or KEK**
 - **Need more detailed plans**
 - **Resources \sim (???)**



Two RF systems

- Suggested by Tom Himel and PT. Idea- run two system 180° apart
- Allows to evaluate two systems with respect to each other – just like we need for the electron and positron BC's
- Relaxes the bunch arrival requirements
- If both systems are run at equal amplitudes, the correlated energy spread is canceled
- The phase jitter of one system with respect to another will show up as the energy jitter of the beam.
- Use energy spectrometer to evaluate the beam energy



S.Nagaitsev

Conclusions

- For a single RF unit:
 - Need a bunch compressor to resolve 0.05-degrees or 100-fs. Bunch length of 1-ps should work, 10-ps will not.
 - Can not run beam close to zero-crossing because of energy spread induced by rf slope and low injection energy.
 - Need also to measured the incoming bunch-to-bunch energy jitter so this calls for dispersive section (a compressor) before the CM
- For two RF units:
 - Need two rf units or, at least, two rf systems powering two cryomodules
 - Does not require bunch arrival jitter measurements.
 - Can run beam at zero-crossing



Summary of the EDR Plan

Item	FY08 FTE	FY09 FTE	FY10 FTE
Lattice design work	1.5	1.5	
Specifications Work	0.2	0.2	
Beam Dynamics	0.5	0.75	
Value Engineering	0.25	0.25	
Implementation Plan	0.2	0.3	
Magnet design Work	???	???	
Magnet prototyping	???	???	
Coll Timing studies	???	???	
Total	2.65+?	3.00+?	



People

- **Optics Design**

[Peter Tenenbaum](#) -- optics design of most sections, parameter selection for BC1 and BC2

[Jeff Smith](#) -- spin rotator

[Mark Woodley](#) -- skew correction and diagnostic section after the spin rotator, match from BC1 to BC2 RF and from BC2 RF to BC2 wiggler

[Sergei Seletskiy](#) -- BC1 and BC2 wigglers, new pulsed extraction lines (in progress)

[Eun-San Kim](#) -- ultra-short bunch compressor

- **Engineering**

[Vladimir Kashikhin](#) -- DC magnets

[Paul Bellomo](#) -- DC power supplies

[Tom Mattison](#) -- fast kickers, septa, dump sweepers, and power supplies for these magnets

[Yusuke Suetsugu](#) -- original vacuum system design for turnaround, warm areas of BC/BC2, pulsed extraction lines

[John Noonan](#) -- vacuum system design for Return lines

[Paolo Michelato](#) -- vacuum system for cryomodules

[Tom Markiewicz](#) -- dumps, stoppers, and collimators

[Ray Larsen](#) -- 1.3 GHz RF sources (klystrons and modulators)

[Manfred Wendt](#) -- Instrumentation, including dipole-mode cavities and power sources for them

[John Carwardine](#) -- original work on RTML controls

[Claude Saunders](#) -- later work on RTML controls

[Tom Peterson](#) -- cryogenics

[Fred Asiri](#) -- installation

[Jean-Luc Baldy](#) -- main contact on CFS

[Gerry Aarons](#) -- additional contact on CFS

[Tom Lackowski](#) -- contact on CFS, mainly for area near DR

[Gerry Dugan](#) -- engineered RTML Layout



People (2)

- **Performance**

[Peter Tenenbaum](#) -- dispersion control upstream of BC1, emittance preservation in BC1-BC2, collimator wakefields

[Jeff Smith](#) -- dispersion and coupling control upstream of BC1, spin preservation

[Kiyoshi Kubo](#) -- dispersion control upstream of BC1, emittance preservation in BC1-BC2, stray field effects

[Andrea Latina](#) -- emittance preservation in BC1-BC2

[Eun-San Kim](#) -- emittance preservation in ultra-short BC

[Lanfa Wang](#) -- estimates of ion instabilities and electron cloud effects

[Panagiotis Spentzouris](#) -- space charge (in progress)

[Marco Venturini](#) -- space charge (in progress)

[Sergei Seletskiy](#) -- beam-gas scattering

[Gerry Dugan](#) - emittance preservation