# Cavity Shape and Configuration

- SCRF Technology for The 1 TeV Upgrade -


## Kenji Saito, KEK

#### **Statement:**

Combine the LL high gradient cavity shape and the Superstructure,

then we could operate cavities at an effective gradient of 40-45MV/m.

#### RF Magnetic Critical Field



$$H_{C}^{RF}[mT] = \left(\frac{H_{P}}{E_{acc}}\right) \times E_{acc,max}[MV/m], \quad \frac{H_{P}}{E_{acc}} = 4.23[mT/(MV/m]@TESLAshape]$$

**Current technology has reached the fundamental limit!** 

RF magnetic critical field is around 180mT.

#### New Cavity Shape optimized for Hp/Eacc

TESLA

1992

LL(Richer)

2002/2004

RE

2002


TESLA shape was well optimized on Ep/Eacc(~2.0) in 1990's against field emission.

We know how to reduce  $H_P$  / Each: more volume in equator region and smaller iris.

#### Courtesy Jack Sekutowicz, DESY

		TESLA	LL(Ichiro)	RE
R <sub>iris</sub>	[mm]	35	30	33
$\kappa_{CC}$	[%]	1.9	1.52	1.8
$E_P/E_{acc}$	-	1.98	2.36	2.21
$H_P/E_{acc}$	[mT/(MV/m)]	4.25	3.61	3.76
R/Q	$[\Omega]$	113.8	133.7	126.8
$\Gamma$	$[\Omega]$	271	284	277
Expected $E_{acc,max}$ $@H_P=180mT$	[MV/m]	42.4	49.9	47.9

#### Successful Principle-Proof of High Gradient Cavity Shapes at KEK



#### LL 9-Cell Cavity Design/ RF Parameters

LL 9-cell cavity: FM parameters Courtesy Jacek Sekutowicz, DESY

Parameters	Unit	TESLA - Shape	LL-Shape	
Øiris	[mm]	70	60	] ,
K <sub>CC</sub>	[%]	1.9	1.52	5
$E_p/E_{acc}$	-	1.98	2.36	\  \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
H <sub>p</sub> /E <sub>acc</sub>	[mT·(MV/m) <sup>-1</sup> ]	4.15	3.61	$rac{1}{t}$
Lorentz factor*, k <sub>L</sub>	[Hz·(MV/m) <sup>-2</sup> ]	-0.74	-0.81	
R/Q	[Ω]	113.8	133.7	
G	[Ω]	271	284	
R/Q·G	[Ω·Ω]	30840	37970	
$k_{\perp}(\sigma_z = 1mm)$	[V/(pC·cm²)]	0.23	0.38	
$k_{\parallel}(\sigma_z=1mm)$	[V/pC]	1.46	1.72	

\*With optimally located
stiffening ring: TESLA shape
at
r = 54mm, LL-shape at
r=44mm when the wall
thickness is 2.8 mm.

	H-Gradient	RF Efficiency	Field emission	Cell to Cell coupling	Lorentz factor	HOM issue
Pros	20% high	20% high		no excites other passband		
Cons			20% high	20% small	10% week	65% increase


#### **HOM Issues in LL 9-Cell Cavity**

3rd passband makes always some problems.


Needs to optimize the End-cell!

Courtesy Jacek Sekutowicz, DESY

F=2.451071E+09




Excellent damping F=2.551659E+09




#### Successful Demonstration of ILC ACD Spec. by Ichiro Full 9-cell Cavity




CBP(80 $\mu$ m)+ CP(10 $\mu$ m)+AN(750°C, 3hr)+EP(80 $\mu$ m)+HPR Bake+VT @ KEK, then sent Jlab.




#### **KEK/JLAB** collaboration



#### **Optical Inspection of the Quench Location from 2nd Sound Signals**




### ICHIRO#7 S0-Study @ JLAB Current Summary



45MV/m is hoped by the next EP, further study will be done very soon9

### **Configuration: Superstructure**



There are 2 limitations in number of cells per structure:

- 1. Field unflatness (  $\sim N^2/k_{cc}$ )
- 2. HOM trapping

The beam currents of this structure does not exceed 500 μA and are well below ILC current of 9.5 mA.


Conclusion: we could not go this way for ILC (TESLA 1999).

### **Idea of the Superstructure (SST)**

These **limitations** could be relaxed **by** <u>weakly coupled structures</u> (superstructures), (JS, M. Ferrario, Ch. Tang, PRST-AB, 1999).

**SST layout:** Two (or more) N-cell structures are coupled by  $\lambda/2$  long tube (synchronization).

Each structure has its own cold tuner and HOM couplers.





One FPC/(2N) cells
Cost savings


Will the RF power flow via extremely weak coupling to keep energy constant over a train of bunches ???

#### Pioneer Study of the SST (2x7cell) in TESLA R&D at DESY

Courtesy Jacek Sekutowicz, DESY

The preparation of the experiment begun in 1999.


In 2002, two **2x7-cells SSTs** were assembled in the cryomodule and installed next to the injector in the TTF linac for the test.



Two 2x7-cell pairs for field profile adjustment and HOM measurements


#### Beam TEST of the STT(2x7Cell) at DESY

Direct measurements of the energy gain for the whole train



Beam acceleration test was successfully performed at Eacc =14.7MV/m!

#### Successful Beam acceleration by the SST (2x7cell) at DESY



No voltage drop was observed.

This was the first hint that SSTs works!!

#### **DESY's Conclusion on the STT**

#### DESY's Conclusions from the experiment

- The experiment showed that SST concept for acceleration works.
- The energy modulation  $\triangle E/E = 3.5 E-4 <$  the collider spec.  $\triangle E/E = 5 E-4$ , TESLA
- HOM damping is very good ( at least for 7-cell units)

#### **But**

• Handling and preparation are more difficult.



Demountable structure

• Subunits should be produced with tighter tolerances.

#### **Combined Scheme for the ILC 1TeV Upgrade**


Cavity Operation Gradient	Real Gradient [MV/m]  [V/(Structure length+interconnection/2)]  1x9cell	Real Gradient [MV/m]  [V/(Structure length+interconnection/2)]  2x9cell SST	Real Gradient [MV/m]  [V/(Structure length+interconnection/2)]  4x9cell SST
Eacc=31.5MV/m ILC Baseline	24.7	26.4 (Eacc, eff=33.7)	28.2(Eacc,eff=35.9)
Eacc=36MV/m ILC ACD	28.2	30.2 (Eacc,eff=38.5)	32.1(Eacc,eff=41.0)
Eacc=40MV/m ILC Upgrade	31.4	33.6 (Eacc,eff=42.8)	35.8 (Eacc,eff=45.6)

	Tunnel Length	Input Coupler	RF Distribution	LL Control	Cryogenic load	Gradient Performance	Cavity Fabrication Tolerance
Pros	7-14% shorter	Number reduces to 1/4 max.	Number of parts reduce to 1/4 max.	Station reduces to 1/4 max.	Reduces ~6kW max.@2K		
Cons		Power increases to 4 times max.				SST gradient is limited by the lowest gradient cavity	Becomes tighter

### Key Technologies for Superstructure & Ongoing R&D

#### **R&D 1 : Super joint**

To make SST handling easy, demountable structure is desirable. Super joint is needed for it.




#### Ongoing R&D on Super-Joint by P. Kneisel at JLab




2.7 GHz cavity for testing of sc gaskets

#### Application of MO seal for Super-Joint, to be started soon at KEK



#### **R&D 2**: High Power Coupler

For 4x9cell SST, 2MW coupler is needed but it almost exists.



# Summary

- LL full 9-cell cavity has reached the ILC alternative specification: Eacc=40MV/m @ Qo=0.8E+10.
- Combined scheme of LL shape and Superstructure will bring big benefit not only on the gradient performance but also on the cost reduction.
- Key R&D issues for this scheme will be the super joint and high power coupler.
- Of course the beam test is essential but it will be done rather easily using the existing SRF module test facility.
- So far the resource is limited very much for the ILC alternative R&D. If GDE takes more concern to this, the realization might be done in the 500GeV phase.

#### **HOM Issues in LL 9-Cell Cavity**

#### LL 9-cell cavity: HOMs

Damping modeling for end-cells I.

End-cell optimization not yet finished!

Mode	f [MHz]	(R/Q)* [Ω/cm <sup>n</sup> ]	Q <sub>ext</sub>
M: TM010-9	1300.00	1161	8·10⁵
D: TE111-7a	1717.15	5.0	4⋅10⁴
D: TE111-7b	1717.21	5.0	5⋅10⁴
D: TE111-8a	1738.12	3.0	6⋅10⁴
D: TE111-8b	1738.15	3.0	8⋅10⁴
D: TM110-2a	1882.15	3.4	6·10³
D: TM110-2b	1882.47	3.4	6·10³
D: TM110-4a	1912.04	4.6	9·10³
D: TM110-4b	1912.21	4.6	1.10⁴
D: TM110-5a	1927.10	15.6	1.5·10⁴
D: TM110-5b	1927.16	15.6	1.5·10⁴
D: TM110-6a	1940.25	12.1	2·10⁴
D: TM110-6b	1940.27	12.1	2·10⁴
M: TM011-6	2177.48	192	10⁴
M: TM011-7	2182.81	199	10⁴
D: 3-rd-1a	2451.07	31.6	1·10 <sup>5</sup>
D: 3-rd -1b	2451.15	31.6	2·10 <sup>5</sup>
D: 3-rd 1-2a	2457.04	22.2	5.10⁴
D: 3-rd 1-2b	2457.09	22.2	5⋅10⁴
D: 5-th – 7a	3057.43	0.5	3·10 <sup>5</sup>
D: 5-th – 7b	3057.45	0.5	3⋅10⁵

3060.83

3060.88

0.4

0.4

8·10<sup>5</sup>

9.105

D: 5-th - 8a

D: 5-th - 8b

