


ILC Infrastructure and ILD Integration

Karsten Buesser

ILC@DESY Project Meeting
16.10.2015

Infrastructure Working Group


Location of ILC Lab Main Campus and IP Campus



ILC alignment as proposed for Kitakami

- IP campus: above IP
- ILC lab main campus: not yet decided; somewhere between Shinkansen line and IP

Infrastructure and planning WG: Chair: Sakue Yamada one of the Physics-Detector WGs, active since June 2014



Members

ILD: K. Buesser, F. Simon/MC. Fouz,
SiD: M. Breidenbach, M. Stanitzki,
Local: K. Kawagoe, Y. Sugimoto,
Chair: S. Yamada

Given mandate

- 1: Study of the human and budgetary resource needs and their availability during construction and operation
- 2: The time profile of the resources and their reality to quire
- 3: The organizational structure to interact with the ILC laboratory

Purposes

A: to provide inputs from the detector groups to the Infrastructure design studies for the ILC lab, and to the Governance discussions

B: to prepare answers to possible inquiry in the expert sub-committee of the MEXT

The target date: February 2015.

Possible types of the ILC lab

- Three types were considered first:

A: Very simple lab with minimum facilities

B: More facilities and services as seen in the existing labs but not complete. (flexible between A and C)


C: Fully complete lab with everything (like e.g. CERN)

We assumed that ILC lab may be a kind of type B.


As required services are compiled, the type may end up rather closer to C than A.

Human resources for detector construction

ILD Hum. Res. need for const. in FTE
(total: 3200)



SiD Hum. Res.need for const. in FET
(total:2600)




- Both groups estimated the human power during the entire construction period (9 years) in FTE.
(only the sum for each component shown)
- They will be mostly paid by collaborating institutions around the world.

Total FTEs: **ILD 3200**, **SiD 2600**


The numbers include physicists, post-docs, engineers and technical personnel with about the same fraction, and a small number of administrative support.

Human resources for detector construction

ILD Hum. Res. need for const. in FTE
(total: 3200)



How good are these numbers?




- Both groups estimated the human power during the entire construction period (9 years) in FTE.
(only the sum for each component shown)
- They will be mostly paid by collaborating institutions around the world.

Total FTEs: **ILD 3200**, **SiD 2600**

The numbers include physicists, post-docs, engineers and technical personnel with about the same fraction, and a small number of administrative support.

People visiting/staying on site for construction and operation/maintenance



More people will be on site as time goes and peaks around 7th~8th year. Total sum peaks ~300 FTEs.

The Y10 level remains for operation and maintenance.

A considerable part of them will be working at the IP region.

(ILD: ~30~40%, SiD: 70~80%)




The level remains the same for operation/maintenance

The number of users on site

- There will be a big number of users from the time of commissioning through the physics run period.
- They start with a small number at Y1 but will reach in total (500~600)/year or more including physicists, post-docs and students.

Note: The numbers are
in FTEs.

(They will peak e.g. during
the collaboration meetings.)



Central campus


Draft proposal plan for discussion




Transportation in Kitakami

KITAKAMI Site: Transportation

Slide from Tokiko Onuki



We have to get permission from the authorities.



General rule

total weight	trailer/ track	our package	daytime	night	Xpwy	paper work
25 ton	~10 ton	~15 ton	YES	YES	YES	0
44 ton	~20 ton	~24 ton	YES [†] / NO	YES	NO	1
80 ton	~30 ton	~50 ton	NO	YES	NO	10

[†] Probably “YES”, if our package fits into a standard container (W=2,438mm).

20kW Cold Box

- L17.0m x W4.4m x H4.7m
- 80 ton
- #10



CAYON

IVECO

CONVOI
EXCEPTIONNEL

Linde

LHC Cold Box

2015/10/05



- Found solutions.
- New loads are to be built.



Transportation Status

- The current transportation rules in Japan are rather strict
- At this time we cannot assume that reinforcements of bridges and streets are possible
 - this might change, when the project gets approval
 - but even then there might be boundary conditions given by nature






News from the Interaction Point

IP area for vertical access


North

South



➔ more detailed survey

Vp



- Our budget is limited. Only one boring.
- Have to demonstrate that a detector cavern with a vertical shaft is possible in Kitakami.

Vp / electrical resistivity

sample @ Mt. Hayama

B




CH



CM




CL



“better than CL” ==>>>

“electrical resistivity > 1,000Ωm” & “Vp>~2,500m/s”


Vp



Slide from Tomo Sanuki

candidate IP, from the point of view of surface condition (topography, nearby roads, existing houses, land use, ...)

Vp



I bet on this site.

so far, so good

2015/10/05



Slide from Tomo Sanuki

【速報用コア写真(簡易版)】

孔名: H27-No. 1孔
掘削期間: 2015/9/17~2015/ /
掘進長: 140.00m


深度 m	コア写真	深度 m
20		21
21		22
22		23
23		24
24		25
25		26
26		27
27		28
28		29
29		30
30		31
31		32
32		33
33		34
34		35
35		36
36		37
37		38
38		39
39		40

コア写真 (H27-No. 1孔)


Buildings and Caverns





Underground Structure



Surface ground Buildings and facilities




Current Design of Detector Hall




- Main shaft locates IR position.
- DH length : 108m.
- Utility lines are in UT shaft
- Personnel entrance way is elevator installed in UT shaft
- Access tunnels connect at the both end of DH

Example Trailer locus




	Tractor Head	Trailer
Length	5.635m	13.240m
Width	2,500m	3,200m

Surface ground Buildings and facilities






Assembly Hall




Two Garages for each Detector
 Two Large Entrances for SiD
 Two Large Entrances for ILD
 All Large Entrances are at the same side

Outer space
 ILD: L67.0m x w27.0m
 SiD: L64.0m x w27.0m

Vertical section around Main shaft





Construction facilities Arrangements



Major construction facilities

items	Contents
Main shaft and DH construction facility	Cranes, Elevator, Hanging deck, Mucking equipment Ventilation fans
Utility shaft construction facility	Cranes, Elevator, Hanging deck, Mucking equipment Ventilation fans
Disposal Water Treatment Facility	Disposal water treatment Sedimentation reservoirs
Blasting powder preparation and storage chamber	Preparation and management chamber Storage chamber
Concrete mixing plant	Mixing plant Aggregates stock silos Disposal water treatment facility
Power supply facility	High voltage transformer Emergency generator
Offices	CM Office Contractors Office Subcontractors Offices
Construction yd.	Material stock yard Mucking yard

No.1 Preparation work






Notes

- Preparation work
- Assembly yard forming

Ground surface allocation according timeline



No.2 AsH, Shaft, A/T Construction



Notes

- Access tunnel excavation
- Main shaft construction
- Assembly hall 1 phase construction




No.3 Main Shaft, AsH P1 completion



Notes

- UT shaft construction
- Main shaft completion
- Access tunnel excavation
- Detector hall excavation
- Assembly Hall almost completion




No.4 Detector Assembling, DH construction



Notes

- UT shaft completion
- Detector hall construction
- Detector hall excavation
- Detectors assembling at AsH




No.5 DH Ex. Completion



Notes

- Detector hall completion
- Utility facility construction
- On ground Service building construction
- Detectors assembling at AsH




No.6 AsH Phase 2 completion



Notes




- Assembly hall 2nd phase construction
- Detectors assembling at AsH

No.7 DH platform completion



- Notes
- Assembly hall 2nd phase construction
 - Detectors assembling at AsH




No.8 Gantry Crane installation



Notes

- Assembly hall 2nd phase completion
- Gantry crane installation
- Detectors field mapping at AsH




No.9 SiD Detector Lowering



Notes
- SiD lowering




Ground surface allocation according timeline

No.10 ILD Detector Lowering



Notes
- ILD lowering

No.11 Assembling Completion




Notes

How to Assemble ILD in Kitakami?

Assumption

- New timeline for CFS
 - Ground breaking (GB) 4 years after project approval
 - AH becomes ready ~2.5 years after GB
 - DH becomes ready ~6.5 years after GB
- Magnetic field measurement on surface after ECAL installation
- TPC and silicon inner trackers are installed after lowering the detector to DH
- AH is used only for iron yoke assembly, solenoid assembly, and installation of ECAL, HCAL, solenoid, and muon detector
- Assembly hall has a 250t crane and an 80t crane for ILD
- Installation period of each sub-detector is based on TDR

Gantt chart




Simplified table

- Definition of T0 here is the beginning of the land development = Ground Breaking (consistent with CFS group)

2015/9/16	Y1				Y2				Y3				Y4				Y5				Y6				Y7				Y8				Y9				Y10			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4				
Land deve bp.																																								
AH	Phase-1																								-2															
DH	Civil construction																								Utility															
Yoke																	Assem bly on site																							
M uon																	Installation																							
Solenoid																	Assem bly on site								Ins.				FM											
Endcap HCAL																	Ins.																							
Endcap ECAL																	Ins.																							
Barre lHCAL																	Ins.																							
Barre lECAL																	Ins.																							
Tracker																	Ins.																							
Q D O																	Ins.																							
Com m issioning																	Ins.																							
Beam tuning																																								


Step 1

- Platform construction
- YB0 Yoke assembly
- Coil assembly preparation




Step 2

- YE+ Yoke assembly
- YB0 outer vacuum tank (OVT) assembly
- Coil assembly




Step 3

- YE- Yoke assembly
- YE+ Muon detector installation
- Inner vacuum tank (IVT),
Coil assembly




Step 4

- YE- Yoke assembly
- YB0 Muon detector installation
- YE+ Calorimeter installation
- IVT, Coil assembly




Step 5

- YB+ Yoke assembly
- YE- Muon detector installation
- YE+ Calorimeter cabling
- Coil, IVT installation




Step 6

- YB+ Yoke assembly
- YE- Calorimeter installation
- Coil, IVT installation




Step 7

- YB- Yoke assembly
- YB+ Muon detector installation
- YE- Calorimeter cabling
- YB0 Calorimeter installation




Step 8

- YB- Muon detector installation
- YB0 Calorimeter installation




Step 9

- YE-, YB-, YB0, YB+, YE+ shuffle the position



Step 10

- Close the detector
- Field mapping




Open questions

- Yoke
 - Size of yoke pre-assembly building: 20mx20m?
 - Capacity of the crane: 20t ?
- Muon detector
 - Location of module storage/test space: Central campus or IP campus? (Probably Central campus)
 - Size of the storage/test space (size for one sector (1/12) of a yoke ring would be enough)
- ECAL
 - Location of module storage/test space: Central campus or IP campus? (probably Central campus)
 - Reduction of the size (900m²) possible? (Endcap and barrel in series)
- SDHCAL
 - Location of module storage/test space: Central campus or IP campus? (probably IP campus)
 - Reduction of the size (1200m²) possible? (Endcap and barrel in series)
- AHCAL
 - Location of module storage/test space: Central campus or IP campus? (probably IP campus)

Proposal

- Fix space requirement for sub-detector assembly at IP campus
 - Iron yoke pre-assembly building (~400m²?)
 - HCAL assembly building (~600m²?)
 - (Control room and clean rooms for TPC and VTX/Si tracker can be located in the research office building)
 - If we can make agreement in this meeting, we would give the information to J-Power to update the IP campus design by LCWS2015
- Define ILD official timeline
 - Timeline on p15 as a starting point
 - Each sub-detector group can make “change request” to ILD technical coordination team

IP campus with 600m² HCAL-AH



What about the ILD subdetectors?
(selected examples)

AHCAL Assembly

Kitakami Side



or anywhere in any detector

AHCAL Assembly

solution: all needed AHCAL parts fit into here




**the container fits to standard transport systems
as ships, railways, trucks and through tunnels.....**

AUSSENMASSE		
Länge	mm	6058
	ft	19' 10 1/2"
Breite	mm	2438
	ft	8'
Höhe	mm	2591
	ft	8' 6"

GEWICHT		
Tara	kg	2700
	pd	5950
Max. Zuladung	kg	27780
	pd	61250
Max. Bruttogewicht	kg	30480
	pd	67200




AHCAL barrel integration tools



- lifting and turning tool for AHCAL barrel absorber submodules available
 - 2 x 18 t capacity
 - operation with 2 hooks (z angle adjustment)
 - precise motor controlled turning
 - design for adaptation for sub-modules with and without sensitive layers started
- mounting, support and insertion frame
 - insertion frame design ready
 - insertion frame support design depends on final yoke size and useable space
- push and pull tool available
 - must be modified to the rail distance and rail shape

AHCAL half barrel absorber installation step 1

Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay (



AHCAL assembly in ILD

experimental site requirements

- experimental site must be reachable by standard trucks with 20“ containers and a payload of 20 t under convenient conditions (moderate slopes and curves)
- the AHCAL test hall must be passable with trucks like above
- the AHCAL test hall must be equipped with 2 x 20 t gantry cranes
- the two crane hooks must reach a distance of 2,5 m between each other and a height of 6 m over ground
- the operational area of the cranes for the AHCAL must be 10 m (crane bridge) x 20 m
load area 4 x 8 m / AHCAL test area 6 x 8 m / AHCAL storage area 10 x 12 m
- the AHCAL test area must be air conditioned
- cooling water (16°C, 2 bar, 50 l/min) must be supplied to the AHCAL test area
- electrical power 4 x (3 phase x 400V / 50Hz, 32 A) must be supplied to the AHCAL test area
- workshop (5 m x 10 m with a height of 3,5 m) for sensitive layer repair directly at the AHCAL test area
- 4 offices with 20 m² directly at the AHCAL test area








Barrel integration : scenario A

Wheel Building in **Assembly Hall** : 8 modules x 5

Transport to Assembly Hall with normal truck - ILD area

- **Step 1** : Wheel structure transport (8 travels) & assembly
- **Step 2** : Modules transport 40 travels with 11 t
- **Step 3** : Modules assembly on the wheel structure with **100 t crane**
 - **8 modules in position on specific tool & screwing/welding**






Wheel assembly in Auxiliary building :

S

Building Method

- **Step 1 : Modules assembly to wheel**
 - 8 modules in position on specific tool
 - welding / screwing and rotation
- **Step 2 : Wheel on specific tool**
- **Step 3 : Special convoy to Assembly Hall**





Wheel assembly in Auxiliary building : 8 modules => 5 wheels

Building Method


• Step 1 : Modules assembly to wheel

- 8 modules in position on specific tool
- welding / screwing and rotation

• Step 2 : Wheel on specific tool

• Step 3 : GRPC insertion and connected

• Step 4 : **Special convoy to Assembly Hall with GRPC inside wheels – ready to be connected**



Back to Transportation

- Container vessel „MOL Comfort“, 8110 TEU, Mitsui O.S.K. Lines
- Line service LP1: Japan - Hong Kong - Singapore - Jeddah - Rotterdam - Hamburg - Southampton - Le Havre and back to Japan



„MOL Comfort“ 17.6.2013



- Indian Ocean between Singapore and Jeddah





„MOL Comfort“ Rear Part

- Salvage operation failed, sunk on June 27th.





„MOL Comfort“ Rear Part

- Salvage operation failed, sunk on June 27th.



„MOL Comfort“ Front Part



- Salvage operation failed, caught fire, sunk on July 11th





„MOL Comfort“ Front Part

- Salvage operation failed, caught fire, sunk on July 11th





„MOL Comfort“ Front Part

- Salvage operation failed, caught fire, sunk on July 11th

Why should we care?




„MOL Comfort“ Front Part

- Salvage operation failed, caught fire, sunk on July 11th



Why should we care?



A Toshiba klystron for the XFEL was on board of this ship....

Summary



- The planning for the layout and infrastructure at the Kitakami site is advancing
- Now is the time to provide input from ILD for this process
 - Area and space requirements
 - Infrastructure: power, cooling, computing, etc.
 - Special environments: clean rooms, etc.
- Need to understand better the dependencies on local conditions, e.g. transportation limits, on ILD assembly and maintenance philosophy
- We have a proposal for a central ILD installation plan
 - continue discussions and finalise a.s.a.p.
- Next integration/infrastructure meeting (besides Whistler)
 - March 2016 KEK
 - ECFA WS June 2016 Santander