

Mini-Workshop on ILC Infrastructure and CFS  
for Physics and Detectors Study  
Campus

2016.03.15

Tokiko Onuki/Tohoku University

## 1.Main Campus

- fundamental plan
- site location
- schedule
- facilities

## 2.IP campus

- schedule
- site volume and facilities

# ILC main campus- Fundamental Plan

Tohoku university is making the draft of campus fundamental plan in close communication with KEK .

## Fundamental concept

- Connect to the world
- Open to the public
- Consider rich natural environment
- Good transportation system for ILC and public
- Safety and security campus

## Fundamental Plan

- environmental plan
- opened campus plan
- zoning and facility plan
- welfare facilities plan
- housing plan
- transportation plan
- infrastructure plan

# ILC main campus- location requirement

## KEK report Study of the ILC Project Infrastructure Design Guidelines

(February 2014)

- Within 30-40minutes from existing urban area and IP(p. II -4)

## the ILC candidate site evaluation in Japan

- within 30km from IP(p.164)
- about 50ha in one place at the first stage, and 50ha as future expansion within 15km from the first stage area (total 100ha)(p.164)
- accessibility between the main transportation hub, rich public transportation system(p.165)

## for Kitakami site

- strongly recommend a location near the Shinkansen station which is superior in a study, living environment by having accessibility to Sendai, Tokyo(p.344)

→Considering these requirements, the Kitakami site starts to identify a final candidate site of main campus.

# ILC main campus

necessary to do these to make the main campus (also IP campus)

## ■legal procedures

- Urban Planning
  - development permission(by local city)  $\geq 1$  ha
- Agricultural Land Act
- Forest Act, ...

## ■environmental assessment (Iwate prefecture)

- necessary for the land development project  $\geq 50$ ha

## ■site acquisition arrangement

## ■site development

- basic & detail design
- site development

## ■building construction


- basic & detail design
- construction

mainly by the local area (outside of campus)

## ■surrounding infrastructure (water supply and drainage,electricity, ...)

- basic & detail design
- construction

# ILC main campus Schedule- case study



# ILC main campus-Schedule(Draft)

main critical point is environmental assessment.

	Pre Preparatory Phase		Preparatory Phase				Construction Phase											
	1	2	1	2	3	4	1	2	3	4	5	6	7	8	9	10	11	
<b>legal procedures</b>	<b>by local</b> Pre study		Consultation with local government															
<b>environmental assessment</b>	<b>by local</b> Pre survey		<b>5years→or shorter?</b> Research & Conservation Plan				Post-project survey (depends on the development)											
<b>site acquisition arrangement</b>	<b>by local</b> Land survey & arrangement																	
<b>site development</b> (includes infrastructure)	<b>by local&amp;ILC</b> Pre study		Basic & Detail design				Development(depends on the site condition)											
<b>building construction</b>	Pre study		Basic design															
	<b>by local&amp;ILC</b>																	
<b>surrounding infrastructure</b> (outside of campus)	Pre study		Basic & Detail design				Development(depends on the site condition)											
	<b>by local</b>		<b>by local</b>				<b>by local</b>											

**start from the usable place**  
staged Construction(depends on site development)  
★the first building will be completed (depends on the volume & function)

※all include the contract procedure

# ILC main campus-facilities(Draft)

based on the KEK report Study of the ILC Project Infrastructure Design Guidelines (February 2014)

Until the end of construction phase, those facilities will be constructed.

(also in the operation phase, the construction will be continuing.)

## ■Office

Office for researcher : rooms for 1,200people (7~20m<sup>2</sup>/person) → 1,600people

Office for technical staff : rooms for 350people (7~10m<sup>2</sup>/person)

Office for management staff : rooms for 150people (7m<sup>2</sup>/person)

+multipurpose space(for temporary office, meeting space,···)

## ■Conference facilities

Lecture hall (large) : 500seats

Lecture hall (small) : 200seats

Meeting room (Large) : 100seats×2room → 100seats×3room

Meeting room (small) : 50seats×4room → 50seats×6room

## ■Experimental facilities

Assembly hall : 25,000m<sup>2</sup> (3buildings)

Common Experimental facilities : 5,000m<sup>2</sup> (workshop, low-temperature experiment, Radiation experiment,···)

Control center : 3,000m<sup>2</sup>(including computer room 1,000m<sup>2</sup>)

Finally



# ILC main campus facilities(Draft)

based on the KEK report Study of the ILC Project Infrastructure Design Guidelines (February 2014)

Until the end of construction phase, those facilities will be constructed.

(also in the operation phase, the construction will be continuing.)

## ■Service facilities

Information & exhibition: 250m<sup>2</sup> (reception(half size of CERN))

→1,150m<sup>2</sup>(+Visitor center & exhibition space, library)

Welfare facilities : 1,900m<sup>2</sup>(cafeteria, nursery)→2,500m<sup>2</sup>(+dispensary, recreation space)

Life support : 1,500m<sup>2</sup>(User's office, Bank, Post office, travel agency, convenience store,···)

## ■Accommodation

Apartment type : 40m<sup>2</sup>×300room→450rooms

Townhouse type : 100m<sup>2</sup>×50room→75rooms

→need to think more considering the off campus housing


# ILC main campus facilities(Draft)

## ■Accommodation


Apartment type :  $40\text{m}^2 \times 300\text{room} \rightarrow 450\text{rooms}$

Townhouse type :  $100\text{m}^2 \times 50\text{room} \rightarrow 75\text{rooms}$

40m<sup>2</sup> sample








100m<sup>2</sup> sample



Basic hotel size: single room 15m<sup>2</sup>(10~20m<sup>2</sup>)    twin room 20m<sup>2</sup>(15~25m<sup>2</sup>)



CERN, DESY : mainly for short term and single stay

KEK : for short and long term stay OIST : mainly for long term stay

	CERN	DESY	KEK	OIST
Photo				
Rooms	<p>Myrin site : 3 hotel                      single 338room 27-58CHF/night · person                      twin 56room 38.5-64CHF/night · person                      shared room 52room 14CHF/night · person  <b>total 446room</b></p>	<p>3guesthouse  <b>170room 197bed</b></p>	<p>single(without bath) 13-14 m<sup>2</sup>                      133room ¥1,500/night · person                      single(with bath) 15 m<sup>2</sup>                      32room ¥2,000/night · person                      for couple(1LDK) 45 m<sup>2</sup>                      24room ¥40,700~49,600/month                      for family(2LDK) 88 m<sup>2</sup>                      6room ¥62,800/month  <b>total 195 room</b></p>	<p>Seaside house : twin 22room                      Hillside/Seaside faculty house                      2LDK 30house                      Campus village apartment                      1LDK(45 m<sup>2</sup>) 39room, 2LDK(70 m<sup>2</sup>) 33room                      West court                      2LDK(70 m<sup>2</sup>) 12room, 3LDK(85 m<sup>2</sup>) 8room,                      4LDK(105 m<sup>2</sup>) 16room                      Southhill : 1LDK 24room                      Eastcourt : 47room  <b>total 231room</b></p>
note	<ul style="list-style-type: none"> <li>· desk, bed, toilet, shower in each room</li> <li>· shared kitchen(cockware, tableware, refrigerator), TV rounge, laundry, nursing room</li> <li>· rental service (hair dryer, adapter), amenity kit sales (toothbrush, soap, etc)</li> <li>· FreeWi-fi, Free shuttle service to airport, parking</li> <li>· keep 151rooms at Saint Genis hostel at outside of campus</li> </ul>	<ul style="list-style-type: none"> <li>· the average occupancy rate is more than 50%. In the conference season, the occupancy rate becomes the higher.</li> <li>· cleaning : outsourcing</li> <li>· management/reservation : DESY</li> <li>· locate near main gate</li> </ul>		<p>Option(extra charge)</p> <ul style="list-style-type: none"> <li>· room cleaning</li> <li>· linen change</li> <li>· construction by PPP</li> </ul>
				

# ILC main campus layout model (KEK report)

## Low-rise case




# ILC main campus layout model(Draft)

- 1.Office
- 2.Conference
- 3.Service
- 4.Experimental
- 5.housing
- 6.Transportation
- 7.supply and disposal services
- 8.buffer green/ open space


To Shinkansen Station

City Center



Public/Semi-Public zone

≡Town



make the face of campus to the access road by Public zone


Of course, it depends on the landshape

# ILC main campus layout model(Draft)-Variation


- 1.Office
- 2.Conference
- 3.Service
- 4.Experimental
- 5.housing
- 6.Transportation
- 7.supply and disposal services
- 8.buffer green/ open space

To Shinkansen Station

City Center



make the face of campus to the access road by Public zone



Of course, it depends on the landshape

## 1.Main Campus

- fundamental plan
- site location
- schedule
- facilities

## 2.IP campus

- schedule
- site volume and facilities

# IP campus schedule(draft)

	Pre Preparatory Phase		Preparatory Phase				Construction Phase										
	1	2	1	2	3	4	1	2	3	4	5	6	7	8	9	10	11
<b>legal procedures</b>	by local Pre study Urban Planning(development permission), Agricultural Land Act, Forest Act...																
<b>environmental assessment</b>	by local Pre survey		4years Research & Conservation Plan				there is some possibility to cut environmental assessment Post-project survey (depends on the development)										
<b>site acquisition arrangement</b>	by local Land survey & arrangement																
<b>site development</b>	by local Pre study		Basic & Detail design				Development(depends on the site condition)										
<b>building construction</b>	Pre study		Basic design				Detail design		start from the usable place Construction A.H(23month)★experimental group work will start								
<b>surrounding infrastructure</b> (outside of campus) by local	Pre study		Basic & Detail design				Development(depends on the site condition)										

※all include the contract procedure    ※A.H. schedule is from change request NO.ILC-CR-000R




# IP campus requirements-ILD

IP campus requirements from the slide presented at the ILD topical integration meeting held at LAL in the last October.

sub detector	room	area(m <sup>2</sup> )			
Yoke	Strage	1300	250t crane		
	<b>subtotal</b>	<b>1300</b>			
AHCAL  either AHCAL or DHCAL	load area	32	2 x 20t crane	covering 10m x 20m	air conditioner
	test area	48			cooling water (16deg., sbar, 50L/min)
	strage area	120			4x (3phase 400V 32A)
					workshop 5x10m direct connection with test area 50
					office 20m2 x4 80
<b>subtotal</b>	<b>200</b>				<b>130</b>
DHCAL	assembly, GRPC	1200			
	storage	200	250t crane		
	<b>subtotal</b>	<b>1400</b>			
ECAL	barrel	strage	160	15t crane	
		test	40		
		assembly	200		
		strage/test	120		
		<b>subtotal</b>	<b>520</b>		
	endca	strage	80		
		test	50		
		assembly	180		
		<b>subtotal</b>	<b>310</b>		
TPC		100			clean room
	<b>subtotal</b>	<b>100</b>			
VTX/FTD		?			
<b>total</b>		<b>3830</b>	<b>+VTX/FTD+130=3960+VTX/FTD</b>		

※+ restspace, WC, etc

# IP campus requirements-ILD



※+ restspace, WC, etc

## + necessary information

- facility requirements - SiD, addition of ILD, facilities for collider (cooling tower,···)
- critical size (width×depth×height)
- layout (gather & share the same function, each connection)
- other necessary equipments
- site volume (considering future expansion)→at least, 70,000m<sup>2</sup> ?
- schedule (when do you need these facilities?)


# IP campus 4,000m<sup>2</sup> for ILD on the draft plan of Apr. 20 2015



LINEAR COLLIDER COLLABORATION  
Designing the world's next great particle accelerator

## Outline of the ground facilities

### Facility Arrangement on the above ground in Operation Phase



2015/4/20

ALCW2015 @K


11

# IP campus requirements-ILD sort by function

	strage	test area	load area	assembly	clean room	workshop	office	total
Yoke	1,300							1,300
AHCAL	120	48	32			50	80	330
DHCAL	200			1,200				1,400
ECAL: barrel	160	40		200				520
	120 (strage/test)							
ECAL: endcap	80	50		180				310
TPC					100			100
VTX/FTD								?
total	1,980	138	32	1,580	100	50	80	3,960+?

# IP campus requirements-ILD sort by function

possible to gather & share?



※+ restspace, WC, etc

# summary

## 1.main campus

- decision of site location
- check the necessary function, volume...
- adjustment of development schedule  
and coping with the early phase (collaborate with local area)  
(in the draft schedule, the first building will run from the 5th year of construction phase)

## 2.IP campus

- adjustment of development schedule  
and coping with the early phase (collaborate with local area)  
(in the draft schedule, A.H. will run from the 5th year of construction phase)
- check the necessary function, volume...
- based on the facilities volume, decide the site volume and location

# summary

No campus “candidate” site, without your requirements.

Please give us your request.

Kitakami will answer with full efforts.