

# **Measurement of Nanometer Electron Beam Sizes with Laser Interference using IPBSM**

**LCWS12  
Joint CLIC/ILC Working Group  
Instrumentation and Technical Systems**

Oct 25, 2012  
Arlington, Texas

**Jacqueline Yan, M.Oroku, Y. Yamaguchi, S. Komamiya**  
(The University of Tokyo, Graduate School of Science)

T. Yamanaka, Y. Kamiya, T. Suehara,  
(The University of Tokyo, ICEPP)

T. Okugi, T. Terunuma, T. Tauchi, S. Araki, J. Urakawa (KEK)




# Role of IPBSM (Shintake Monitor) at ATF2

ATF2: Linear Collider FFS test facility@KEK

$$L = \frac{n_b N^2 f_{rep}}{4\pi\sigma_x\sigma_y} H_D$$

For high luminosity  
must focus  
vertical beam size at IP !!  
flat beam :  $\sigma_y \ll \sigma_x$



ATF: 1.28 GeV LINAC , DR  
→high quality e- beam with extremely small normalized vertical emittance  $\gamma\varepsilon_y$

ATF2 Goal 1 :  
focus  $\sigma_y^*$  to design size 37 nm  
→verify Local Chromaticity Correction

ATF2 Goal 2:  
O(nm) beam trajectory stabilization

## OUTLINE

measurement scheme, performance, beam tuning roles

Beam Time results  
2011~2012

upgrades


Summary & Goals

# Measurement Scheme

use laser interference fringes as target for e- beam


Only device able to measure  $\sigma_y < 100 \text{ nm} !!$

- Crucial for beam tuning  
→ realization of future linear colliders



Split into upper/lower paths

→ phase scan by piezo stage




Detector measures  
signal **Modulation Depth "M"**

$$M = \frac{N_+ - N_-}{N_+ + N_-} = |\cos(\theta) \exp(-2(k_y \sigma_y)^2)|$$


$$\Rightarrow \sigma_y = \frac{d}{2\pi} \sqrt{2 \ln \left( \frac{|\cos(\theta)|}{M} \right)}$$

measurable range  
determined by **fringe pitch**




$$d = \frac{\pi}{k_y} = \frac{\lambda}{2 \sin(\theta/2)}$$



depend on  
crossing angle  $\theta$  (and  $\lambda$ )



N: no. of Compton photons  
Convolution between e- beam profile and fringe intensity



Crossing angle $\theta$	174°	30°	8°	2°
Fringe pitch	266 nm	1.03 μm	3.81 μm	15.2 μm
$d = \frac{\pi}{k_y} = \frac{\lambda}{2 \sin(\theta/2)}$				
Lower limit	20 nm	80 nm	350 nm	1.2 μm
Upper limit	110 nm	400 nm	1.4 μm	6 μm

## Expected Performance

$37 \pm 2 \text{ (stat.) } {}^{-0}_{+4} \text{ (syst.) nm}$

### Measures



$\sigma_y^* = 20 \text{ nm } \sim \text{few } \mu\text{m}$   
with < 10% resolution

$$\sigma_y = \frac{d}{2\pi} \sqrt{2 \ln \left( \frac{|\cos(\theta)|}{M} \right)}$$

$\sigma_y^*$  and M for each  $\theta$  mode

must select appropriate mode  
according to beam focusing


Resolution for each  $\theta$  mode



# Laser Optics

## Laser table

- Source (SHG)
- diagnostic devices



## Vertical table


## Interferometer

- Phase control  
→ piezo stage
- construct path for each  $\theta$  mode  
(auto-stage + mirror actuators )

Nd :YAG  
Q-Switch laser

PRO350  
Spectra Physics

Wavelength	532 nm (SHG)
Pulse Energy	1.4 J
Peak power	164 MW
Pulse Width	8 ns (FWHM)
$f_{rep}$	6.25 Hz
Line Width	< 0.003 cm <sup>-1</sup>
Timing Stability	< 0.5 ns
Energy Stability	$\pm 3\%$




# Role of IPBSM in Beam Tuning

1 path construction: access to IP, confirm precision with “ eyes & hands”

switch e- beam ON → remote control


2 Timing alignment

Timing scan of laser Q-SW and e- beam  
→ matched with precise TD2



3 Preliminary position alignment


Overlap laser and e- beam spots on screen monitor  
(within  $\sim 20 \mu\text{m}$ )



extremely precise position alignment

4 transverse : detect Compton peak

laser wire scan




6 After all preparations .....

continuously measure  $\sigma_y^*$  using interference mode  
→ Feed back to beam tuning

5 Longitudinal :

z scan




# post-earthquake recovery and upgrade in 2011

- overall stabilization of laser optics
- suppress signal jitters

## Beam Time (autumn~)


$\sigma_y^*$  focused down to  $\sim 1 \mu\text{m}$   
(beam tuning issues)  
IPBSM resolution improved  
(2 – 8 deg mode )



**Large jitters**  
 $\sim 30\%$

**Hardware  
upgrade**

**much smaller jitters**  
**clear contrast**



## overcome signal jitter sources (example)

### Beam size jitter

high response , effective  
status monitors  
& scan software  
introduced to ATF2


→ monitor instability factors  
on beam/laser profile

**fast M detection → scan under stable conditions**

extra bremsstrahlung at post-IP dipole

### High BG

intermediate  
collimator  
installed



# Beam time status in 2012


full commissioning  
of 30° mode

First Modulation detection

(10 x  $\beta_x^*$ , 10 x  $\beta_y^*$  optics)

stably measure  $\sigma_y^* \sim 160 \text{ nm}$

(10 x  $\beta_x^*$ , 3 x  $\beta_y^*$  optics)



## 2 - 8 ° mode

Measured larger  $\sigma_y$  ( $\sim$ few 100 nm )  
with clear contrast  
(i.e. high M : 0.8 – 0.9)

- ➔ Syst error study
- ✓ upper limit on M\_meas
- ✓ consistency of  $\sigma_y$ \_meas

## Began commissioning of 174 ° mode

- hardware check
- Optimization of scan strategies

Obstacles (2012 Feb)

- Beam condition drift (over many hours)
- Not very focused  $\sigma_y^*$  (still at 3 x  $\beta_y^*$  optics)

one more step before full commissioning of  
174 ° mode i.e. consistent fringe scans

# Systematic Error Study


Interpretation of  
M under-evaluation /  $\sigma y^*$  over-evaluation)

## Modulation Reduction Factor

$$M_{meas} = C_1 C_2 \dots M_{ideal} = \left( \prod_i C_i \right) M_{ideal}$$

$$\sigma_{y,ideal}^2 + \frac{1}{2k_y^2} \left| \sum \ln C_i \right|$$

degraded fringe contrast due to bias



Example of syst error evaluation  
(June, 2012 ,4 deg mode )

major  
bias  
factors

Laser profile imbalance

compare Compton signal  
of upper / lower path laser wire scans

Fringe tilt

limited by alignment precision

Phase jitter (relative position)

$C_{phase} > 95\%$

Laser path alignment

Ct,pos : ~ 100%, Cz,pos : > 99.5%

M reduction  
“worst limit”

polarization

> 98% adjusted to nearly pure S state

From actual data:

upper limit on M (= “fringe contrast”)

Ctotal = 0.8 – 0.9

## Improve through 2012 summer upgrade

### Profile Imbalance



- ✓ peak power
- ✓ IP spot size  $\sigma_{\text{laser}}$

◆ partially: optical components related loss  
 (transmission, reflection, delay line)  
 total  $P_t = 0.88$  )

2 times difference in  
 laser-wire  
 Compton signals ( $N_{\text{av}} = 20$ )

$$M' = CM = \frac{2\sqrt{P_t}}{1+P_t} M$$

$$P_t \equiv P_U / P_D$$




### Fringe Tilt

fringe not formed  
 perpendicular  
 to e- beam axis

→ improve alignment precision  
 on final focus lens before IP


observable limit:  $\Delta = 3 - 5$  mm  
 ↔ tilt  $\delta\phi_{t,z}$  : 5 - 20 mrad




# Syst. Errors specific to very small $\sigma_y^*$ (174 deg mode)

## Spherical wavefronts


Offset of ultra-focused e- beam vs laser waist → distorted fringes  
 $C_{\text{sphere}} > 99.7 \%$




Solution is **focal point scan**



attach mover to lens  
→ align focal point to IP within  $< 100 \mu\text{m}$   
( $\sim 0.1^*\text{Rayleigh length } Z_R$ )



## Change of $\sigma_y^*$ within fringes




due to strong focusing,  
 $C_{\text{growth}} \sim 99.7\%$

Tiny  $\sigma_y^*$  is very sensitive to relative position jitter !!!

**IPBPM** (O(nm) design resolution)  
under commissioning

- beam pos. monitoring
- feedback correction



# Stabilization of laser system



transport line  
→ insulation,  
anti-vibration

Insulated mirror box



## long term path stabilization

Beamlok (piezo feedback)  
added to laser cavity

Improved pointing stability  
 $< \pm 50 \mu\text{rad} \rightarrow < \pm 25 \mu\text{rad}$

## improve oscillation, profile




Tuning / exchange of  
cavity mirrors, seeder, flash-lamp



*SUPPRESS SIGNAL JITTERS*

Transport line

regular monitor / analyze  
temperature sensors



*CLEANER ENVIRONMENT...*

protective booth  
@ IP vertical table

Maintain dust-free  
component surfaces

LCWS12, J.Yan



2012 summer: **major upgrade of laser optics**

Goal: **alignment precision & reproducibility**


- suppress syst. errors
- effective small  $\sigma_y^*$  tuning
- better conditions to accomplish goals in autumn beam run

**BEAM TIME GOAL:**


- ◆ Full commissioning of 174° mode
  - stably measure  $\sigma_y^* < 100$  nm
  - focus down to  $\sigma_y^* \sim 37$  nm

improvements	details
<b>easier alignment</b> match focal point to IP Injection position / angle into lens	<ul style="list-style-type: none"><li>• focal point scan for all modes</li><li>• redefine clear reference lines on new base plates</li></ul>
<b>consistency , reproducibility</b> esp. before / after mode switching	<ul style="list-style-type: none"><li>• <b>new <math>\theta</math> switching method</b> <b>{small linear stage + mirror actuators }</b> independent for each mode (instead of shared rotating stages)</li><li>• re-commission <b>PSD system</b> → monitor jitters / drifts</li></ul>
<b>profile imbalance</b> focal point difference between upper/lower paths	<ul style="list-style-type: none"><li>• suppress path length difference in new design</li></ul>


**Small linear stage  
+ mirror actuator**




just after injection onto vertical table



**Confirm fine alignment using  
CW laser and transparent IP target**



inside IP chamber  
→laser waist & crossing point



CW laser spot


LCWS12, J.Yan

## Schedule:

assembling of new setup completed by end of September

- ❖ Beam off tests , (re)commissioning hardware: PSDs, phase monitor, profilers, DAQ modules
- ❖ Autumn beam run (10/15~): *already detected Compton signal during first week!!*  
many improvements to be verified from here on


### Tests of PSDs (+ preamps, readout circuit)



LCWS12, J.Yan



CCD camera  
as  
profile monitor



# SUMMARY

**IPBSM (“Shintake Monitor”)** installed at ATF2 IP

- use laser interference fringes  
→ only device capable of measuring  $\sigma_y^* < 100 \text{ nm}$
- Crucial for beam tuning → realization of future linear colliders

< Status >

- ❖ Stable measurements of  $\sigma_y^* \sim 160 \text{ nm}$  (30° mode)
- ❖ dedicated systematic error study (2 – 8 °mode)


<upgrades>


- suppress jitters & bias factors
- stabilize laser system
- reliability & reproducibility in laser optics alignment


< Goals for 2012 autumn beam run>



- ◆ full commissioning of 174 ° mode
- ◆ stable measurement of  $\sigma_y^* < 100 \text{ nm}$   
→ achieve focusing down to  $\sigma_y^* \sim 37 \text{ nm}$

# BACKUP










# New 174 mode







Table 3: Upper limits of each M reduction factor predicted for measuring the design  $\sigma_y^* = 37$  nm at ATF2. Assumed here are nominal laser and ATF2 beam parameters, as well as implementation of specific correction functions for the sensitive 174 deg mode used in this case[6].

<b>Modulation reduction factor</b>	<b>37 nm at 174 deg</b>
Total power imbalance	> 99.8 %
Relative position jitter	> 98.0 %
Fringe tilt	> 97.2% (tilt < 1 mrad)
Alignment (t, z)	(> 99.6%, > 99.1 %)
Spatial coherence	> 99.9%
Spherical wavefronts	> 99.7%
Beam size growth within fringe	> 99.7%

Table 4: Upper limits of dominant M reduction factors for measuring  $\sigma_y^* \sim 500$  nm at 4 deg mode, estimated using data from June, 2012

<b>Modulation reduction factor</b>	<b>O(500) nm at 4 deg</b>
Profile imbalance (t, z)	(> 94%, > 89 %)
Relative position jitter	> 95 %
fringe tilt (t, z)	> 95% (tilt < 20 mrad)
Alignment (t, z)	(> 95%, > 99 %)
Polarization	> 98%

# laser path misalignment

## 1 . Laser profile imbalance

misalignment of final lens focal point  
divergence angle affected by reducer setup

In past:

replaced damaged optical components  
optimized lens / reducer setup, alignment methods

## 2. Laser position offset from IP (beam center)



→ not a concern,  
mirror actuators finely adjust  
to 1/10 of  $\sigma_{\text{laser}}$

long. : Cz- pos > 99.5 %  
transv : Ct-pos ~ 100%

# Polarization related errors

## → imbalance in intensity/ profile

→ half mirror R = 50% only for pure S state  
elliptical components (P contamination)



adjust to S state  
by rotating  $\lambda/2$  wave plate

• measured in past :  
half mirror properties,  
eccentricity Es : Ep = 1: 0.13

→  $C_{\text{pol}} = 97.8 \pm 12.8 \cdot \tan\theta \pm 0.1\%$   
(2-8, 30 deg)

$C_{\text{pol}} = 97.2 \pm 1.3 \cdot \tan\theta \pm 0.1\%$   
(174 deg)

for now assume  $C_{\text{pol}} \sim 98\%$

Figure 4.7: [Left] The optical delay system for controlling fringe phase. [right] The piezoelectric stage

# 顕著な系統誤差

(2012連続ランより)

夏の光学系アップグレードで系統誤差を改善

## Profile Imbalance

- ✓ Compton peak power の違い:  $C_{\text{pow}} \sim 98\%$
- ✓ IP spot size  $\sigma_{\text{laser}}$  の違い:  $C_{\text{pro}} \sim 90 - 95\%$

◆一部は光学素子由来のロス  
(反射・透過率、光路長差ect...)  
total  $P_l = 0.88 \leftrightarrow C = 99.8\%$

◆lensのalignment精度  
(→ 焦点位置のばらつき)

実laserwire  
scan

$$M' = CM = \frac{2\sqrt{P_l}}{1+P_l} M$$

$$P_l = P_U / P_D$$



上パス

下パス

上図 ) 2倍の信号量の差

## Fringe Tilt

干渉縞がbeam軸に垂直でない場合





見積もり方:  
収束レンズ中心からの  
相対的オフセット  $\Delta t, z$

光路精度  $\Delta < 3 \text{ mm}$


→ 傾き:  $\delta\phi_t < 10 \text{ mrad}$   
 $\delta\phi_z < 5 \text{ mrad}$

$C_{t\text{-tilt}} > 95.3\%$   
 $C_{z\text{-tilt}} > 99.8\%$




$$\tan \Delta\phi = \Delta x / 2f \sin\theta/2$$


*Transverse plane*




○ mod



**Very narrow optimum setting**



**Beam profile of lower path**



# Current status of laser system

## Stat errors


relative timing	Stabilized by timing scans TDC, TD2 modules	Laser timing	1 - 3 %
Intensity	<ul style="list-style-type: none"> <li>• Stability ~ 1%</li> <li>• optics damaged by high intensity laser in March</li> <li>• Safe at ~ 40% power for now</li> </ul>	Laser intensity	1.5%
Oscillation	<p>currently stable</p> <ul style="list-style-type: none"> <li>• exchanged flash lamps and seeder</li> <li>• cavity mirror tuning</li> </ul>	Beam intensity jitters	ICT monitor resolution: 2-5% (Measured energy is normalized by ICT)
profile	<p>Triangular (non-Gaussian) profile at IP dark spots</p> <p>→ Improved by rear mirror tuning</p>	Laser pointing stability	10 ~ 15%
Major upgrades in laser optics	<ul style="list-style-type: none"> <li>• Beamlok</li> <li>• new laser table box</li> <li>• additional mirror for precise injection onto vertical table</li> <li>• changed reducer and expander lens (AR coating , magnification)</li> </ul>	Beam position jitters	unknown

$M^2$  : 0.5 – 3.0

near field to few times of rayleigh length

- Assume injected size of  $\omega = 4.5$  mm,
- fix focal point to 5.6 mm (lens mover position)

### beam focusing dependence on $M^2$



#### 4 consistent measurements at 4 deg mode :

including long range fine scan (60 rad, Nav = 10)

**M = 0.887 ± 0.005** (stat only)       **$\sigma_y = 589 \pm 13 \text{ nm}$**


init. phase: **-2.162 ± 0.009 rad**

*phase drift ~ 18 mrad (~ 0.8 % only)*

Rotation Control | TD2 FineDelay | LW28 | LW30 | LW174 | Fringe28 | Fringe30 | Fringe174 | Zscan28 | Zscan30 | Zscan174 | 2-8 |

#### Fringe Scan 2-8 degrees

Graph



#### Phase Scan Range

Min: 1.00 Max: 60.00 Step: 0.60 Nread: 10

Origin Phase Position: 1.2609

Current Phase Position: 1.23711

Intensity Cut [e9]: 2.000 < 1 < 10.000

Fit Mode: layer 1-4 3.637

Start


Stop

Collision Angle: 4.00907

Filename: /atf/data/ipbsm/interfere/meas120614\_231021.c



FileSelect

Recalculation




Modulation	0.885	+/-	0.006
Beam Size	593.1	+/-	15.5 nm
Average	1473.501	+/-	10.531
Phase	-2.167	+/-	0.010

optics for recent run	S/N	BG [GeV]	Sig. jitter
10x $\beta y^*$ (ex: 30 deg)	4	5	15 – 25%
3 x $\beta y^*$ (ex: 2- 8 deg)	1	15	
1 x $\beta y^*$ (ex: 174 deg)	0.5	20	BG のふらつき ~10 – 15 %





# ガンマ線検出器

カロリーメータ型CsI(Tl)シンチレータ



ATF2 で signal と BG エネルギースペクトル  
が大きく違うことを活用




多層構造


前4層 (10 mm x 4) + 後ろの "bulk" (290 mm)

高いシグナル・BG分離能


各層でのシャワー発展を測定  
→ 参照シャワーで fitting



<b>BeamLok Specifications</b>	<b>Standard Pro Series</b>	<b>With BeamLok/D-Lok</b>
Beam Pointing Stability <sup>12</sup>	<±50 µrad	<±25 µrad
Beam Divergence <sup>13</sup>	<0.5 mrad	<2 x initial level
Lamp Lifetimes <sup>14</sup>	30 million pulses	40 million pulses
<b>Linewidth</b>		
Standard		<1.0 cm <sup>-1</sup>
Injection Seeded <sup>15</sup>		<0.003 cm <sup>-1</sup>
Timing Jitter <sup>16</sup>		<0.5 ns



# ATF



Linac: ピームエネルギー 1.3 GeV


Damping Ring: 鉛直エミッタンス  $11 \text{ pm} \cdot \text{rad}$



規格化鉛直エミッタンス  $30 \text{ nm} \cdot \text{rad}$

ILCでの規格化エミッタンス  $35 \text{ nm} \cdot \text{rad}$

# ATF2



Final Focus: 局所色収差補正に基づいた設計

- 37 nmの鉛直ビームサイズ → 新竹モニタで測定
- nmレベルのビーム安定化 100 nm以下のビームサイズ測定に実績

## FFTB vs ATF2



Table 2: Typical e- beam and IPBSM parameters: ATF2 vs FFTB[2, 4]

	FFTB	ATF2
Beam energy	46.6 GeV	1.28 GeV
1 photon energy	8.6 GeV	15 MeV
rep. rate	30 Hz	1.56 Hz (3 Hz)
e- / bunch	$1 \times 10^{10}$	$1 \times 10^{10}$
Bunch length	3 ps	16 ps
$(\sigma_x^*, \sigma_y^*)$ at IP	(900, 60) nm	(2200, 37) nm
Laser wavelength	1064 nm	532 nm (SHG)
Range for $\sigma_y^*$	40-720 nm	20 nm-6μm

