


# Construction the RPC Digital Hadron Calorimeter Physics Prototype

Lei Xia  
Argonne National Laboratory



CALICE collaboration meeting at UTA

# RPC DHCAL Collaboration



## Argonne

Carol Adams

Mike Anthony

Tim Cundiff

Eddie Davis

Pat De Lurgio

Gary Drake

Kurt Francis

Robert Furst

Vic Guarino

Bill Haberichter

Andrew Kreps

Zeljko Matijas

José Repond

Jim Schlereth

Frank Skrzecz

(Jacob Smith)

(Daniel Trojand)

Dave Underwood

Ken Wood

Lei Xia

Allen Zhao

## Boston University

John Butler

Eric Hazen

Shouxiang Wu

## Fermilab

Alan Baumbaugh

Lou Dal Monte

Jim Hoff

Scott Holm

Ray Yarema

## IHEP Beijing

Qingmin Zhang

## University of Iowa

Burak Bilki

Edwin Norbeck

David Northacker

Yasar Onel

## McGill University

François Corriveau

Daniel Trojand

## UTA

Jacob Smith

Jaehoon Yu



RED = Electronics Contributions  
GREEN = Mechanical Contributions  
BLUE = Students  
BLACK = Physicist

# 1 m<sup>3</sup> – Digital Hadron Calorimeter Physics Prototype

## Description

Readout of 1 x 1 cm<sup>2</sup> pads with one threshold (1-bit) → Digital Calorimeter

40 layers each ~ 1 x 1 m<sup>2</sup>

Each layer with 3 RPCs, each 32 x 96 cm<sup>2</sup>

~400,000 readout channels

Layers to be inserted into the existing CALICE Analog HCAL structure

## Purpose

Validate DHCAL concept

Gain experience running large RPC system

Measure hadronic showers in great detail

Validate hadronic shower models

## Status

Started construction in 2008 - 09



# RPC Construction

## RPC design

- 2 – glass RPCs
- 1 – glass RPCs (developed at Argonne)
- Gas gap size 1.1mm
- Total RPC thickness < 3.4mm
- Dead area ~5% (frame, spacer)



## Chambers needed

~120 + spares



## Material

Glass in hand for 300 chambers  
Kilometers worth of PVC frame extruded

## Assembly steps

- Spraying of glass plates with resistive paint
- Cutting of frame pieces
- Gluing frame
- Gluing 1<sup>st</sup> glass plate onto frame
- Put in fishing line
- Gluing 2<sup>nd</sup> glass plate onto frame
- Mounting of HV connection, etc.



# Spraying of the glass sheets

## Challenge

Produce a uniform layer with  $R_{\square} = 1 - 5 \text{ M}\Omega$   
(value only critical for thin plate, thick plate can be lower)



## New paint (artist paint) identified

- Reasonably cheap
- Non toxic
- 2 component mixture (BLACK and GREEN)
- Needs to be sprayed


## Production

Been struggling with spraying for a while

- Poor uniformity in a single plate
- Mean value not well controlled from plate to plate
- Low yield:  $\sim 60\%$  passes quality cut
- Slow: barely match RPC assembly speed





# Spraying setup



# Improving paint spraying

- **(almost) Exhaustively studied all spraying conditions**
  - Environmental temperature, humidity
  - Air brush pressure, flow rate, nozzle cleanliness
  - Paint ratio and quality
  - Horizontal slide speed
- **Improvement 1:** pneumatic slide → motor driven
  - Significantly improved uniformity
- **Improvement 2:** air brush → spray gun
  - Further improved uniformity
  - We believe that we are in control of the mean value now
  - Much faster spraying process
- We are close to claim: **problem solved**



# RPC Assembly


## Cutting frames

Dedicated (adjustable) cutting fixture  
Cut length to .2mm precision  
Drill holes




## Assembly

Dedicated gluing fixture  
Frame/gap glued to ~0.1mm precision  
Very time consuming process:  
~1 RPC/day/tech, 3 RPC produced/day



## Production


30+ final RPC completed or near complete  
Full speed production started





# Quality assurance

- Pressure test
  - Test at 0.3 inch of water pressure
  - Pass if pressure drop < 0.02 inch in 30sec
  - Chambers not passing in 1<sup>st</sup> test are repaired
  - All repaired chambers pass 2<sup>nd</sup> test so far
- Gap size measurement
  - Gap sizes of all chambers are measured along the edges
  - Gap sizes along all edges are controlled at ~0.1mm level (central region assured by spacers)
  - Corner regions are worse (but within 1-2 cm from corner)
    - Typical ~0.1mm thicker
    - A few corners are ~0.3 – 0.4mm thicker
    - Currently related to the way corners are glued
    - In the process of improving the procedure
- HV test
  - Chambers are tested with HV before put readout board on
- Chamber rejection: only 4 so far
  - 2: wrong glass sheet
  - 1: tubing arranged in wrong direction (typical learning process)
  - 1: gas inlet/outlet in wrong place, glass cracked

RPC 018



RPC 012





# Test of production RPC with new (full size) board

## Setup


Uses up to 7(4) small chambers from VST  
Currently 5(4) large chamber with 7(5) board  
Will increase to ~10 large chambers  
Will be used for RPC/FE board check out

## Data taking

First events on 9/11/2009  
Just finished prototype FE board tests  
Large cosmic/noise/Qinj data set



Geometrical Distribution of Noise with Large FEB







# Some electronic test results

- “Spark Tests”
  - One RPC has a ‘feature’ of sparking at a known voltage
  - Initially will send nearby FE boards to a funky state
  - Shielded data cable and improved grounding solved the problem
- Tested noise floor of new FE boards
  - Noise performance (significantly) better than VST boards
- Eliminated ALL data errors in system
  - NO data error ever observed in cosmic ray data
  - Eliminated a trivial DCOL firmware bug that creates check sum errors
  - Found 1 error mode in the last few weeks when push the system off the design limit (high rate)
  - Eliminated this error mode last week (firmware improvement)
  - Currently system run smoothly in ALL conditions (low threshold, high rate, sparks(?!))

# Some cosmic ray events: single track




Run 675:0 Event 219

Time: 363755  
Hits: 9 Energy: xxx mips



Run 675:0 Event 221

Time: 9998423  
Hits: 10 Energy: xxx mips







Cosmic ray data analysis in progress

# Some cosmic ray events: multiple tracks




Run 675:0 Event 395

Time: 6278234  
Hits: 48 Energy: xxx mips



Run 675:0 Event 620

Time: 9047623  
Hits: 77 Energy: xxx mips





Cosmic ray data analysis in progress

# Some cosmic ray events: air shower?





Run 675:0 Event 359

Time: 6048426  
Hits: 177 Energy: xxx mips



Run 675:0 Event 424

Time: 576399  
Hits: 162 Energy: xxx mips



Cosmic ray data analysis in progress

# Cosmic ray test stand

- **Current issue**
  - Uses scintillator trigger, only map out part of an RPC at a time
  - Low trigger rate ( $\sim 10/\text{min}$ )
  - Takes forever to map out entire RPC
- **Planned changes**
  - Remove VST and trigger counters
  - Expand to  $\sim 10$  large RPC's
  - Run in self-trigger (triggerless) mode
- **Challenges**
  - New event builder: rely entirely on timing information of hit packages (no help from trigger packages)
    - Find cosmic ray tracks out of RPC noise hits
    - Tried with VST, should not be a major challenge
  - Data size:  $\sim 10\text{GB}/\text{day}$ 
    - Need timely data processing, data storage
    - Throw away raw data, only keep built cosmic ray events?
  - Soft tracks?
- **Cassette test stand**
  - All finished cassettes will be put into a hanging structure for continuous test
  - Expect to run in self-trigger mode, utilize same event building/analysis
  - Qinj runs from time to time to test readout system

# Cassettes

## Purpose

Protect RPCs, cool front-end ASICs, compress RPCs/FE boards

## Design

2 x 2mm copper sheets + cooling tube on top  
Will fit into CALICE Analog HCAL structure  
Uses nylon strings to compress the two copper sheets

## Prototypes

First one built with all final dimensions  
Tested out with 3 RPCs and 6 FE boards  
Assembled again with 3 RPCs and 6 mock-up boards  
Tested in the CALICE Analog HCAL absorber structure




## Assembly

Not expected to be labor-intensive




# Cassette design: press two plates together

- It is important to keep positive pressure on the two metal plates of the cassette
  - Ensure good thermal contact with ASIC's
  - Ensure good contact between RPC and pad board
- Solution: use pre-tensioned nylon string
  - String go between the RPC's
- Tested several string candidates
  - Pre-tensioned to ~4 – 5 pounds
  - No significant drop over ~ 30 days





# FrontEnd/DCON board + Pad board



- Build FE and pad boards separately to avoid blind and buried vias (cost and feasibility issue)
- Glue the two boards together with conductive epoxy
- Tried out in VST: all glued by hand (~10 boards)
  - Failing rate < 1%
- Extrapolation to 1m<sup>3</sup> not trivial
  - VST: 256 glue dots/board → 1m<sup>3</sup>: 1536 glue dots/board

# Gluing fixture for Pad- and FE-boards

Initial Goal: 1536 glue dots in less than 3 hours

## Fixture

Designed, built and commissioned



## Practice

Glued 8 full size boards successfully

## Production

~55 minutes/board

can glue 6 - 8 boards/day



Controller

Solenoid valve

x axis motor and driver

y axis motor and driver

z slider

Glue Dispenser



# Peripherals

## Gas

Mixing rack – done

Distributing rack – almost done

Recently decided not to expand old rack

Parts for a new rack (partially) arrived

New rack assembly in progress



## Low Voltage

7 Wiener power supplies in hand


1<sup>st</sup> distribution box built and in use

being torture tested at full load (8 FE boards)

## High Voltage

Units in hand

Computer control programs commissioned



# Summary

## **RPC construction is progressing well**

Issues mostly resolved, production in full speed  
Quality assurance in place

## **Cosmic ray test stand ready for RPC/electronic tests**

Still working on self-trigger running (event building/analysis)

## **Cassette design proven, production start soon**

## **FE/pad boards gluing ready and tested**

## **HV, LV, gas systems are mostly ready**

# Physics prototype construction status

Task	Status	Comment
<b>RPC construction</b>	30% done	Much more tedious than anticipated
<b>Cassette construction</b>	Design complete 1 <sup>st</sup> prototype assembled Material on order	Costly, but not very labor intensive
<b>Front-end electronics</b>	Prototypes fully debugged Boards in fabrication	Pursued a very conservative approach
<b>Back-end electronics</b>	DCOL 100% done New TTM in fabrication	
<b>Low voltage</b>	Power supplies in hand 1 <sup>st</sup> distribution box assembled and tested Parts for all units on order	
<b>High voltage</b>	Units in hand Computer controlled program completed	
<b>Gas system</b>	Gas mixer completed and tested Decision to built 2 <sup>nd</sup> distribution rack Parts on order	
<b>DAQ software</b>	Implemented into CALICE framework 99% complete	
<b>Event builder and display</b>	Event building started Event display complete	
<b>Data analysis</b>	Started to reconstruct tracks in CR data	Lots of experience from VST
<b>Simulation</b>	RPC response simulated Implementation of DHCAL into MOKKA ongoing	

Gary's  
talk

Jacob's  
talk

# Physics prototype plans

Task	Dates	Comments
Construction	Complete by June 30 <sup>th</sup>	Should not slip much more...
Cosmic ray testing of cubic meter	April through August	
Installation into Mtest	Early September	
1 <sup>st</sup> data taking period	September - October	DHCAL standalone (with TCMT)
2 <sup>nd</sup> data taking period	December	Combined with ECAL
3 <sup>rd</sup> data taking period	Early in 2011	DHCAL standalone or combined
Disassembly and shipping of stage	March 2011	Hard deadline