

# FNAL SCRF Program Overview

Robert Kephart

---

- **Introduction**
- **R&D Goals and required infrastructure**
- **Why an generic SCRF R&D program vs ILC R&D or a DOE construction project?**
- **Organization and Financial Management**
- **FY06 Financials and technical achievement**
- **FY07 plan**
- **FY08 and beyond**
- **Conclusion**

- Superconducting Radio Frequency Technology (SCRF) has emerged as an important “enabling” accelerator technology
  - Think... “like SC magnets in 1980’s”
- Many existing SCRF based accelerators or under const.
  - ATLAS ( ANL)
  - CBEAF (TJNL)
  - SCRF cavities for LEP, KEK b factory, etc
  - SNS (ORNL)
  - TTFII/FLASH, XFEL ( DESY)
- Remarkable improvements in the achievable accelerating gradients ( $\sim 5 \rightarrow 35$  MV/M) over the last  $\sim$  decade or so
- → SCRF is the chosen technology for the **International Linear Collider**, the next new global High Energy Physics facility
- It is being considered for many other applications

- **The uses of SCRF go far beyond the ILC**
  - High Intensity Neutrino (ie proton) Sources (HINS)
  - Front end of neutrino factories or Muon Colliders
  - Spallation neutron sources ( e.g. like SNS)
  - Light Sources ( e.g. XFEL)
  - Energy Recovery Linacs
  - Rare Isotope Accelerators ( RIA)
  - Medical Accelerators
- **High Energy Physics has developed much of the accelerator technology used by Nuclear Physics & Basic Energy Sciences**
- **As the only National Laboratory (after 2009) dedicated to HEP, it is FNAL's natural role to be the steward of of SCRF technology**
- **If it wishes to be a viable host for ILC, FNAL should strive to become a leader in SCRF development**

- **Europe**
  - DESY/INFN developed world class SCRF expertise and infrastructure as it built the Tesla Test Facility in support of the TESLA proposal.
  - Infrastructure is being expanded to support the XFEL
  - Strong industrial vendors involved: ACCEL, Zannon in cavity fabrication; some in processing
  - Previous experience with LEP SCRF cavities at CERN
- **Japan**
  - Several decades of SCRF R&D at KEK ( Saito)
    - **New cavity shapes and processing techniques**
  - Experience with SCRF cavities for KEK B factory
  - Major effort to build STF facility (CM cold this year)
  - Strong working relationship with Industry

- **U.S.**
  - ATLAS machine at ANL
  - SCRF R&D at Cornell, MSU, ANL, TJNL, etc
  - CEBAF and SNS experience at TJNL
  - RIA R&D at ANL, MSU, TJNL
  - Most work done in labs and universities, no significant industrial participation prior to ILC.
- **FNAL**
  - Small SCRF program as part of TESLA collaboration for > 10 yrs
    - Built A0 FNPL photo-injector in parallel (twin of TTF I)
    - Supplied components to DESY (modulators, cryo parts)
    - Working to complete 3.9 GHz 3<sup>rd</sup> harmonic cavities for DESY
  - Until 2005 this was a small ~ \$1-2 M/yr program
  - Moreover, OHEP did not want FNAL to grow the SCRF effort at FNAL, largely because the U.S. was focused on the warm technology for ILC


- **FNAL and collaborators submitted the SMTF proposal in Feb 2005 to greatly expand U.S. SCRF infrastructure and capability**
  - Much of the infrastructure we are discussing today to support ILC and HINS was requested in that proposal
  - For complicated reasons SMTF was not funded...
    - Multiple offices in DOE, multiple projects, etc.
- **Change! Following August 2005 technology choice for the ILC**
  - FNAL began a major program to build its SCRF capability, infrastructure, and expertise
  - Even though SMTF was not approved, we were encouraged to use “GDE recommended” ILC funds and lab core funds to start building the necessary SCRF infrastructure.
- **Our rate of progress has been limited financially**
  - More on FY06 finances in a minute

- We are pursuing 4 SCRF activities in Parallel
- Plan A: ILC
  - Our goal is to Work with the international community to carry out the R&D necessary to demonstrate the machine is technically feasible and affordable
  - We also want to prepare FNAL as a strong host candidate for the machine. Command of SCRF technology is essential
- Plan B: HINS
  - If the ILC is delayed or sited elsewhere, build an intense SCRF based proton source for long baseline neutrino physics
  - Such a project could serve to build up industry for a delayed ILC
- Generic SCRF development:
  - Mostly 3.9 GHz work in progress as part of the TESLA Technology collaboration and Materials R&D collaboration
- AARD:
  - So far this has been largely the FNPL Photo-injector effort
  - FNAL wishes to increase activities on Accelerator R&D and this can be a natural extension of our ILC and HINS plans (more)



- A primary ILC R&D goal is to rapidly advance the intellectual understanding of SCRF surface physics and establish process controls to reliably achieve high gradient ( 35 MV/M) SCRF cavity operation needed for ILC (usually referred to as GDE S0 goal)
- Approach: Establish so called “tight loop” processing and test infrastructure
- Tight loop elements:
  - Cavity fabrication capability (U.S. vendors)
  - BCP & Electro-polish facilities
  - High purity water and High pressure rinse
  - Vertical test facilities
  - SCRF experts & materials program to interpret results
- SCRF materials program =FNAL,UW,NW,Cornell,TJNL,MSU, etc





Plan... Develop in labs then transfer technology to industry

- **This process requires extensive infrastructure**
- **Bare cavities**
  - Fabrication facilities (Industry: Electron beam welder, QC, etc)
  - Surface treatment facilities BCP & Electro-polish facilities (EP)
  - Ultra clean H<sub>2</sub>O & High Pressure Rinse systems
  - Vertical Test facilities (Cryogenics + low power RF)
- **Cavity Dressing Facilities (cryostat, tuner, coupler)**
  - Class 100 clean room
  - Horizontal cavity & Coupler test facilities (RF pulsed power)
- **String Assembly Facilities**
  - Large class 10/100 clean rooms, Large fixtures
- **Cryo-module test facilities**
  - Cryogenics, pulsed RF power, LLRF, controls, shielding, etc.
  - Beam tests → electron source (RF unit test facility at NML)
- **The focus of this review is to describe to you our plans to build this infrastructure and develop SCRF expertise at FNAL**


- Why NOT just an ILC R&D expense?
- Answer:
  - The ILC in many ways “sets the bar” for the needs
  - ILC funds are supporting some FNAL infrastructure construction and SCRF R&D.. but ILC is a global project.
  - The GDE has steered ILC R&D funds at the most pressing issues for the benefit of “project”.
    - → use existing U.S. SCRF institutions to get “quick” answers
    - Because FNAL does not have much SCRF infrastructure we are at a disadvantage to participate in this activity.
  - Known that existing SCRF facilities are inadequate for ILC R&D needs → new “generic” facilities with better process control and throughput are needed
  - The GDE does not have the responsibility for building generic SCRF capability at any laboratory or in any region
- This is the responsibility of the DOE.
- HINS or other U.S. SCRF projects will benefit from R&D aimed at high gradients and from this improved infrastructure

- It is important to recognize that SCRF efforts are funded from various sources
- ILC funding (ILC B&R... GDE recommends)
  - Funds actual machine design effort
  - ILC cavity fabrication, processing, CM parts, etc.
  - Only funds most crucial infrastructure
- HINS ( lab core funds)
- SCRF infrastructure ( lab core funds)
  - Funds the bulk of infrastructure
  - Funds efforts that are generic or that serve to “train” our staff... e.g. 3.9 GHz effort with DESY
  - Funds facility “operations” not paid for by ILC or HINS
- This review is focused on the last category...

- **Should the required SCRF infrastructure be built as a “construction project” in the DOE system ?**
  - **Answer No! We do not fully understand today the process steps to reliably produce high gradient cavities and CM**
  - **This is R&D! Can only partially specify the equipment and infrastructure that will be required.**
  - **Plans will evolve, so will the costs and milestones... they are dependent on the outcome of the R&D**
- **The framework of a DOE Project would waste lots of effort and not improve the outcome**
- **Of course it must be well planned and managed !**
- **We will present “next steps” and our best estimate of the associated costs and schedule for 2-3 yrs**

- For the next few years FNAL faces the difficult challenge of delivering on the existing program (especially Run II) while building the ILC effort
  - The lab also recognized that SCRF is an “enabling” technology that will be useful any of a variety of future projects in addition to ILC.
- We also recognize that success on the ILC requires the full resources of the laboratory
  - Technical, business, HR, FESS, etc.
  - Hence ILC is not organized as a project in a division
- In FY06 Pier chose to organize ILC and all SCRF efforts by creating an office in the Directorate
- Full budget authority, matrix management org

## FRA Organization





- **Deputies**
  - Shekhar Mishra
  - Sergei Nagaitsev
- **Resource Manager – Rich Stanek**
- **Leaders in the Divisions and Sections**
  - AD (Sergei Nagaitsev)
  - TD Marc Ross (as of Feb 1)
  - PPD Marcel DeMarteau
  - CD Steve Wolbers
  - FESS Vic Kuchler
- **Detailed organization chart exists**
  - Task Leaders responsible for deliverables
  - Workers may come from more than one Division
  - SWF in Division (labor agreement), M&S in Directorate
- **Evolving... eg new strong additions ( e.g. Marc Ross)**
- **Full WBS ( Project 18 in FNAL financial system)**
- **Technical and Financial tracking in place**

- **Full WBS breakdown of tasks**
  - **ILC Division Leaders organize efforts in each Division**
    - Task managers responsible for budget & technical progress
  - **SWF is assigned to Divisions for scope of work**
    - Essentially a scope of labor agreement
    - Guidance provided for FY 06, renegotiated as required
    - High level assignments made by Division Heads in consultation with ILC Director and Division leader
    - Mostly this worked fine, but a few cases where key personnel were reassigned without notice
    - This is new, so some task leaders not yet fully up to speed
  - **M&S and management reserve held in Directorate**
    - Division Leaders & Task leaders have signature authority
    - M&S in FY06 changed due to incremental funding by DOE
  - **Seven separate funding changes in FY06!**



- The ILC/SCRF effort was organized as a “Project 18” in the FNAL financial system
- 18.1 GDE directed activities
  - Deliverables and levels of effort specified in GDE MOU
  - All funding in ILC B&R category, we report on this
  - Contains all “ILC specific” work (accounting)
- • 18.2 FNAL directed infrastructure and R&D
  - Efforts are arguably more general (e.g. SCRF = enabling technology with other applications, advanced controls system development benefits other projects, detector develop, etc)
  - Informed GDE about what we are doing (endorsement)
- • 18.3 DESY collaborative 3.9 GHz effort
- 18.4 U.S. Bid to host ILC (small, mostly outreach)
- 18.5 ILC Americas (communicator support)
  
- Project 19: GDE Directors salary, office expense, travel
- **This reorganization took effect ~ Jan 06 (25% thru fiscal yr)**

- **Role of ILC Resource Manager (Rich Stanek)**
  - Interacts with Task Managers on budget and resource issues
  - Monitors ILC (GDE) vs. SCRF Infrastructure split to assure it is done correctly (Multiple funds transfers → Serious Issue!)
  - Oversees MOUs and financial transfers to outside institutions
  - Produces monthly financial reports (with Budget Office)
  - With Program Engineers (Harry Carter & Jerry Leibfritz)
    - Developing a resource loaded schedule & milestones
    - Produce GDE quarterly technical & financial reports
  - With input from task managers, produce summary cost estimates for FNAL SCRF program in future years

- The vision of the GDE is that the ILC R&D program be proposal driven, prioritized, and optimized across the globe
  - U.S. DOE has asked the GDE Americas Regional Team (ART) Director for R&D funding recommendations
  - Some influence in U.K... less in Europe and Japan
- In the U.S. in FY06 and FY07 U.S. labs and universities made proposals for ILC R&D efforts
- The ART Director (Dugan now, soon Harrison)
  - Received guidance from OHEP on available funding for U.S. ILC R&D (funds in the ILC B&R code)
  - GDE research board assigned relative priority to tasks
  - ART Director consulted with RDB and EC then recommended funding by work package to the DOE

- **FY06 national funding for ILC R&D was \$ 30 M**
  - GDE recommended ILC R&D funding to FNAL was \$ 13 m
  - Some of this funded the RDR work, but part funded cavity development and infrastructure of the highest priority to ILC
  - FNAL added \$ 19 M in core funds to develop generic SCRF capability & infrastructure ( includes ~\$3 M for DESY collaboration)
- **FNAL's total FY06 ILC/SCRF effort was \$ 32 M**
  - Numbers include salaries and overhead
- **In FY06 the FNAL workforce (ILC + SCRF) ramped from 60 FTE to 150 FTE by year end**
  - ie, a major increase in emphasis and effort
  - Rapidly evolving workforce and capability

- Total FNAL spending on ILC/SCRF in FY06 was \$ 25,545 K
  - Spending on just SCRF infra was \$ 15,231 K
- Labor: FY06 spending on SWF was \$ 12, 943 K
  - Steady growth of workforce through the fiscal year ( next slide)
  - Workforce increased from 60 FTE to 150 FTE at EOY
  - 72% of this labor worked on SCRF R&D and building infrastructure
- M&S: FY06 spending in was \$ 12,603 K
  - Most of this went into the SCRF R&D program and infrastructure
- Level of funding was very uncertain during the year
  - Numerous funding changes... with funds added late in the year
- Our progress was paced by available funding.



	SWF Budget		SWF Actual
	Guidance	Revised	
AD	5250	4620	4719
CD	848	1217	1182
DIR	410	488	488
FES	0	0	9
PPD	2131	2226	2324
TD	4409	4228	4221
<b>TOTAL</b>	<b>13,048</b>	<b>12,779</b>	<b>12,943</b>

- All Divisions contributing
- Full effort reporting in place
- Note: FES is chargeback organization so CFS work shows up as M&S expense



- **ILC Design:**
  - FNAL made a large contribution to ILC RDR machine design and cost estimate
- **DESY 3.9 GHz Collaboration**
  - Fabricated, processed, & tested first 3.9 GHz cavities
  - Completed design of the CM and ordered parts
- **Capture Cavity II**
  - DESY supplied high gradient cavity intended for use with NML RF unit test facility
  - Completed MDB cryogenics modifications and demonstrated 1.8 K operations
- **300 KW klystron, LLRF, etc installed in MDB**
- **Operated Capture Cavity II at 31.5 MV/M**



# FY06 Accomplishments and status



Fermilab

- **Cavities:**
  - **Cavity Processing:** Purchased and received 4 nine cell TESLA cavities from ACCEL (Europe) to develop U.S. surface processing facilities ( at TJNL and Cornell)
  - **Vendor Development:** Ordered 4 nine cell cavities from AES a U.S. vendor: first step in qualifying them to make ILC cavities, ordered single cells from Roark/Niowave
  - **Lab Development:** Ordered two standard 9 cell TESLA cavities from TJNL, experienced cavity fabricators. Goal is both processing development and as a bench mark
  - **Large Grain:** Ordered two large-grain Nb 9 cell TESLA cavities from TJNL to explore BCP processing as an alternative processing technique
  - **Populate cryomodules:** The best of these cavities will be used to populate the 2<sup>nd</sup> cryomodule we build

- **Processing:**
  - **Cornell:** Funded Cornell to use existing BCP facilities to process an ACCEL cavity
  - **TJNL:** Funded TJNL to upgrade its facilities to EP process TESLA cavities and test them
    - 1<sup>st</sup> ACCEL cavity achieved 29.5 MV/ M
- **VTS**
  - Began construction of Vertical Test System in IB1
  - Civil done, ordered cryostat, power amp, etc
- **HTS**
  - Began construction of Horizontal Test System
  - Cryo connections in MDB ~done, cryostat in hand, will use same RF system as CCII
- **Cryomodules**
  - Slide on this
- **RF unit test facility**
  - Slide on this

Need to finish these slides

- **Cryomodule Assembly Facility (MP9)**
  - Large class 10/100 Clean room installed and operational
  - Large CM assembly fixtures fabricated and in hand
- **Joint ANL/FNAL processing facility built and is coming into operation for BCP and EP**
- **Began cleanout of NML**
  - CCM gone, Cryogenics installation under way
- **Fabricated cavities at ACCEL, AES**
  - 1 Processed at Cornell with BCP (26 MV/M)
  - 1 Processed at TJNL with EP ( 29.5 MV/M)
- **Initiated extensive collaborative activities**
- **Much more about all of this in the talks that follow...**

- GDE assumed U.S. funding increase \$30 → 60 M
- ART call for proposals in May resulted in \$ 105 M of proposed ILC R&D activity (not much on EDR in this)
- FNAL FY07 Request: ( without distinguishing between ILC and SCRF B&R categories) was:
  - SWF support for ~ 180 FTE incl. Detector R&D
  - \$22 M of M&S
    - Not including site specific civil design
    - Not including industrialization activities
    - Not including EDR effort >> RDR
    - Our plan assumed ~ \$ 4 M of M&S would go to other labs and universities, largely to cover cavity processing and collaborative activities
  - Total FNAL request was for \$ 56 M

- **Cavity R&D:**
  - Need to purchase enough cavities to measure yield (~50)
  - Need to develop processing technology and improve yield
  - Need infrastructure to dress cavities, test them, and put them in CM
- **Cryomodule R&D:**
  - Finish the Cryomodule fabrication infrastructure
  - Purchase parts for 2nd Cryomodule ( 1<sup>st</sup> with U.S. cavities)
  - Improve design and cost reduction (involve US Industry)
- **RF Unit Test:**
  - Prepare ILCTA\_NM infrastructure to test DESY cryomodule by end of year, and eventually with beam
- **SRF Infrastructure:**
  - Start design and initial fabrication of cavity processing and test infrastructure needed for S0. Complete VTS, HTS, etc systems
- **EDR Launch: Opportunity to take a major leadership role in ILC**

- **FY07 GDE recommendation to DOE was to support 68 FTE and \$ 9.8 M in M&S at FNAL... \$22.7 M total from ILC funds**
  - **A big increase, but far from supporting the existing workforce**
  - **Recommended additional support of staff & infrastructure from other funds, but no OHEP plan for these funds ( funding depends on availability of lab's core funds for this)**
- **FNAL IFP (core funding) too low to support infra work**
- **Next: FY07 national ILC funding became uncertain**
  - **Presidents budget recommends \$ 60 M (House also)**
  - **Senate recommended \$ 45 M, but no bill passed**
  - **Awaiting Senate passage of the bill, resolution in conference**
  - **meanwhile... THE ELECTION... Democrats win →CR**
- **We now are told that the continuing resolution will be in force for the entire FY07 fiscal year → SCRF budget is completely uncertain... very disruptive !!!**

- Clearly need to establish a “line” of funding so the required SCRF infrastructure can be built and so that long term planning is possible
- What is the scope of the overall effort required ?
  - DESY spent ~ \$150 M of M&S to build TTFII and associated infrastructure.
  - The facilities we need are more advanced... higher gradients (cleaner) and higher cavity/CM throughput
  - But... many existing pieces of infrastructure at FNAL that we can be exploited ( buildings, refrigerators, A0 photo injector parts, etc)
  - The infrastructure we plan in the next ~ 3 years is comparable in scope to DESY ~ **\$130 M**



- **What sets the scope?**
- **The best cavity fabrication and surface processing can yield outstanding cavity performance ( $> 40$  MV/m Eacc)**
  - But the process yield is low for 9 cell cavities
  - Evidence points to one or more uncontrolled variables
  - Goal is to achieve clean smooth Nb surfaces
  - Particulates at the micron level lead to field emission, defects of 10s of microns lead to quenches
- **Need adequate lab infrastructure to build, process, and test a large number of cavities to track down the sources of variability.**
  - S0 ILC goal:  $> 100$  cavities process/test cycles per year
  - TJNL  $\sim 30$ /yr, Cornell  $\sim 12$ /yr: both institutions have other plans beyond 2008 for their facilities
  - Clear need for new large facility

- **What are the key R&D issues ?**
  - **Reliable achievement of high gradients ( ie yield)**
  - **Cavity fabrication techniques, surface processing technology, process control, and cavity diagnostics and test facilities are all key elements**
  - **So is cost of fabrication and processing**
  - **Achieving high gradient cavity operation in cryomodules with beam is also crucial**
    - **Goals outlined in GDE S2 task force report**
  - **Additional goals associated with spoke resonators**
- **Will the facilities we plan be adequate to address key questions ? On what time scale.**
  - **Yes... our claim is that the facilities we propose will be**
  - **But... timescale depends on funding profile**

- **Laboratory Collaboration**
  - Have we developed close collaboration with U.S. SCRF experts at universities and DOE labs (TJNL) ? We claim yes..
  - Extensive Collaborative activity with non-U.S. partners, and U.S.universities, and labs ( next slide)
- **Are we developing industry ?**
  - No... not yet
  - Have started, but effort is limited by our own expertise to guide them and by available funding
- **Is our plan prioritized so that it can be scaled back?**
  - Yes... Priority set by 1) GDE goals, 2) FNAL desire to host ILC
  - Scale back ? Sure, but to the extent we do that we will never catch up with Europe and Japan on SCRF
  - Priorities and scope largely set by the needs of the ILC R&D program, but facilities can serve many other needs in the future

- **ANL:** EP development and cavity processing
- **Cornell:** Cavity processing & test, materials R&D
- **DESY:** 3.9 GHz, cryomodule kit, TTF
- **KEK:** Cavity R&D, ATF II
- **MSU:** HPR, Cavity vendor development and cost
- **TJNL:** EP cavity processing and test
- **INFN:** tuners, HTS, NML gun cathodes
- **Penn/Triumf:** cavity tuners
- **SLAC:** RF power, klystrons, couplers
- **CERN, DESY, KEK, INFN, etc:** Type IV CM design
- **India:** Design, couplers, cavities, etc
- **NW,UW/NHML,Cornell, DESY, KEK:** Materials etc...
- **Major Ramp up in planned collaborative efforts !**

- Spread sheet here

- I have described to you the importance of SCRF as and “enabling” technology for HEP.
- In the talks that follow we will:
  - Address the questions in the charge in more detail
  - Describe plans for the needed generic infrastructure
  - Present the estimated cost and schedule to build it
  - Describe an R&D program using that infrastructure to address the key R&D questions in HEP, primarily those that face the ILC, HEP’s new planned flagship facility
- Hopefully we will convince you that this crucial enabling technology urgently needs significant investments and that FNAL is the place to make them.