

# **Horizontal Test Stands and CC2 Results**

Andy Hocker

---

- **PRODUCTION NEED:**
- **After passing a vertical test, much cavity handling ensues**
  - **Welding to He vessel, installation of coupler/tuners...**
- **Until we perfect this process, best to make sure cavities survive it before they're buried in a CM**
  - **Figure of merit:  $E_{acc}$  and  $Q_0$  within spec**
- **R&D NEED:**
- **Plenty of ideas on the table for ways to address cavity tuning, microphonics, Lorentz force detuning, high power RF processing...**
- **HTS serves as a bench where these ideas can be tested**

- **Shielding cave**
- **Vacuum vessel (a one-cavity cryomodule)**
- **1.8 K cryogenic plant/distribution**
- **Clean vacuum systems for cavity/coupler**
- **High-power (at least ~300 kW) pulsed RF (klystron/modulator), LLRF control system**
- **Cavity diagnostics**
  - **X-ray detectors**
  - **Dark current detectors (Faraday cups)**
  - **Thermometry**
- **DAQ and controls system**
- **Much of this is already in place at Meson Detector Building (MDB)**


- **Nine-cell TESLA cavity from DESY shipped to FNAL for A0PI energy upgrade**
- **Horizontal testing infrastructure built up at MDB to ensure that it survived the trip**
  - ...and with an eye toward HTS
- **CC2 operations began in FY06, quite successful:**
  - **CC2 peak gradient: 31.3 MV/m ( $Q_0 \sim 1.5e10$ )**
- **Bodes well for HTS**
  - **Most of the RF and cryo infrastructure will be the same**

setpoint		input calibration	
SP amp	32.0 MV	offset	+420

Sustained 800  $\mu$ s “flat-top” of ~31 MV/m, stable LLRF feedback control

EXPERT PANEL      I and Q after detector

DAC offset calibration



**Coupler Processing**

Current Sequence Status

RF Power Setting: 44.000 dbm

Pulse Length: 0.000

RF Power: 44.000

Hardware Trip: 44.000

Interlocks Reset: Not New



Center Frequency: 132000000.000000

Sequence Definition	Diagram	Soft Limits	Simulate
Max Power Warm [J]	14000		
Step Time [A] (s)	2.000		
Watt/step [J]	7000		
Step time soft trip [s]	2.000		
Watt/step down soft [J]	7000		
RF Fraction at Trip [F]	0.50		
Steps After Trip [N]	10		
Post Trip Delay [S]	1		
Step Time After Trip [C]	2		

Pulse Width (ms) Dwell Time (s) [I]


T100	3	
T150	3	
T200	3	
T250	3	
T300	3	
T350	3	

## Automated coupler processing



## Dynamic heat load studies ( $Q_0=1.5e10$ )

## X-rays observed at full gradient



- New cave and cryogenic transfer lines in MDB
- New cryostat for easy cavity installation/removal



- Cryostat installation in MDB underway, commissioning to follow

- HTS testing cycle is ~2 wks/cavity
- ILC needs will eventually demand higher throughput
- A second cryostat (clone of first) could be housed in existing cave --- would need additional
  - cryo transfer lines (plant capacity sufficient)
  - RF distribution
  - vacuum systems
  - instrumentation
- **Even better: a two-cavity cryostat**
  - Yet more throughput with minimal incremental cost
  - Could be run as a mini-CM, with RF system upgrades

- **Except for the 1.3 GHz RF system, HTS is not very ILC-specific**
- **A 1.8 K fridge with ports for RF, vacuum, and instrumentation**
- **Example: FY07 will see HTS testing 3.9 GHz SCRF cavities for DESY's VUV-FEL**
  - **Modified a few cavity/coupler support structures**
  - **Bought a 3.9 GHz klystron and some waveguide**
  - **Downconverter for LLRF system**
  - **That's about it!**
- **The use of HTS for R&D on cavity “accessories” (couplers, tuners, etc.) has wide applicability**





# Cost



## HTS1

	M&S	SWF
Cryo	330K	1.3 FTE
HLRF	50K	1.0 FTE
LLRF	21K	1.5 FTE
Controls	30K	0.5 FTE
Test infra	36K	1.3 FTE

## HTS2

Cryostat	250K	2.0 FTE
Cryo	280K	2.5 FTE
RF	140K	1.0 FTE
Vacuum	60K	0.5 FTE
Test infra	23K	1.3 FTE

## Total

**1220K**                      **1055K**

- **HTS plays a key role in developing high-performance ILC cryomodules**
- **Provides Fermilab with unique opportunity for studying SCRF cavities and their accoutrements under high-power pulsed RF**
- **Infrastructure at MDB already highly developed**
- **Capture Cavity 2 program a successful demonstration of laboratory's horizontal testing capabilities**