



# Overview XFEL RF System

S. Choroba, DESY


- **XFEL RF Requirements**
- **RF Station Layout**
- **Overview RF Components**

Many people from DESY groups in HH and Zeuthen, other labs and companies have contributed to the RF System



# XFEL RF System Requirements

Number of sc cavities:	928 total	
Power per cavity:	122 kW	
Gradient at 20GeV:	23.6 MV/m	
Power per 32 cavities (4 cryo modules):	3.9MW	
Power per RF station:	<b>5.2MW</b> (including 10% losses in waveguides and circulators and a regulation reserve of 15%)	
Number of RF stations:	<b>29</b> (26 active)	
Number of RF stations for injectors:	<b>2</b> (5)	
Macro beam pulse duration:	600 $\mu$ s	
RF pulse duration:	<b>1.38ms</b>	
Repetition rate:	<b>10Hz (30Hz)</b>	
Average RF power per station:	<b>72kW (150kW)</b>	

# Layout of the RF System (1)





# Layout of the RF System (2)



- Tunnel components (klystrons, pulse transformers, aux. power supplies etc.) will be installed below the cryo module.
- The waveguide distribution will be installed on the side of the cryo module.
- They are not accessible during accelerator operation.



# Layout of the RF System (3)



- The modulators will be installed in the modulator hall. 7x5 modulators in one hall.
- Maintenance and repair is possible during accelerator operation.


# Multibeam Klystron

→ Details in V. Vogels presentation

## Multibeam Klystron Requirements

Operation Frequency:	1.3GHz
Cathode Voltage:	< 120 kV
Beam Current:	< 140 A
Max. RF Peak Power:	10MW
RF Pulse Duration:	1.5ms
Repetition Rate:	10Hz
RF Average Power:	150kW
Efficiency:	65%
Solenoid Power:	< 5.5kW
Length:	2.5m

developed for TESLA



# Vertical MBK Prototypes



THALES TH1801



CPI VKL8301




TOSHIBA E3736

3 klystron vendors have developed MBKs during the last years

## Vertical MBKs

- 5 THALES TH1801 have been built, 1 is in bakeout at THALES  
(Best tube 10MW, 1.5ms, 10Hz, 63%)  
klystrons in use at FLASH, PITZ, MBK Test
- 1 TOSHIBA E3736 at DESY (10.4MW, 1.5ms, 10Hz, 66%)
- 1 CPI VKL8301 at DESY (8.1MW, 1.3ms, 10Hz, 53%)


# Horizontal MBK Prototypes




Horizontal versions of MBKs by all 3 vendors are under construction (total length of spec. 11 pages): first deliveries are expected early 2008

# Modulator Requirements

- Modulators must generate HV pulses up to 120kV and 140A, 1.57ms pulse length and 10Hz (30Hz) repetition rate
- The top of the pulse must be flat within 1%
- The bouncer type modulator with its simple circuit diagram was chosen



# Bouncer Modulator (1)



- 3 modulators have been developed, built and delivered to TTF by FNAL since 1994
- They are continuously in operation under different operation conditions





## Bouncer Modulator (2)


- Industry made subunits (PPT, ABB, FUG, Poynting)
- Constant power power supply for suppression of 10Hz repetition rate disturbances in the mains
- Compact storage capacitor bank with self healing capacitors
- IGCT Stack (ABB); 7 IGCTs in series, 2 are redundant
- Low leakage inductance pulse transformer (ABB)  $L < 200 \mu\text{H}$  resulting in shorter HV pulse rise time of  $< 200 \mu\text{s}$
- Light Triggered Thyristor crowbar avoiding mercury of ignitrons






# HV Pulse Cable

- Transmission of HV pulses (10kV, 1.6kA, 1.57ms, 10Hz (30Hz)) from the pulse generating unit (modulator hall) to the pulse transformer (accelerator tunnel)
- Maximum length 1.5km
- Impedance of 25 Ohms (4 cable in parallel will give 6.25 Ohms in total) to match the klystron impedance
- Triaxial construction (inner conductor at 10kV, middle conductor at 1kV, outer conductor at ground)



# HV Pulse Cable Test

- Pulse transmission has been successful at FLASH, Mod. 5.
- Remaining problem: EMI needs investigation
- Modifications of the modulator are required (high bouncer, better EMC cabinets) already integrated in new specification
- Collaboration MKK/MHFp





## Bouncer Modulator (3)

- 11 Modulators have been built, 3 by FNAL and 8 together with industry
- 11 modulators are in operation (FLASH, PITZ, Teststands)
- 10 years operation experience exists
- Modulator foreseen for waveguide tests will be installed in DESY hall 2 and connected to PT and klystron in hall 3 (Bouncer type plus improvements) and used for pulse cable tests
- Order for XFEL prototypes has been placed (27 pages of specification) (1 Bouncer plus 1 PSM)
- Test of prototypes in Zeuthen starting early 2008

→ Details in W.  
Köhlers presentation

# Waveguide Distribution

- Distribution of klystron output power to the superconducting cavities
- Protection of the klystron from reflected power
- Control of phase



→ Details in V. Katalevs presentation

# Waveguide Distribution

3 Stub Tuner (IHEP, Beijing, China)




Changing phase, degree  
Impedance matching range  
Max power, MW

$\pm 60$   
 $1/3Z_w \square 3Z_w$   
2

\*  $Z_w$  – waveguide impedance

E and H Bends (Spinner)




Circulator (Ferrite)




Type	WFHI 3-4
Peak input power, MW	0.4
Average power, kW	8
Min isolation at 1.3 GHz, dB	>30
Max insertion loss at 1.3 GHz, dB	$\square 0.08$
Input SWR at 1.3 GHz (for full reflection)	1.1

Hybrid Coupler (RFT, Spinner)



Directivity, dB	$\square 30$
Return loss, dB	$\square 35$
Coupling factor, dB	12.5; 12.0; 11.4; 10.7; 10.1; 9.6; 9.1; 8.5; 7.8; 7.0; 6.0; 4.8; 3.0
Accuracy of coupling factor, dB	$\pm 0.2$




RF Load (Ferrite)



Type	WFHLL 3-1
Peak input power, MW	1.0
Average power, kW	0.2
Min return loss at 1.3GHz, dB	32 $\square$ 40
Max VSWR at 1.3 GHz	<1.05
Max surface temperature, $\square T$ °C (for full average power)	50
Physical length, mm	230


RF Load (Ferrite)




Type	WFHL 3-1	WFHL 3-5
Peak input power, MW	2.0	5.0
Average power, kW	10	100
Min return loss at 1.3 GHz, dB	32 $\pm$ 40	32 $\pm$ 40
Max VSWR at 1.3 GHz	<1.05	<1.05
Max surface temperature, $\Delta T$ °C (for full average power)	20	30
Physical length, mm	385	850

# New Waveguide Distribution

## Standard FLASH like Distribution



Combined System with shunt tees: less space, less parts, less weight, lower costs, must be tested, planned for ACC6 at FLASH



# Preamplifier




- Specification reworked
- Several new amplifiers are ordered, some received and in test
- Will be used at MBK teststand, FLASH, Zeuthen





# RF Interlock

- Zeuthen/HH development
- FPGA Based
- Version #2 installed at FLASH
- Version #3 installed at PITZ and module test facility, will be tested at FLASH too
- Version #3 allows setting of interlocks remote controlled



Interlock WebServer – Screenshot 1

INTERLOCK 3 - Mozilla Firefox

Label: Bearbeiten Ansicht: Geho Lesezeichen Extras: Hilfe

http://141.34.30.105/

**XFEL Interlock**

Welcome to the Nios® Webserver.

Please select a function:

**INTLK3 Controller**

Display	System Info	Reboot	NIOS2 Webserver Ver 1.08
Hardware Status	Complete date	Mar 17 2006	
WebServer Configuration	Flashdate:	unknown	
Serial #	Flashfile:	unknown_virgin	
OS/IO-Statistics	MAC:	14 43 12 11 10 34	
Logfiles	IP Addr:	141.34.30.105	
Management	IP Mask:	255.255.255.0	
	Gateway:	141.34.30.1	

**Connected Stations**

Station	Current Configuration			Stored Configuration		
	Name	Version	Prog.File	Name	Version	Prog.Date
1	INTLK3_CNTRLM	1.0	intlk3_ctrlm.pdf	INTLK3_CNTRLM	1.0	Mar 14 2006
2	INTLK3_WinComp_A	1.3	INTLK3_WinComp_A			No changes
3	INTLK3_WinComp_V	1.3	INTLK3_WinComp_V			No changes
5	INTLK3_Dig400	1.0	intlk3_dig400			No changes
6	INTLK3_Dig400	1.0	intlk3_dig400			No changes
8	INTLK3_ANAIO	1.0	intlk3_anaio.pdf			No changes
9	INTLK3_ANAIO	1.0	intlk3_anaio.pdf			No changes
13	INTLK3_LogIO	1.0	INTLK3_LogIO.pdf			No changes
15	INTLK3_LogIO	1.0	INTLK3_LogIO.pdf			No changes

Ferng