

Key R&D Issues in SCRF
and
FNAL Collaboration

Marc Ross

Superconducting RF

- **Luminosity requires beam power;**
 - Superconducting RF is the *most effective* way to create high power beams
- **Proven design:**
 - 1.3 GHz sheet metal cavities
 - ILC - Each cavity delivers 285 KW to 9mA beam
 - ILC - fill time 38% total pulse
 - ILC - linac efficiency (RF to beam): 50%
 - Fill time, distribution and feedback overhead
- **Large irises → minimal emittance growth with achievable tolerances**
 - If we can achieve tighter assembly/tuning tolerances, can improve efficiency

Adopt TESLA cavity design

- **Capitalize on momentum of the DESY-centered development**
 - 1992 to present
 - Copy, Develop, Extend, Deploy → full system Test
 - Unprecedented scale → ILC >16000 cavities
- **US labs / universities:**
 - Will appropriate and perfect 'large scale' preparation technology
 - ('RD – scale' systems to date)
 - Are suited for this task:
 - Substantial expertise – distributed –
 - JLab, Cornell, ANL, MSU, LANL, FNAL, SLAC... (Cavities, Cryo, RF)

SRF Infrastructure Plan: Goals

- To perfect U.S. fabrication & processing of SCRF cavities and modules and to demonstrate performance with a full range of testing (including beam performance)
 - Copy TESLA-style design / processing / assembly techniques
 - Establish *process controls* to reliably achieve high gradient cavity operation and cryomodule performance
 - Test cavities and cryomodules at the component level and in a *systems test* to demonstrate yield, reproducibility and beam performance
- To facilitate commercial production of SCRF components and modules
 - Provide training and facilities to allow *industrial participation* and input to the process
 - (Similar to SC cable and magnet technology transfer)
- To participate in SCRF Research and Development
 - Our attempt to *aggressively support* the world's SCRF RD community
- All of this work will be carried out in collaboration with US/international partners

Setting the Scale

- For ILC: produce 4 to 6 cryomodules in the next 4 years
 - ~ 50 cavities used;
 - additional needed for development and testing
- The number of cavities needed and the scope of work required to establish a reliable, cost-able process determine the scale of the US infrastructure
- International (ILC/GDE) coordination:
 - S0 'tight loop':
 - Process and re-process the inside surface of a limited number of cavities, repeatedly, testing each time... (~100 procedures/year for several years)
 - Answers due 08, 09 → guidance for a final gradient recommendation
 - S1 cryomodule demo:
 - 31.5 MV/m OPERATING cryomodule
 - S2 'string test':
 - Put it all together
 - Various critical tasks

This talk:

1. What are the key R&D issues faced by the U.S. accelerator community in the area of SCRF?
4. Does the laboratory make effective use of collaboration and existing SCRF assets at other laboratories and universities?

- **Outline specific 'RD' tasks (~8)**
 - Based on technical risk v/v state of the art
 - Based on ILC Linac cost-drivers
- **How does our proposal connect to each?**
- **How national SCRF RD 'fabric' connects to each?**
 - i.e. what is role of collaboration

Specific tasks - technical

- (Key challenges that will still be with us 09..)
- Electron beam welding (EBW) of formed Nb sheet
- High volume etching of finished assemblies
- Surface smoothness and particulates
- Practical gradient → radiation, Q, dissipation (multipactor)
- Assembly, including power couplers and Higher Order Mode couplers
- HOM
- Process and Testing Diagnostics
- Full power system tests – static, dynamic (w&w/o beam)

Specific Tasks – Cost

<u>Cryomodule costs</u>	<u>fraction</u>	<u>sum</u>
Cavity Fabrication	36%	36%
Power Couplers	10%	46%
Helium Vessel Fabrication	8%	54%
Magnetic Package (Quad)	7%	61%
Tuners	7%	68%
Assembly, Testing, Transport	5%	72%

(Next 7 items – to 1% level (22%)– Vacuum vessel, shields, interconnect, processing, dressing, pipes, supports, instrumentation)

The cryomodule / cavities in it are a cost driver for the ILC linac.

Cavity Fabrication: EBW

- (Almost) all Nb cavity welds done in HiVac conditions with EBW
- Identified as critical path for ILC Linac construction
 - KEK – based evaluation: 2003
- a single cavity requires dozens of welds
- e.g. 800 machines produced by Mitsubishi Electric Company to date → mostly small
- typical cost 3 M\$, 80% used for automotive precision welding (from KEK study)

- EBW supports RD → flexibility
- RD needed to reduce EBW costs/perfect operation
- JLAB EBW machine at 2 shifts now...

7x time reduction (v/v RD) using multi-chamber-type high-speed machine with load-lock. ←

TESLA TDR

EBW for automotive components has multi-chambers with gate valve separation. **PRIUS NiMH**

→

Most comprehensive: KEK-TESLA TDR eval. (2004)

Needed capital investment (MEC):

6 dedicated for the 9-cell cavities (60M\$ for specialized machines),

12 dedicated small machines for stiffening rings (24M\$ for specialized machines).

Additional machines for HOM couplers and beam pipes, using 'standard' welders



FNAL EBW: Buy one 'properly configured machine'
(M. Foley)

DESY Process parameters: HF / H₂SO₄ (10/90)

Process data	fixed in middle of 2005	
Voltage	17 V	
Acid refill volume	9- 10 l / min (flow)	→ 200 liters total
Average temperature		
Cavity inlet	24 C	
Cavity outlet	29 C	→ 'active' cooling required
Average current	240 A	→ 4kW power dissipation
N ₂ overlay	30 l/min	
Acid usage up to Main EP	12-14 gr Niobium per liter acid	→ 2.5 kG acid load
Duration	2*180 Min	
Removal	nominal 144 μm	→(cavity wall thickness ~ 2.5 mm)
Fine EP		
Duration	1*120 min	
Removal	nominal 48 μm	
Cooling	regulation to flat Current curve	

Is max cavity gradient ‘scatter’ due to EP process?

- Process parameters:
 - non-reproducibility, non-uniformity of material removal
- Set-up: acid level, cathode bag, cathode shielding, current leads, T-control
- “Q-disease”: unpredictable, material?
- Reproducibility in acid composition (DESY)
- Draining and rinsing:
 - overheating? for multi-cell cavities


- Is scatter caused by
 - “environmental” problems?
 - Malfunction of system
 - Problems during rinsing and/or assembly
 - Vacuum problems
 - Problems during testing
 - Human errors
- (Peter Kneisel - JLAB)

- Re-visit residual contamination of EP surfaces: XPS, SIMS? FE
- Investigate different rinsing methods:
 - hot water (Henkel), H₂O₂ + US, anodizing, oxipolishing,..
 - on samples, single cells: either several or reference cavity of known performance
- Removal of sulfur from mixture:
 - filtering?, solvents,...
- Implement “on line” monitoring of HF concentration and polarization curves, purity (gas chromatography)
- Shaping of cathode:
 - more uniform material removal, more uniform polarization curves over whole surface, lower voltage to achieve required current density, more uniform T-distribution?
- Does it make sense to explore other acid mixtures? Or should one concentrate on making present process “fool proof”?

- **Surface studies:**
 - Saclay, Univ. Wuppertal, Jlab/Fnal, INFN Genoa, Cornell?
- **Rinsing studies:**
 - KEK, DESY, Jlab/Fnal, Cornell, Saclay, ANL, MSU?
- **Electrode shaping:**
 - INFN Legnaro, DESY/Henkel, KEK, Jlab, Cornell, ANL/Fnal
- **Implementation of “on-line” monitoring:**
 - DESY, KEK/Nomura Plating, Jlab/Fnal, Henkel, ANL?

(slides adapted from Peter Kneisel, TTC 09.06)

Jlab EP:





FNAL EP: H. Carter / C. Antoine

f

Surface smoothness / particulates

Fermilab




- Residual 70 um particulate – sulfur – in single cell test at Cornell
 - Before and after high pressure rinse
- New method needed to clean post-polished surface
- Sulfur residue from H₂SO₄ decomposition → EP process
 - Acid preparation/degradation?

Advance Material R&D



Superconductivity limits

The theoretical limits for RF superconductivity aren't well known

- **What causes the high field losses/ hot spots ?**
 - Morphology ?
 - Grain boundaries
 - Surface contamination (O)
- **Recommendations**
 - Basic R&D on superconductivity
 - e.g. Hot Spot Model – A. Gurevich (Coil:n w FSU)




- **Effect of trapped vortices**
- **Heat source ~ can be very small (nm to mm)**
- **Thermally affected zone: ~ 5 mm and growing with B!**



- **Feedback from vertical test: 3 criteria**
 - Achievable field (quench)
 - Q and dQ/dE 1W/cavity in pulsed operation (5e9@25) – (cryogenic load)
 - Radiation (x-ray)
- **Vertical test provides the first indication**
- **How to interpret the vertical test result:**
 - What is the 'real yield'?
- **Practical gradient degraded from max achievable**
 - VTS analysis key to understanding above limitations

DESY Data: 22 cavities – 2006
 Predicted usable gradient based on vertical test results:




**FNAL Vertical Test: C.
Ginsburg**

Assembly -

Does performance further degrade due to handling?

Typical assembly variation is *better*; esp. Horizontal to CM



Performance of FLASH Accelerator Modul From H. Weise/ D. Kostin

A State-of-the-art module


- cryogenic type III
- latest coupler generation
- Etched (BCP) cavities

In single cavity measurements 6 out of 8 cavities reach 30 MV/m!

Equal power feeding $\langle E_{acc} \rangle = 25 \text{ MV/m}$

Cavity tests:

- Vertical (CW)
- ▨ Horizontal (10Hz)
- Module 5 (1Hz)
- ▨ Module 5 (5Hz)



Cavity String Assembly



The assembly of an 8 cavity string

- is a **standard procedure at DESY**
- was done by technicians from the TESLA Technology Collaboration
- was the basis for two industrial studies.

The transfer of this well known and complete procedure to **industry** has started.




DESY will provide sub-components for the first string / module built in industry; this allows for an **early training**.



f

Fermilab

Cryomodule assembly: 1200+ parts



02/13/07

Key R & D, M. Ross - SCRF Infra

FNAL CM Assembly: T. Arkan

- **Single most serious problem with SNS cryogenic accelerator cavities**
 - Also implicated as most critical failure in 3 separate 2006 RD programs
 - 2 cavity developments at KEK
 - Fermilab / DESY 3.9 GHz cavity
- **Typical failure:**
 - Modelling of multi-pactor thermal breakdown
 - Failure to clean closely spaced components
 - Failure to adequately cool coaxial feedthrough
 - Coupling strength to fundamental
 - Construction / fabrication
- **For new cavity designs, clean HOM extraction must be demonstrated with beam**
 - System test issue #1


FNAL HOM: H. Edwards

Damping of Higher Order Modes (HOMs)

The spectrum of the electron bunch ($\sigma_z = 25 \mu\text{m}$) reaches high frequencies up to 5 THz.


The standard accelerator module has an **integrated loss factor of 135 V/pC**.

The total power deposited by the nominal beam is **5.4 W per module**.




The design of the HOM coupler and the beam pipe absorber take into account a possible XFEL upgrade (more bunches / CW mode).

The HOM coupler was tested in CW mode. The absorber is specified for 100 W.



HOM coupler



beam pipe absorber

Diagnostics

- **Best opportunity/ unique opportunity for Fermilab particle physics community to contribute**
 - Labs with fully operational 9 cell cavity vertical test stands don't have resources or time for this challenge (JLab, DESY, KEK, Cornell)
 - Radiation, thermal, data acquisition/control and RF control
- **Goal:**
 - Identify and track field emitters through 9 cell / 1 cell cavity process (VTS, HTS, CM assy/test, final install)
 - Cleanly separate failure modes:
 - Quench due to 'flaws'
 - Field emission & field emission induced quench
 - Multi-pactor and related thermal breakdown
 - Q- reduction
- **Dynamics changes through process**
 - CW, high power, high peak power

**FNAL Vertical Test:
C. Ginsburg**

- **Purpose of system test - ILC evaluation:**

Test:	Comment	Risk
Component testing for reliability		high – specialized tests also required
Full intensity beam energy stabilization	will be done at DESY	medium – controls
‘Dirty vent’ / fast protection		
Fault recognition – controls	developed at DESY	high
quench/coupler breakdown rates		high
dark I		
gradient spread		
long term testing		high
trapped HOM		medium
Stability energy / phase		high
x-ray		
thermal cycling		
heat loads		
vibration control - incl quad		
test bed for dev ancillary		high
demonstration of effective international management		high

- **Critical Goal for FNAL infrastructure: System test**

**FNAL System Test ‘NML’:
S. Nagaitsev**

RD Challenges Summary (1):

- **EBW is a platform for development: prototype Nb sheet structures / cavities**
 - Buy an EBW, to be used for prototyping and understanding weld performance and geometry
- **Chemistry remains single most serious limit**
 - Develop systems at JLab and ANL, stair-step to next generation here
- **Residue implicated, not properly removed by rinse(s)**
 - Rinsing program underway at KEK, starting at JLab (TTC)
- **Final acceptance testing will be done at lab**
 - All project 'scenarios' have VTS defined as a 'Lab function'

RD Challenges Summary (2):

- **CM assembly tooling still quite primitive**
 - DESY staff have not had time to work things forward
 - Their industrial transfer is starting, we are observers
- **HOM coupler remains weak link in the design**
 - Sort of a surprise. FNAL group active throughout the development process
- **Diagnostics require substantial development effort**
 - Technical
- **System test is primary demonstration**
 - NML is the US system test
 - World system test in many ways
 - KEK / STF will not have high power beams
 - DESY / TTF does not have flexibility for long term high power tests

Collaboration – Summary

- **International partners: cavity technology transfer**
 - From DESY
 - From KEK
 - NML ‘joint venture’
- **US partners, SRF labs: long term (multi-year) relationship**
 - Strong staff exchange and infrastructure development
 - Jefferson Lab
 - Argonne
- **US partners, universities: fundamental RD**
 - Cornell, MSU, LANL, FSU, Universities
 - Various, ranging from materials physics to tooling development and data analysis
- **High Level: How does this work? →**

- **The mission of the collaboration is**
 - to advance SCRF technology research and development and related accelerator aspects across the broad diversity of scientific applications, and
 - to keep open and provide a bridge for communication and sharing of ideas, developments, and testing across projects
- **Interwoven in S0 plan**
 - **Parallel single cell rinsing studies**
 - (defined in TTC EP study 1.2005)
- **Interaction with TTC**
 - **TTC is the resident 'pool' of SRF expertise**
 - Thanks to DESY for the formation of this group through the TESLA effort (~10+ years)
 - Ideal group for RD, review and analysis
 - **Requested TTC perform single cell work**
 - September 2006
 - **Affirmation of interest.**

FNAL – DESY

- **Management and technical connections:**
- **Excellent ~15 year history, based largely on efforts of Helen Edwards**
 - TTF Beam Time Allocation Committee member
 - Fermilab-built hardware is basic component of TTF
 - Ongoing TTF studies: HOM, LLRF, beam dynamics...
- **Steady exchange of testing and infrastructure development staff**
 - XFEL Project has (informally) offered management role
↔ mutual benefit
 - Participation offer leads to expectation of steady collaboration through XFEL construction

- **Technical connections:**
 - Strong staff exchange through KEK – ATF (instrumentation and control) 15 years (MCR)
 - three-way collaboration with DESY on HOMs
 - Parallel development of infrastructure – competition and collaboration (KEK is ahead)
 - Orthogonal development: new shapes at KEK; design work at Fermilab
- **Starting inter-lab SCRF projects**
 - Cavity pre-tuning machine (DESY also)
 - Cavity exchange (part of GDE 'S0') to start in 2 months (personnel accompaniment)

FNAL – JLAB

- **JLAB is lead US lab for 07 ‘ILC –S0’ cavity processing demonstration**
 - **Recent results extremely encouraging: 40MV/m & 30 MV/m in JLAB –processed cavities**
 - **JLAB has produced more niobium cavities than any other lab now holds (close to) the world’s performance record.**
 - **We have participated in this work – through:**
- **FNAL staff on long-term assignment (~2 FTE 07)**
- **Joint team development of JLAB infrastructure (tooling, diagnostics, procedures)**
- **Long term (~5 year) commitment to work through process technology**

FNAL – ANL

- **Formal linkage between lab directorates**
- **A heavily shared ‘local’ resource**
 - ANL 20+ years of expertise, including electro polishing
- **Now:**
 - **Chemistry rooms at ANL ‘co-fab project’**
 - **Electro-polish and chemical etching**
 - To be fully operational in mid-late 2007
 - Development of spoke resonators (HINS)
- **Soon:**
 - Active participation in cavity processing and testing on day to day basis

Why is THIS the right strategy?

- **What is the relationship between infrastructure development on site and collaboration with US Labs?**
 - Our infrastructure will be based on what we learn through collaboration now established
- **How do the facilities in this plan accomplish goals?**
 - Each process component (we know of) is included; each step is to be extended
- **What are the priorities?**
 - Support the GDE – determined priorities (TTC); focus on equipment needed to answer toughest questions: Chemistry, system test, diagnostics

Why is THIS the right strategy? (2)

- How do we complement facilities at SLAC, JLab, Cornell, MSU, and ANL? What are the costs/benefits of each of these relationships? How would we like them to grow?
 - We will learn from these facilities, through staff exchange, usage and feedback, and then develop each.
 - The equipment left behind in this process enriches each partner
- What is the impact of the infrastructure on each of the (known) projects – including non-wholly-owned – like ANL/JLab projects, XFEL
 - Diverse projects facilitate understanding
 - Projects with added momentum (i.e. XFEL) will benefit from accessible, flexible, test area.
 - We benefit from their ‘volume’ and management lessons learned

Fermilab and SCRF

- **US must demonstrate competence in this field in order to host ILC**
- **Such competence is also a requirement for related machines**
 - FEL, ERL, proton...
- **In a very basic way, Fermilab and collaborating US labs must compete**
 - (i.e. in order to be a viable ILC host)
 - ‘Doing’ is the best way to learn, and this project contains required components