

Beam Test Facility at NML and Cryomodule Test Stand

Sergei Nagaitsev
Fermilab

February 13, 2007

What is this talk about?



Infrastructure	M&S	SWF	Total with Indirect
Cavity Fabrication Infrastructure	\$ 3,000	\$ 675	\$ 4,380
Cavity Processing Facilities	\$ 11,100	\$ 4,590	\$ 18,945
Vertical Test Stand (VTS 2 & 3)	\$ 2,625	\$ 1,845	\$ 5,475
Horizontal Test Stand (HTS 2)	\$ 1,220	\$ 1,057	\$ 2,805
Cavity/Cryomodule Assembly Facilities (CAF_MP9 & ICB)	\$ 690	\$ 270	\$ 1,158
NML Facility (ILCTA_NML)	\$ 18,270	\$ 23,220	\$ 51,700
Cryogenics for Test Facilities	\$ 10,690	\$ 950	\$ 13,692
Cryomodule Test Stand	\$ 5,400	\$ 2,970	\$ 10,180
Material R&D	\$ 870	\$ 722	\$ 1,960
Illinois Accelerator Research Institute	\$ 20,000	\$ 4,050	\$ 28,605
Grand Total	\$ 73,865	\$ 40,349	\$ 138,900

Goals for SRF Infrastructure



Fermilab

- **To perfect U.S. fabrication & processing of SRF cavities and modules and to demonstrate performance with a full range of testing (including beam)**
 - Deploy ILC design / processing / assembly techniques
 - Establish process controls to reliably achieve high gradient cavity operation and module performance
 - Test cavities and modules at the component level and in a systems test to demonstrate yield, reproducibility and beam performance
- **To facilitate commercial production of SRF components and modules**
 - Train and transfer SRF technology to the US industry
 - Allow industrial participation and input to the process
 - Similar to SC cable and magnet technology transfer
- **To participate in SRF Research and Development**
 - Develop expertise in SRF technology and provide training base for construction and operation of future accelerators
 - Our attempt to fit into the world's SRF community

All of this work will be carried out with US/international collaboration

Our overall strategic goal: bring the ILC to the Fermilab site



- **Need to create state-of-the-art SCRF technology base at Fermilab**
 - **Tight-loop cryomodule manufacturing and testing process**
- **Need to train personnel to be experts in linac construction, commissioning and operation**
 - **This can only be accomplished by “building” a large enough facility to create a critical mass of people on site**
- **Focus on international collaborations to conduct critical R&D and tests.**
- **Need to educate students who will be building and operating the ILC in the future.**

How does our plan address these goals ?



- The facility we are proposing will be the **primary facility in the world to build and test new ILC CM's for the near future.**
- Several important changes to the Tesla CM design are being planned for the ILC CM. These include a higher gradient, relocation of the quad, shortening of the cavity end-group, and a new tuner design. Also under discussion are different modulators, klystrons, cavity shapes, and other things.
 - Need to test all critical components in realistic operating conditions, prior to design freeze. The “realistic conditions” to include the following four: rf power, mechanical, thermal cycles, and radiation.

ILC S2 recommendation

- **ILC S2 task force (string test) recommends: the minimum size system test needed to confirm the performance of a new design is a single RF unit with ILC like beam.**
 - **ILC RF unit is 3 CMs powered by a 10 MW MBK**
- **Many tests are statistical in nature, a longer string test with several RF units would be better.**

Why beam tests?

- **Cryomodule gradient calibration with beam energy spectrometer; there could easily be a 10% uncertainty in rf calibrations.**
 - **Need energy spectrometer upstream and downstream of CMs.**
- **Many tests can be done at the Horizontal Test Stand. What is missing:**
 - **Beam loading effects;**
 - **HOM excitations;**
 - **Cavity alignment;**
 - **Check static and dynamic heat loads**
- **Allows to train Fermilab personnel by “doing” it.**
 - **Needs to be intellectually stimulating**
 - **Exercises all support departments: controls, instrumentation, utilities, cryo, EE, RF, safety, operations, mechanical**

Total Cost - NML Test Facility



Expenditure Description	M&S	SWF	Total Including Indirect
NML Conventional Facilities	\$ 720.00	\$ 445.50	\$ 1,422.32
NML Cryogenic System	\$ 2,400.00	\$ 3,334.50	\$ 7,163.53
NML RF Power System	\$ 2,900.00	\$ 1,849.50	\$ 5,800.98
NML Auxillary Systems	\$ 530.00	\$ 472.50	\$ 1,236.33
NML Operations	\$ 400.00	\$ 1,080.00	\$ 1,880.58
NML LLRF	\$ 710.00	\$ 3,294.00	\$ 5,141.63
NML Controls	\$ 940.00	\$ 4,711.50	\$ 7,266.22
NML Instrumentation	\$ 1,510.00	\$ 2,875.50	\$ 5,525.48
NML Injector/Laser	\$ 1,230.00	\$ 1,323.00	\$ 3,165.82
NML Accelerator	\$ 250.00	\$ 796.50	\$ 1,334.51
NML Test Beamlines	\$ 990.00	\$ 999.00	\$ 2,461.84
NML Support Equipment/Systems	\$ 2,340.00	\$ 1,431.00	\$ 4,600.42
NML Building Extension	\$ 3,350.00	\$ 607.50	\$ 4,698.45
Total NML Infrastructure	\$ 18,270.00	\$ 23,220.00	\$ 51,698.11

- Includes FY07 - FY09
- Assumes FY07 M&S funding of ~ \$4M
- Cost given in FY07 dollars
- Does not include escalation or contingency

NML cost drivers




- **Cryogenics (J. Theilacker's talk): \$7.2M** – The temporary 1.8K system is needed to start the program. A new cryo plant is needed by FY09.
- **RF power (M. Champion's talk): \$5.8M** – Not included in our request is the SLAC contribution, which is essential for making the system test.
- **LLRF and controls (B. Chase' talk): \$12.4M** -- Very labor-intensive. Switching to a new controls system.
- **Instrumentation (M. Wendt's talk): \$5.5M** -- Substantial development effort required.
- **Injector and test beam lines: \$6.9M** – Much already exists at A0, but a lot more is needed.
- **Building extension (\$4.7M)** is needed to fit the system test.
- **Support systems (\$4.6M):** safety, alignment, vacuum, cable pulls etc.

NML



- **NML is a facility to be located in the existing building at Fermilab (New Muon Lab)**
 - The New Muon Lab building is not large enough to accommodate 3 cryomodules and need to be extended by FY09
- **New Muon Lab building is part of Fermilab's ILC Test Areas (ILCTA_NM)**
 - Other areas are: MDB (horizontal SCRF cavity test stand), IB1 (vertical test stand) etc.
- **The first NML users will be the ILC program.**
 - The cryomodule tests are also essential to HINS ($\beta=1$)
 - The Accelerator R&D (AARD) portion will first piggy-back on these programs; its share will increase with time

Location



New Muon Lab building



Fermilab



Feb 13-14, 2007

DOE SCRF Review (S. Nagaitsev)

12

NML inside (before)



NML inside (now)



NML: north side




Outline of our plans



- **Cryomodule delivery**
 - 1st (Type 3+) cryomodule is planned to be delivered in fall, 2007
 - 2nd (Type 3+) CM – summer 2008
 - 3rd (ILC Type 4) CM – Mid FY09
 - Replace all three CMs with ILC Type 4+ in FY2010
- **The NML facility will start as a Cryomodule Test Stand in FY07-08**
- **FY08: add beam; start civil construction of the building extension**
- **Convert to an ILC RF Unit beam test facility in FY10**
- **Construct a separate Cryomodule Test Stand (no beam) in FY10. Location TBD.**

Stage 1: 1st CM (end of CY07)





ILC-like beam?




Fermilab

- **3.2 nC/bunch @3 MHz, up to 3000 bunches @ 5Hz**
- **Bunch length: 300- μ m rms**
- **Transverse emittance: not important (\sim 5 μ m)**
- **Energy: 30-40 MeV (to avoid overfocusing in the CM operating at 31 MV/m)**
- **Need “known and frozen” beam parameters at the cryomodule entrance**
- **The AARD program requires more flexibility, mostly in terms of peak current.**

Current Photoinjector Layout at A0



Proposed NML Injector Layout



- Rf-gun
- 40-50 MeV injector
- Bunch compressor chicane
- Off-axis beam line (dogleg w tunable R56)

Possible test area
(can be invasive)
(intended initially for ILC
crab cavity tests)

P. Piot

Photoinjector Upgrades for NML




- **Laser** - no additional major upgrades for NML
- **Egun** – entirely new – similar to DESY(PITZ) egun design; capable of ILC beam parameters
- **Egun modulator** – upgrade: 1 Hz → 5 Hz; 300 msec → 1 msec
- **Beamline** – higher energy → decreased space-charge
- **3rd harmonic cavity** – shorter bunch length; higher peak current
- **Instrumentation** – upgrade
- **Off-axis beamline** – addition of a 4-dipole dogleg will provide an off-axis beamline for testing ILC crab cavities, emittance exchange experiment, and other tests
- **Better integrated controls system**

Other beamline elements needed



- **High-energy beamline elements (downstream of CMs)**
- **A beam dump (50 kW at final stage)**
- **A spectrometer magnet(s)**
- **Cryomodule instrumentation (and other devices)**
- **New beam instrumentation**
- **Machine protection system**


Two CMs with beam



The existing building is perfect for testing two cryomodules with ILC-like beam. The building can be extended to fit 3 cryomodules.

Can we fit 3 CMs?

- With 3 CMs, the space available for the injector is ≤ 10 m.
 - Possible, but injector is compromised;
 - Many ILC studies impossible;
 - AARD impossible.




● BPM pair

X instrumentation cross

▲ current monitor

- Energy low (18 MeV), can not get 300-um, no room for instrumentation

Building extension



- **Construct a new building ~50m away from NML. Connect by a tunnel when schedule allows. Move loading dock.**
- **ILC-like tunnel, space for 3 more cryomodules**
- **Room for a new cryoplant (see Jay's talk)**

New Cryo Plant

- **Temporary cryo system (being installed now):**

NML Stage		# of Tev Satellite refrigerators	
		1	2
1	PI + Single ILC Cryomodule	1 Hz	5 Hz
2	PI + Two ILC Cryomodules	n/a	5 Hz
3	PI + Single ILC RF Unit	n/a	< 2 Hz

- **New Cryo plant**
 - **Must be flexible to allow a wide range of heat loads, including 5-Hz operation**
 - **Must meet specifics of the ILC operating temperature levels of 2.0 K, 5 K, and 40-80 K**
 - **Long lead time**
- **Requires a 15m x 25m building; the plan is to combine it with the NML extension.**
- **Engineering studies complete, have a quotation.**
 - **See Jay's talk**

ILC plans at NML



1. **Demonstrate stable long-term high-gradient beam operation at ILC-like bunch parameters.**
2. **While operating at high gradient and ILC-like beam currents, demonstrate a LLRF controls system such that the beam energy and beam phase stability meet the ILC specs.**
3. **Evaluate effects of cavity gradient spreads, dark current, cryogenic load, radiation levels with beam operation.**
4. **Measure beam kicks due to couplers, cavity tilt, quad rotations + tilt errors characterize focusing properties of SCRF cavities.**
5. **Measure vibrations of cavities and quads.**
6. **Test beam diagnostics.**
7. **Test ILC crab cavities.**
8. **Test the ILC installation procedure and tunnel layout.**
9. **May evolve into a near-final system integration test.**

A facility to test ILC baseline and alternative designs




- Many groups in the US and world-wide are looking for a place to test their ILC-related designs.
 - Need beam at 200-800 MeV, need space to set up tests
- Baseline design:
 - “Keep alive” positron source (ANL)
 - SC undulator (Cornell)
 - Crab-cavity (SLAC, Cockcroft Inst)
- Alternative designs:
 - New HOM coupler design (MIT)

AARD plans


- The existence of the NML facility provides the opportunity to conduct an AARD program
 - Had a workshop in Nov 2006
- Fermilab wants to establish an AARD program at NML.
 - In this proposal, we are not asking to fund the AARD program at NML.
- Flexible beam injector needed to support various beam parameters (emittance, bunch charge, bunch length)
- **Unique beam parameters anticipated:**
 - Record high peak current of 14kA possible
 - ~30 um beam spot size (FWHM)
 - Beam energy up to 800 MeV
 - Structure: 3000 bunches or a witness bunch 300 um behind

AARD plans

- Number of AARD experiments possible in NML itself:
 - one at low energy (50MeV), one-two at full energy (space!)
- Building extension needed to provide area for 4-7 more



Collaborations



NML collaborations



- **SLAC: RF power dist system, 10 MW Klystron; crab cavities;**
- **DESY: too many topics to list;**
- **KEK: rf gun, diagnostics;**
- **ANL: controls, AARD;**
- **INFN: photo cathode;**
- **Rochester: laser;**
- **NIU: AARD, injector;**
- **Cockcroft Inst.: crab cavities**


Cryomodule Test Stand



- We know we will need it eventually. ...Need by FY2010-11
- Location yet undetermined
- A 500 sq meters, 32m x 16m, building required. Includes some utility and access space
- Much larger than a typical Fermilab magnet test stand due to the shielding cave
- Comparable in scope to Stage-1 of NML
- Motivations for cryomodule tests
 - Mechanical checks
 - Alignment of tubes, flanges, etc.
 - Leak checks of all volumes
 - Conditioning of main RF-couplers
 - Cryo load measurement, Q and Eacc
 - SC magnet power test
 - Dark current measurements



XFEL Module R&D Test Stand

From Yury Bozkho, Bernd Petersen (DESY)



Module Test Stand (Lutz Lilje, DESY)

- Allows cryogenic tests and RF measurements independent from the LINAC
 - No beam tests
 - Dark current measurements



Summary

- **Fermilab plans to create the NML facility to test the ILC RF unit (3 CMs) with beam at ILC-like parameters by FY10.**
 - **Planning and engineering designs underway**
 - **Building extension and new cryo plant are needed to meet demands of users (ILC, AARD).**
- **Plans to use the NML for accelerator research and training; develop partnerships with NIU and other local universities. Collaborations with SLAC, KEK, DESY and ANL.**
 - **Building extension required to make it a users facility with competitive and flexible beam parameters.**
- **Plan to construct a new Cryomodule Test Stand by FY10-11.**