

# ILC Cavity and Cryomodule Overview

**Shekhar Mishra**

Fermilab

---

# Outline



- **Motivation and Goals**
- **Infrastructure for Cavity Fabrication, Processing and Testing**
- **Infrastructure for Cryomodule Fabrication**
- **Proposed Scope of the facility**
- **Present and Developing US SRF Infrastructure**
- **Future SRF Infrastructure @ FNAL**
- **Summary**

Focus on Charge 2 and 3

Generic infrastructure is needed, ILC sets the scale

# International SRF Collaboration



## US SRF Collaboration

- Fermilab
- Jlab
- Cornell
- ANL
- LANL
- MSU
- SLAC
- Universities

S. Mishra (FNAL)  
H. Padamsee (Cornell & SRF collaboration)  
J. Mammoser (JLab)  
M. Kelly (ANL)

R. Kephart, FNAL, Regional Interest & WBS 7  
S. Ozaki, BNL, Regional Interest  
T. Tajima, LANL  
R. York, MSU  
Nigel Lockyer, UPenn, University Groups  
G. Gollin, UIUC, University Groups

Co-ordinate with Main Linac Accelerator Physics and RF  
P. Tenenbaum (SLAC) and N. Solyak (FNAL)  
C. Adolphsen (SALC) and S. Nagaitsev (FNAL)

# Technical Goals



- **Demonstrate the basic ILC Main Linac technology**
  - Develop cavity processing parameters for a reproducible cavity gradient of 35 MV/m; improve the yield of 9-cell cavities for gradient of 35 MV/m in vertical tests (S0.1).
  - Carry out parallel/coupled R&D on cavity material, fabrication, and processing to identify paths to success (S0.2).
  - Assemble and test several cryomodules with average gradient > 31.5 MV/m (S1).
  - Build and test one or more ILC rf units at ILC beam parameters, high gradient, and full pulse rep rate (S2.1).
  - Carry out Key Alternate Design R&D item
    - GDE wants a “forward looking” approach
    - Improve ILC performance, reduce cost
- **Install Sufficient Infrastructure to support these activities**

# Goals for SRF Infrastructure



- To perfect U.S. fabrication & processing of SRF cavities and modules and to demonstrate performance with a full range of testing
  - Deploy ILC design / processing / assembly techniques
  - Establish process controls to reliably achieve high gradient cavity operation and module performance
  - Test cavities and cryomodules at the component level and in a systems test to demonstrate yield, reproducibility and beam performance
- Facilitate commercial production of SRF components and modules
  - Train and transfer SRF technology to the US industry
  - Allow industrial participation and input to the process
- Participate in SRF Research and Development
  - Develop expertise in SRF technology and provide training base for construction and operation of future accelerators
  - Our attempt to fit into the world's SRF community
- All of this work will be carried out with US/international collaboration
- **US and Fermilab to be a**
  - **“Credible” and “Qualified Host” of ILC**

# Infrastructure for Cavity and Cryomodule Fabrication, Testing



- **Bare cavity production**
  - Niobium QC
  - Fabrication facilities (e.g. Electron beam welders)
  - Buffered Chemical Polish facilities (BCP) for cavity parts pre-welding
- **Pre-Production Cavity Processing**
  - Tuning for field flatness
  - Surface Processing (Tumbling, BCP and Electro Polishing)
  - Ultra clean H<sub>2</sub>O & High Pressure Rinse systems
  - Furnace for 600 – 800 C bake (removal of H)
- **Vertical Test facilities (Cryogenics + low power RF)**
- **Cavity Dressing Facilities (cryostat, tuner, coupler)**
  - Class-10/100 clean room
- **Horizontal cavity test & Coupler test facilities (RF pulsed power)**
- **String Assembly Facilities**
  - Large class-100 clean rooms, Large module assembly fixtures
  - Class-10 enclosures for cavity inner connects

# Cavity and Cryomodule




Figure 1: Sketch of the work-flow during an accelerator module assembly.

# Proposed Scope : ILC-ART Program



## Focus on Crucial R&D

- **Cavity R&D (S0 goals)**
  - Cavity ( 24 FY07, 64 (08), 64 (09) )
    - **Material QC, Fabrication, Tuning**
  - Cavity Processing ( x 3 number of cavities)
  - Cavity Vertical (Low Power) Testing
  - Cavity Horizontal (High Power) Testing
  - Cavity failure analysis (Improve yield)
  - ACD Shapes and Material
- **Cryomodule R&D (S1 and S2 goals)**
  - Design and Fabrication (2 (FY07), 4 (08), 4 (09))
- **Infrastructure**
  - Cavity Tuning
  - Pre-Production Cavity Processing Facility at Fermilab
  - RF Unit Test Infrastructure at Fermilab (With Beam)
  - Cryomodule Test Stand



# ILC Cryomodule Production (RDR)



A Sample Cryomodule Production Schedule  
for One Region




FIGURE 6.3-3. A possible model schedule for cryomodule production shows 1/3 of the required ILC cryomodules produced in one of three regions. R&D and pre-series devices lead to 5 years of series production (yellow). The position and magnitude of the peak of series production will vary with changes to the available construction and test infrastructure.

# Proposed Scope: Ozaki Panel Report




## Develop US Capability

- **Cavity R&D (S0-S1-S2)**
  - US Industrial Development (49 (FY07), 125 (08), 219 (09))
- **Cryomodule R&D (S1-S2)**
  - Industrial Development (3 (FY07),12(08),12(09))
- **Development of SRF Infrastructure**
  - Cavity Tuning
  - Pre-Production Cavity Processing Facility at Fermilab
  - RF Unit Test Infrastructure at Fermilab (With Beam)
  - Cryomodule Test Stand
  - Cavity Fabrication (Electron Beam Welder, etc)
  - Cryomodule Fabrication (Industry Technology Transfer)
  - Vertical and Horizontal Test Stand
  - Cryogenic to support the test stand

# US Program (ILC-ART & OPR)



## Cavity and Cryomodule Production



# Present: US SRF Infrastructure







- **Limited cavity fabrication capability in US industry**
  - One US company (AES) fabricating SRF cavity
  - Developing two new companies (Niowave and Roark)
    - European Industry much advanced in ILC cavity fabrication
- **Cavity Processing and Vertical Testing R&D Facility**
  - Jlab (~30 FY07, ~40 FY08, ~50 FY09) cycles/yr
  - ANL/FNAL ( ~50 FY08, ~60 FY09) cycles/yr
  - Cornell ~12 cycles/yr
  - VTS @FNAL ~50 cycles/yr (late FY07)
  - **Significant fraction of this capacity is used to support R&D Program**
    - Process development
    - Single cell Processing
- **Horizontal Test Stand**
  - FNAL ~24 cavities/yr
- **Cavity Dressing and Cryomodule Assembly**
  - FNAL 2-4/yr (FY07)

# Scope: US Laboratories Capacity



Program	FY07	FY08	FY09	FY10	Capacity Needed/yr by FY10
<b>Cavity Processing (EP, HPR, Bake) Cycles/yr</b>	Jlab-30 Cornell-10	Jlab-40 Cornell-10 ANL-40	Jlab-40 Cornell-10 ANL-40 Fermilab-20	Jlab-40 Cornell-10 ANL-40 Fermilab-100	200
<b>Vertical Testing</b>	Jlab-30 Cornell-10 Fermilab-20	Jlab-40 Cornell-10 Fermilab-75	Jlab-40 Cornell-10 Fermilab-75	Jlab-40 Cornell-10 Fermilab-200	200
<b>Horizontal Testing</b>	Fermilab-6	Fermilab-24	Fermilab-24	Fermilab-72	72
<b>Cryomodule Assembly</b>	Fermilab-1	Fermilab-4	Fermilab-8	Fermilab-12	12
<b>Cryomodule Test</b>	Fermilab: ILCTA_NML	Fermilab: ILCTA_NML	Fermilab: ILCTA_NML	Fermilab: ILCTA_NML CMTS	12

# Proposed: US Laboratories Capacity



# Scope: Fermilab SRF Infrastructure



- **Cavity Fabrication**
  - Increased cavity fabrication R&D and training US industry
    - Electron Beam Welder
    - Eddy Current Scanner
  - Automated Cavity Tuning
    - 100+ Cavity/yr ( by FY09)
- **Cavity Processing Facility (Pre-Production Facility, existing technology with industry, modular and redundancy)**
  - 100+ Cycles/yr (by FY09)
- **Vertical Testing**
  - Additional 100+ Cavity/yr (by FY09)
- **Horizontal Test Stand**
  - Additional 48 Test/yr (Maximum US Capacity needed)
- **Cryomodule Assembly**
  - 1 per month
- **Material R&D**

# Breakout Session I - Cavity/CM



- **Elliptical Cavities - M. Foley**
- **Cavity Processing, Current Facilities, Plans for Future Facility, H. Carter**
- **IB1 Infra - Vertical Test Facility and Future Upgrades - C. Ginsburg**
- **CCII Results and Horizontal Test Facilities - A. Hocker**
- **Cryomodule Assembly Facility - T. Arkan**
- **SCRF Materials Program - C. Antoine**




# Cavity Fabrication

- Present US Cavity production is through
  - Niobium QC at Fermilab, Jlab
  - Advanced Energy System, ACCEL, Zanon
  - Jlab (Cavity and Material R&D)



Fermilab does not have the infrastructure to


- Train and develop a new vendor
- Carry out cavity R&D.
- Auto Tune Cavities



# Proposed: Cavity Fabrication Infrastructure



- The following infrastructure are proposed for the Cavity R&D and Technology Transfer
  - **Electron Beam Welder**
    - Prototype Cavity development
    - Cavity fabrication R&D
    - Industry Development
  - **Eddy Current Scanner (2<sup>nd</sup> to increase throughput)**



Cavity Fabrication Infrastructure: \$4.38M

# Cavity Gradient: 35 MV/m



- At present, there is good proof-of-principle that 9-cell cavities reach gradients of 35 – 40 MV/m after applying the best preparation procedures
  - Electro-polishing (EP),
  - High Pressure Rinsing (HPR)
  - Baking at 120 C.
- DESY has tested (~5-10) cavities with gradients of ~35 MV/m,
  - Yield is less than 0.5,
  - Gradient spread is large ( $\pm 25\%$ )
  - Average number of preparations and test cycles per cavity is three.
- Cavity fabrication and processing R&D is needed to achieve an overall yield  $> 80\%$  in the first test of cavities and 95% ultimate in two tests for cavities
  - Limited by preparation and processing.

# Yield Improvement: 35 MV/m



- **The yield improvements would come in a few stages**
  - Input from R&D activities becomes incorporated into the 9-cell preparation
  - Testing batches for each stage.
- **Dramatic improvement in yield and spread will require coupled R&D programs in parallel to large scale testing of 9-cell cavities.**
  - Basic R&D on the preparation recipes
  - Materials R&D
  - Diagnostics on EP, HPR, VTS systems
  - Multi-cell tests with full diagnostics
  - Single cells preparation/tests
- **Present Limiting Factors:**
  - Field emission
  - Quench
  - Hydrogen initiated Q-disease.
- **Existing Procedure needs optimization and we need to explore any promising procedures that reduces these effects. Some examples are:**
  - Improved methods of final rinsing
  - New final rinsing agents
  - Stringent control of cleanliness during assembly
  - Processing field emission with high pulsed power RF.

# Cavity Processing and Testing



- **The present US cavity R&D is using**
  - **Distributed Cavity Processing and testing infrastructure**
  - **This is an ideal way to get started with very limited resources to make significant progress towards the ILC R&D goals.**
- **The production of high-performance SRF cavities will require state-of-the-art surface preparation.**
- **We are proposing build additional facility at Fermilab, We already have**
  - **Existing infrastructure and significant engineering resources**
  - **Low and High Power Cavity Test Facilities**
  - **Cryomodule Assembly Facility**
  - **Cryomodule Test Facility With and Without Beam**
- **An integrated facility will be needed**
  - **For significant improvement of the current preparation**
  - **Steps towards an industrial production-like level**
  - **A large enough throughput (~100 cavities/yr)**

# Cavity Preparation Infrastructure



- **The proposed infrastructure will improve over the existing infrastructures**
  - **Present infrastructures are single-line processing R&D infrastructure**
    - **Failure in one process chain leads to unacceptable delay in schedule**
  - **New Infrastructure will have**
    - **All cavity processing under one clean environment**
    - **Redundancy in layout**
    - **Modularized for maintainability and flexibility**
    - **Flexibility: Implementing change in the overall production scheme**
    - **Quality Assurance and control process**
    - **Available for use for other projects**

# Model: Processing and Testing Infrastructure



- Degrease & EP 80 um (3 days)
- HPR 1 day
- Drying 1 day
- H-removal, 600 – 800 C (3 days)
- Tune field flat (1 day)
- EP 10 um (1 day)
- HPR (1 day)
- dry (1 day)
- First stage assembly & HPR (1 day)
- Dry 1 day
- Final assembly to bake stand, evacuation (1 day)
- 120 C on bake stand (2 days)
- Assembly to test stand (1 day)
- Cold test, warm up (3 days)


Total 21 days (4 weeks)

Test set-up has maximum 4-day, rate limiting time

- Assume one set-up each per facility
- Max cycles = 5 per month (20 days) = 60 per year
- Down time and maintenance time may reduce this
- Calculation Estimates: 50 per year max
- Jlab estimates : 40/year

## A R&D Model

### Cavity Processing



As defined by ILC-ART & OPR

# Schematic of Cavity Processing Facility



Each EP, HPR .. System can do ~40 cy/yr

Tuning Tank welding Oven

- EP Systems: 2 (1 Spare)
- HPR Systems: 2 (1 Spare)
- BCP Systems: 1 (1 S)
- Vacuum Furnaces: 2
- Low Temp Furnaces: 2
- Cavity Tuning: 1
- Tumbling: 1
- Clean Rooms




Figure 2: Sketch of the cavity preparation infrastructure.



European Infrastructure Proposal

Cavity Processing Facility \$18.9M




# Present: Vertical Test Facility-1

- A Vertical Test Stand is under Construction at Fermilab (IB1)
  - Existing Cryogenic plant in IB1 has the capacity of 125 W at 2 K (250 W available for intermittent test)
  - Test Stand will be capable of testing ~50 Cavities/yr
  - Commissioning late summer 07



# Proposed: Vertical Test Stand 2 & 3

- To increase the capacity of the VTS
  - Upgrade the VTS-1 for 2 cavity operation (~75 cy/yr)
  - Add 2 more VTS pits (VTS-2 and VTS-3) (~200 cy/yr)
  - Upgrade the cryogenic infrastructure (decouple from superconducting Magnet test)
  - Upgrade the cavity staging area
- To support cavity R&D: Field emission studies and Quench Location



Vertical Test Stand 2 & 3: \$5.5M

# Present: Horizontal Test Stand - 1




- Horizontal Test Stand -1 is getting ready for commissioning at Meson.
  - The maximum capacity of this test stand is ~24 cavities/yr
- It will be debugged with a cavity from DESY in early spring.
  - This cavity is getting prepared by Jlab.
- The commissioning of the HTS will happen with AC7 (9-cell, 41 MV/m) cavity.
  - Coupler from DESY
  - Tuner and He Vessel from INFN to Penn, Getting commissioned at Penn
  - Will be dressed at Jlab






# Cavity Testing Infrastructure




RF Power for HTS



Cryogenics for HTS ready at 2 K



Cryogenics for HTS getting ready for 2 K



Capture Cavity

# Proposed: Horizontal Test Stand - 2



- We proposed to build a second Horizontal Test Stand at Fermilab and install it next to HTS-1.
- The HTS-2 will have the capability to cool down and test 2 9-Cell cavities at a time.
  - This will enable us to increase the throughput to 72 cavities/yr
  - It will also allow development of RF controls using multiple cavities.

Horizontal Test Stand 2: \$2.8M

# Present: Cryomodule Assembly Facility MP9 and ICB



## CAF infrastructure:

- Clean Rooms (10,100,1000)
- String Assembly Fixtures
- Vacuum / Ultra Pure Gas Flow Equipment/ Hardware
- Ultrasonic Cleaner
- Ultra pure DI water
- Cavity Handling Cart / Fixture
- Cold Mass Assembly Fixture







# Proposed: CAF (MP9 and ICB) Upgrade




- CAF can be used for small scale mass production assembly area for cryomodules. With the fixtures / tooling procured & installed in FY07.
  - ILC R&D quantity Cryomodules can be assembled at CAF.
- To increase the assembly capacity to **1 cryomodules per month**, get industry involved, additional infrastructure will be needed for CAF, especially for CAF-ICB.
  - Cold Mass Assembly Fixture
  - Vacuum Vessel Assembly Fixture
  - Rail System for Cavity Support
  - Tooling



Cryomodule Assembly Facility (MP9 & ICB): \$1.2M




**Forming Problems at AES:**  
*Nb too hard, spring back, 6 passes vs 1, ovalization...*



Deviation from circular shape


Microstructure & Mechanical Properties studied (MSU):

- **Diagnostic: non fully recrystallized material**
- **Recommendations**
  - Re-annealing of the batch (~ 200 sheets)
  - QA : delivered material should meet tightly specifications
  - We must work with the suppliers to help them to meet specification



**Antenna breaking in HOM coupler**

- **Diagnostic: brittle fracture, but precursor cracks during processing ?**
- **Recommendation**
  - We need to know better cold and room temperature mechanical properties of Nb








# Material Characterization : Mechanical, surface chemistry



## Systematic testing of new batches (QA) + Failure analysis

- RT and Cold mechanical properties
  - data for modeling (forming, mechanical resistance , RF behavior...)
  - Recrystallization study (post doc student) => improving specifications for Nb
  - Crystal orientation/texture effects...
- Rapid SIMS characterization
  - High detection sensitivity (metal or non-metal)
  - Spatial resolution 10  $\mu\text{m}$  (horizontal) and 1 nm (depth)
  - Large size sample (100 mm round )
  - Very robust/reproducible analysis conditions => allows to gather statistics
- Additional benefit
  - Hydrogen, oxygen embrittlement at low temperature
  - Effect of welding (mechanical, chemical)
  - Grain boundary strength, composition
  - Oxide layer study
  - Weaker layer study/Coating study



Material R&D: \$1.96M

# Required Funding



Infrastructure	M&S	SWF	Total with Indirect
Cavity Fabrication Infrastructure	\$ 3,000	\$ 675	\$ 4,380
Cavity Processing Facilities	\$ 11,100	\$ 4,590	\$ 18,945
Vertical Test Stand (VTS 2 & 3)	\$ 2,625	\$ 1,845	\$ 5,475
Horizontal Test Stand (HTS 2)	\$ 1,220	\$ 1,057	\$ 2,805
Cavity/Cryomodule Assembly Facilities (CAF_MP9 & ICE)	\$ 690	\$ 270	\$ 1,158
NML Facility (ILCTA_NML)	\$ 18,270	\$ 23,220	\$ 51,700
Cryogenics for Test Facilities	\$ 10,690	\$ 950	\$ 13,692
Cryomodule Test Stand	\$ 5,400	\$ 2,970	\$ 10,180
Material R&D	\$ 870	\$ 722	\$ 1,960
Illinois Accelerator Research Center	\$ 20,000	\$ 4,050	\$ 28,605
<b>Grand Total (\$k)</b>	<b>\$ 73,865</b>	<b>\$ 40,349</b>	<b>\$ 138,900</b>

Cavity and Cryomodule Fabrication and Testing Infrastructure ~\$34.7 M

# Summary



- **The Main Linac Cavity and Cryomodule R&D program and Infrastructure development as presented would**
  - **Impact and contribute toward the critical ILC R&D as proposed by ILC Task Forces**
  - **Build a minimal facility at Fermilab**
  - **Train people in SRF at Fermilab**
- **Get the US industry involved from the initial phases**
- **Position US and Fermilab to be a “Credible” and “qualified host” of ILC**

**We request a strong support for the full program**