

Fermilab Vertical Cavity Test Facility

**Accelerating RF cavities for the ILC Main Linac
Superconducting RF Technical Challenges
Vertical Cavity Test Facility**

Part 1




The What and the Why

The ILC design today



ILC RDR




ILC Specifications

- q Initial center-of-mass energy up to 500 GeV, upgradeable to 1 TeV
- q Ability to scan in energy between 250 and 500 GeV
- q Integrated luminosity in the first four years 500 fb⁻¹ at 500 GeV
 - q Peak luminosity $2 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$, 75% duty factor

Main Linac

- q Two 11-km linacs, one for electrons and one for positrons
- q Accelerate from injected energy of 15 GeV to the final beam energy of 250 GeV
- ~**16000** 1.3 GHz superconducting RF cavities, operating at average gradient **31.5 MV/m**




The SRF cavities

A TESLA 9-cell 1.3 GHz superconducting niobium RF cavity



this cavity today costs 75 k\$

1 ILC unit = 1 US 2007\$




- q SRF cavities constitute a huge portion of the total ILC cost
- q Also, a big technical challenge

From Cavity to Accelerator



Kephart




Reasons for Vertical Cavity Testing


q Acceptance test before further assembly

- q Currently difficult to get $\langle E_{acc} \rangle$ of >31.5 MV/m...
- q Vertical testing goes hand-in-hand with surface processing

Use to confirm technique effectiveness



difficult to reach $\langle E_{\text{acc}} \rangle > 31.5 \text{ MV/m}$



- q DESY/TTF data
- q Vertical cavity tests
all tests, all cavities
Mar 1993 - Jan 2006
- q $\langle E_{\text{acc}} \rangle$ increasing with
time
- q Significant spread all
years
- q Technical challenge!

Improve Gradient Reproducibility



- The need of making gradients more reproducible is a top priority
 - “S0” Goal: Achieve **35 MV/m at $Q_0=10^{10}$ in 9-cell cavity in vertical dewar tests (low-power)** with a sufficient yield (> 90% for more than 100 preparation and test cycles). Two parts:
 - S0.1: Tight loop to improve “final preparation” yield
 - S0.2: Production-like activities to determine overall yield for cavity materials, fabrication and full cavity processing
- S0/S1 Task Force
 - E. Elsen (DESY), Lutz Lilje (DESY, chair), H. Hayano (KEK), T. Higo (KEK), J. Mammosser (JLab), A. Yamamoto (KEK), H. Padamsee (Cornell), M. Ross (FNAL), Kenji Saito (KEK), Bill Willis (Columbia),
 - New: P. Pfund (FNAL) Task Coordinator and CMG (FNAL) Principle Investigator
- Goal: Multiple facilities get the same results for equivalent surface treatments

What a Vertical Cavity Test is



- **Make the cavity superconducting (2K)**
 - Put the cavity, in a **vertical orientation**, in a dewar
 - Fill the dewar with liquid helium (4K)
 - Pump on the helium bath to cool the cavity to 2K
- **Put RF power with an antenna into the cavity, with appropriate resonant frequency (1.3 GHz), turning on and off judiciously**
- **Measure (minimally) as a function of time**
 - P_t transmitted power (another antenna at the other end)
 - P_r reflected power
 - P_f input or forward power
 - Frequency (frequency generator not that accurate)
 - Helium bath temperature
- **Calculate Q, Eacc, etc.**

Vertical Test (1): Q vs. Eacc



Quality coefficient: a measure of the surface material/quality

$$Q_0 = \frac{2\pi f U}{P_d} = \frac{G}{R_s}$$

[dimensionless]

f = RF frequency [Hz]

U = stored energy [J]

P_d = dissipated power [W]

R_s = surface resistance [Ω]

G = geometric factor [Ω]

Accelerating Gradient: depends mainly on the cavity geometry

$$E_{\text{acc}} = (1/L) \int_{z=0}^{z=L} E \, dz$$

[V/m]

L = cell length [m]

z = acceleration axis [m]

E = electric field [V/m]


Vertical Cavity Tests (1)



Test cavity quality (Q vs. E_{acc})

- Study cavity production quality and processing effectiveness
- Cavity acceptance test prior to cryomodule assembly

Z101 Test 2 (at 2K)
March 3, 2006



“typical” Q vs. E_{acc}

Z101 is a 9-cell Tesla-style cavity

onset of field emission

$E_{\text{acc}} \sim 18$ MV/m

X-ray flux measured

with ionization

chamber at top plate


15 yrs of cavity process development



BCP!

Antoine

Magnetic shielding



All tests on the same kind of cavity

KEK - K. Saito *et al.* RFSC ' 89

DESY-CERN-Saclay - L.Lilje *et al.*, TTF report, 1999


Just to give you a flavor for the effects we are looking for!

DESY vertical test data




- q Latest greatest Production 4 TESLA-style cavities tested 2005-2006
 - q All have (almost) the same surface treatment
 - q Nevertheless have significant variation in performance
- Needs study – diagnostic instrumentation important!
Concentrate on quench detection, and field emission

Production 4 cavities



Vertical test (2): Surface Resistance

- q To support RF fields in the cavity, currents flow within a thin inner surface layer
- q Superconductivity:
 - Above T_c , all electrons unpaired
 - At $T=0$, all electrons paired (Cooper pairs)
 - As T drops from $T=T_c$ to $T=0$, number of unpaired electrons drops as $\exp(-\Delta/kT)$
- q DC case: energetically favorable for pairs to carry entire current while unpaired electrons remain inert
Zero resistance
- q RF case: pairs have inertia – forces must be applied to accelerate/decelerate
Finite but small resistance, which depends on RF frequency



Superconducting: $R_S(\text{Nb}) \sim 10$'s of $\text{n}\Omega$ (@ 2K)

Normal conducting: $R_S(\text{Cu}) \sim \text{few } 100 \mu\Omega$

Vertical Cavity Tests (2)

Test cavity surface resistance (Q vs. T)


- Measure residual resistance

$$R_S = R_{BCS} + R_{Res}$$

$$R_{BCS} = A(Nb) \frac{(2\pi f)^2}{T} e^{-\Delta/kT}$$

SC: $R_S(Nb) \sim 10$'s of $n\Omega$ (@ 2K)

NC: $R_S(Cu) \sim$ few 100 $\mu\Omega$



Part 2



Vertical Cavity Test Facility Design

VCTF Initial Project Scope



- q One Vertical Test Stand (VTS) in Industrial Building 1
- q Single, bare 1.3 GHz 9-cell Tesla-style cavities
 - q Measure Q vs. T ($T_{\min} \sim 1.5$ K)
 - q Measure Q vs. E_{acc} at 2 K
- q RF design parameter: 250 W (CW) max power at cavity
 - q $Q > 5 \times 10^9$ and $E_{\text{acc}} < 35$ MV/m
 - or generally: $P_d = (1.04 \times 10^{-3}) * E_{\text{acc}}^2 / Q < 250$ W
- q Use existing IB1 cryogenic capacity ~ 125 W at 2 K
 - q 250 W for short periods without excessive helium bath temperature increase
- q Maintain “Controlled Area” radiation status in IB1
 - q < 5 mrem in an hour immediately outside the shielding
 - q < 0.25 mrem/hr in normal working areas

VCTF in Industrial Building 1

Existing IB1 cryoplant/infrastructure for Magnet Test Facility (MTF)


- q **Significant cost savings & faster implementation**
 - q **Current replacement value ~\$10M**
- q **Knowledgeable technical staff**
 - q **4 cryogenic magnet test stands**
FY06: tested 29 superconducting magnets
 - q **3 conventional magnet test stands**
FY06: tested 21 conventional magnets
 - q **Cryogenic engineering, data acquisition systems, diagnostic instrumentation, software and data management, etc.**
- q **Continue to share cryogenic system and IB1 infrastructure with magnet test program**
 - q **Cryogenically demanding LHC magnet production tests are finished**

VTS
pit




VTS Cryostat/Insert Design


Based on Fermilab design of DESY/TTF/VTS
Added phase separator for better quality He



Cryostat






Top plate insert



Cryostat manufactured by PHPK Technologies, Columbus OH

Cryostat photos

September 2006: Cryostat ordered
January 2007: He vessel ASME code stamped
February 2007: Received at Fermilab
March 2007: Temporarily installed
April 2007: Permanently installed
May 2007: Cryogenic Safety Review
Thanks to review panel: W. Soyars (chair), H. Cease, J. Makara
May 2007: First cold test and commissioning



Magnetic Shielding



- q **Surface resistance increases due to trapped magnetic flux in localized normal-conducting surface impurities -> reduces cavity Q**
 - q Existing magnetic field at IB1 floor in pit region measured to be consistent with Earth's magnetic field (~0.5 G)
 - q Shield to <0.01 G at cavity
- q **Two-layer design to shield magnetic field**
 - q Outer room-temp cylindrical shield, attached to vacuum vessel OD
 - q Amumetal[®] (80% Ni alloy) 0.040" thick
 - q Inner 2K cylindrical shield, attached to helium vessel ID, with perforated (for LHe flow) endcap
 - q Cryoperm 10[®] 0.040" thick
 - q Both "permanently" installed in/on cryostat to avoid damage
- q **Constructed by Amuneal Manufacturing Corp., Phila., PA**
 - q Outer shield – complete March 2007, installed April 2007
 - q Inner shield – some issues – complete September 2007

Cavity degradation in B field



$B_0 \rightarrow$ higher surface resistance \rightarrow lower cavity Q

$$Q = G/R_s$$

G = geometric factor

R_s = cavity surface resistance

$$R_s = R_{\text{BCS}} + R_{\text{res}} + R_{\text{mag}} .$$

R_{BCS} = BCS resistance


R_{res} = residual surface resistance due to cavity surface condition

R_{mag} = resistance due to trapped magnetic flux ←

For a niobium SCRF cavity

$$R_{\text{mag}} = 0.3 B_0[\text{mOe}] \sqrt{f[\text{GHz}]} \text{ n}\Omega \quad \text{Padamsee et al.}$$

compilation by Vallet et al.



Outer Magnetic Shield

- Installation April 2007 on outside of vacuum vessel
- cylindrical shape
- 0.040" thick Amumetal[®] (80% Ni alloy)
- length 166", ID 42.125"
- half-cylinder pieces, tightened against vacuum vessel OD using Amumetal[®] joiner bands, PEM fasteners, 304 SS screws
- More support provided by turn buckles between the top of the shielding and vacuum vessel top flange




Magnetic Shielding Measurements

Sergatskov





- magnetic field measured inside cryostat
 - Few fixed depths as probe lowered/raised along plastic guide tube
 - Tube could be positioned in one of 7 locations inside cryostat
 - Multiple successive measurements to determine reproducibility < 0.1 mG (rms)
 - Repositioning error ~ 0.1 mG
- three-axis fluxgate sensor, Mag-03MC1000 (GMW)
 - $B < 10$ G
 - Sensitive: 0.5 mG offset accuracy, noise level ~ 0.01 mG
 - probe was attached to a power supply/controller unit Mag-03PSU, also from GMW, via a 5m cable
 - controller connected to a digital multimeter, read out via GPIB to a LabView® program.



- Measurement results so far
 - Pit with or without cryostat
 - consistent with Earth $B \sim 0.5$ G, few local enhancements
 - Pit with cryostat and outer magnetic shielding (only)
 - $B < 0.05$ G
 - Permeability of outer shield ~ 40000 (close to expected)
 - Pit with cryostat, both inner & outer shielding to be after VTS commissioning

Radiation Shielding Analysis

- DESY data measured over ~12 years,
 ~85 cavities
 X-ray flux measured
- § ~5 cm off axis
 - § above 1" SS top plate
 - § above 50 kg shielding inside cryostat
 - 20 cm Pb + 5 cm Al



Moeller

Radiation Shielding Analysis


DESY Vertical cryostat 2

1m (heavy concrete)

Movable radiation shield shell

0.5m heavy concrete


Cryostat top plate



DESY radiation data



DESY TTF data



Measured x-ray flux above top plate

< 6 R/hr 90% of the time

< 30 R/hr 99% of the time



Always <58 R/hr

Unfortunately, we don't know the radiation geometric distribution

Use as input to
VTS shielding design

Radiation Shielding

- q X-rays estimated from DESY data
Thanks DESY staff!
- q Design from MARS15 simulation
approved by ES&H
(Fermilab-TM-2350-AD)
- q Tritium production negligible
- q “Controlled area” satisfied
- q Assembly complete next week



normal concrete

borated polyethylene, steel

lead

Additional borated poly at
instrumentation trench
opening (not shown)

Rakhno: radiation shielding design
Poloubotko: lid mechanical design

RF/DAQ System

J. Ozelis, R. Nehring



- q **Based on proven Jefferson Lab VTS RF/DAQ system**
 - q RF system with technology advances
 - q LabView-based data acquisition system
 - q **Very user friendly, useful when we have visitors at test stand**

- q **Collaboration with Jefferson Lab established** **Thanks JLab!**
(T. Powers, C. Grenoble)
 - q added to Jefferson Lab MOU

- q **System status**
 - q **Internal Fermilab design review 24 August 2006**
 - q **Thanks to review committee: R. Pasquinelli (Chair), J. Steimel, B. Chase, C. Worel, J. Reid, W-D. Moeller**
 - all reviewers' recommendations incorporated
 - q **RF personnel safety interlocks design (C. Worel)**
 - q approved by ES&H
 - q **RF amplifier (500 W CW) fully characterized (R. Pasquinelli et al.)**
 - q **Low-level RF commissioning ongoing**



VCTF research goals



- q **“Diagnostic” top plate insert, ready to go when high-throughput cavity tests are paused**
 - q **More instrumentation feedthroughs**
 - q **Variable input coupler**

- q **Program will evolve depending on outcome of ongoing R&D. Current proposals:**
 - q **Thermometry for quench location in 9-cells (Mukherjee, Dhanaraj)**
 - q **Field emission studies with x-ray detectors**
 - q **Systematic study of magnetic field on cavity performance**
 - q **Single-cell studies (processing techniques, large grain Nb, other materials, other cavity shapes)**
 - q **“Collaboration” established and developing with Fermilab PPD scientists with instrumentation experience. Anticipate involving others from Fermilab, universities, other laboratories**


- q **Operating VCTF very close to capacity would negatively affect research goals**

KEK field emission data


Kirk Yamamoto




X-ray Mapping Display for STF B.C. #2 (2007/02/23)



ILC B.C. #2 (2007/02/22)



ILC B.C. #2 (2007/02/22)



- q Example of something interesting to do
- q Photodiodes placed around cavity
- q Hamamatsu S1223-01 3.6 mm x 3.6 mm
- q No thermal contact required – simple ass'y
- q Excellent correlation between gradient and x-ray flux; also one FE burn off observed

Part 3



Vertical Cavity Test Facility Operations

Single VTS Test Cycle Duration



| Task | Duration (hours) |
|--|------------------|
| Receive cavity and cage | 0 |
| Mount cage to insert | 1 |
| Connect cables and TDR test | 1 |
| Install insert in dewar | 1 |
| Perform Dewar seal check | 0.5 |
| Perform Dewar leak check | 1 |
| Backfill Dewar, helium contamination check | 0.5 |
| Cool down to 100K, 8 g/sec | 0.5 |
| Wait at 100K for 8 hours (for Q-disease study) | 8 |
| Cool down to 4K | 1 |
| Fill @ 4K | 2 |
| Pump to 2K | 3 |
| RF Test at 2K | 4 |
| Boil off LHe | 4 |
| Warm up Dewar | 17 |
| Remove insert | 1 |
| Remove cavity cage from insert | 1 |
| Total single-cavity test cycle duration | 46.5 |

RF test is ~10% of total test time

46.5 hours becomes 5 days with current infrastructure, primarily due to sharing of people and equipment with magnet test program, and shift schedules

Annual VTS Test Cycle Throughput



| Downtime cause | # days/year | Comments |
|--------------------------------|-------------|---|
| Cryogenic system down | 60 | Largest contribution is system contamination due to air-leaks |
| Pumps unavailable | 24 | Resource sharing with magnet test program |
| LHe supply unavailable | 12 | |
| VTS unavailable | 15 | Cavity-test-stand-specific problems |
| Total equipment unavailability | 111 | |
| Holidays | 10 | |
| Total down days | 121 | Out of 365 days/year |

address these with cryogenic system upgrades

| | | |
|-----------------------|---|---------------------------|
| VTS test cycle (days) | 5 | Includes shift operations |
|-----------------------|---|---------------------------|


| | |
|--------------|----|
| # tests/year | 48 |
|--------------|----|

Projected US Total # Cavity Processes



Each process requires a Cavity Vertical Test

Mishra



Expected VTS throughput 48 tests/year


US Laboratories' GDE request



| Program | FY07 | FY08 | FY09 | FY10 | Capacity Needed/yr by FY10 |
|-----------------------------------|--------------------------------------|--------------------------------------|--|---|----------------------------|
| Cavity Processing (EP, HPR, Bake) | Jlab-30 Cornell-10 | Jlab-40 Cornell-10 ANL-40 | Jlab-40 Cornell-10 ANL-40 Fermilab-20 | Jlab-40 Cornell-10 ANL-40 Fermilab-100 | 200 |
| Vertical Testing | Jlab-30 Cornell-10 Fermilab-20 | Jlab-40 Cornell-10 Fermilab-75 | Jlab-40 Cornell-10 Fermilab-75 | Jlab-40 Cornell-10 Fermilab-200 | 200 |
| Horizontal Testing | Fermilab-6 | Fermilab-24 | Fermilab-24 | Fermilab-72 | 72 |
| Cryomodule Assembly | Fermilab-1 | Fermilab-4 | Fermilab-12 | Fermilab-12 | 12 |
| Cryomodule Test | Fermilab: ILCTA_NML | Fermilab: ILCTA_NML | Fermilab: ILCTA_NML | Fermilab: ILCTA_NML CMTS | 12 |

Add vertical test throughput



increase cavity throughput by > factor of two by FY10



Upgrade VTS for two-cavity operation

Add two more vertical test stands to VCTF

Upgrade cryogenic infrastructure



Part 3



Wrap it up

Project Status

- **Cryogenic system commissioning May 2007**

- System performed very well

Thanks to review panel: W. Soyars (chair), H. Cease, J. Makara

- **LLRF commissioning ongoing**

- Low power, i.e., < 1 W
- Single-cell cavity


- **Integrated commissioning next week**

- 9-cell cavity from JLab (or use 1-cell)
- Radiation shielding movable lid complete
- RF interlocks (personnel safety) complete
- Operational Readiness Clearance/Safety Assessment Document complete



View from today

- Radiation shielding lid is now there
- Making it movable on rails with a motor
 - In progress



Conclusions



- q **Vertical Cavity Test Facility with one Vertical Test Stand well underway, to be operational in FY07**
 - q **Will establish Fermilab as an ILC cavity testing facility**

- q **Develop Fermilab SRF expertise**
 - q **Study cavity characteristics**
 - q **Develop cavity diagnostic instrumentation**
 - q **Apply advances to new projects**
 - q **Collaborate with university groups & other labs**
 - q **Accommodate visitors with user-friendly facility**

- q **Success: Even before the project is complete, made upgrade proposal**
- q **Upgrade proposal based on analysis of existing system capability**
 - q **Inputs: Considerable experience from Fermilab Magnet Test Facility, and cavity test operations information from other labs**
 - q **Cryo upgrade planned for FY08**
 - q **Additional VTS's planned for FY09**

- q **Advance Fermilab's role in advancement of SRF technology**

Acknowledgements/for more information



C. Antoine, AD/TD Seminar February 22, 2007

http://beamdocs.fnal.gov/DocDB/0026/002667/001/T_Fermi_Seminaire-2006.ppt

R. Kephart, DOE SRF Review, Feb.13-14, 2007

<http://ilcagenda.linearcollider.org/getFile.py/access?sessionId=2&resId=0&materialId=0&confId=1347>

ILC RDR:

http://media.linearcollider.org/rdr_draft_v1.pdf

http://www.linearcollider.org/pdf/RDR_Machine%20Overview_v5-1.pdf

Thanks Cornell, DESY, JLab, KEK, Saclay!

Thanks for strong support of IB1 Technical Staff!

VTS Group: CMG (Project Physicist), Cosmore Sylvester (Project Engineer)
R. Carcagno (IB1 Infrastructure Project Leader), Y. Huang, R. Nehring, B. Norris,
J. Ozelis, V. Poloubotko, R. Rabehl, I. Rakhno, C. Reid, T. Peterson, M. Wong,
C. Worel, A. Yuan

Important VTS contributions: C. Brown, A. Lunin, A. Mukherjee, O. Prokofiev,
D. Sergatskov, TD Support Department