



# GDE Status / Plans & ILC Timeline

**Barry Barish**

***FALC***

*11-July-07*



# The GDE Plan and Schedule

2005



2006

2007

2008

2009


2010





# RDR ILC Schematic

- 11km SC linacs operating at 31.5 MV/m for 500 GeV
- Centralized injector
  - Circular damping rings for electrons and positrons
  - Undulator-based positron source
- Single IR with 14 mrad crossing angle
- Dual tunnel configuration for safety and availability





# RDR Design Parameters

|                               |                         |                     |
|-------------------------------|-------------------------|---------------------|
| Max. Center-of-mass energy    | 500                     | GeV                 |
| Peak Luminosity               | $\sim 2 \times 10^{34}$ | 1/cm <sup>2</sup> s |
| Beam Current                  | 9.0                     | mA                  |
| Repetition rate               | 5                       | Hz                  |
| Average accelerating gradient | 31.5                    | MV/m                |
| Beam pulse length             | 0.95                    | ms                  |
| Total Site Length             | 31                      | km                  |
| Total AC Power Consumption    | $\sim 230$              | MW                  |



# RDR Design & “Value” Costs

The reference design was “frozen” as of 1-Dec-06 for the purpose of producing the RDR, including costs.

It is important to recognize this is a snapshot and the design will continue to evolve, due to results of the R&D, accelerator studies and value engineering

The value costs have already been reviewed twice

- 3 day “internal review” in Dec
- ILCSC MAC review in Jan

**$\Sigma$  Value = 6.62 B ILC Units**

## Summary

### RDR “Value” Costs

**Total Value Cost (FY07)**

**4.80 B ILC Units Shared**

**+**

**1.82 B Units Site Specific**

**+**

**14.1 K person-years**

(“explicit” labor = 24.0 M person-hrs  
@ 1,700 hrs/yr)

**1 ILC Unit = \$ 1 (2007)**




# Assessing the RDR

- **Reviews (5 major international reviews + regional)**
  - **The Design:** “The MAC applauds that considerable evolution of the design was achieved ... the performance driven baseline configuration was successfully converted into a cost conscious design.”
  - **The R&D Plan:** “The committee endorses the approach of collecting R&D items as proposed by the collaborators, categorizing them, prioritizing them, and seeking contact with funding agencies to provide guidelines for funding.
  - **International Cost Review (Orsay):** Supported the costing methodology; considered the costing conservative in that they identify opportunities for cost savings; etc.
- **Final Steps**
  - The final versions of Executive Summary, Reference Design Report and Companion Document will be submitted to FALC (July), ILCSC and ICFA (August).



# Technically Driven Timeline






# Engineering Design Phase

- **ILC Engineering Design**
  - We have a solid design concept in the reference design, but it is immature and needs engineering designs, value engineering, supporting R&D and industrialization.
- **GDE will be reorganized around a Project Management Office to reach this goal**
  - M. Ross, N. Walker and A Yamamoto – PM “Troika” + high level engineering managers in the project office
  - Central management will have authority to set priorities and direct the work
  - Resources for the engineering design and associated R&D appears feasible
  - Investments toward Industrialization and siting
  - Anticipate LHC results by ~2010. We are committed to be ready at that time!






# Technically Driven Timeline



# Double Tunnel



- Three RF/cable penetrations every rf unit
- Safety crossovers every 500 m
- 34 kV power distribution



## Conventional Facilities

**72.5 km tunnels ~ 100-150 meters  
underground**


**13 major shafts  $\geq$  9 meter diameter**

**443 K cu. m. underground excavation:  
caverns, alcoves, halls**

**92 surface “buildings”, 52.7 K sq. meters  
= 567 K sq-ft total**






# Civil Construction Timeline





# On-surface Detector Assembly

## *CMS approach*




### **CMS assembly approach:**

- Assembled on the surface in parallel with underground work
- Allows pre-commissioning before lowering
- Lowering using dedicated heavy lifting equipment
- Potential for big time saving
- Reduces size of required underground hall



# Technically Driven Timeline



**Siting Plan being Developed**

Site Prep

Site Select

All regions require ~ 5 yrs






# Americas Fermilab Sample Site

**Situation :** *in solid rock, close to existing institute, close to the city of Chicago and international airport, close to railway and highway networks.*

**Geology :** *Glacially derived deposits overlaying Bedrock. The concerned rock layers are from top to bottom the Silurian dolomite, Maquoketa dolomitic shale, and the Galena-Platteville dolomites.*


**Depth of main tunnels :** *Average ~ 135 m*






# Preconstruction Plan for Fermilab

*Central Area fits inside the Fermilab boundary*



~ Boundary of Fermilab




**Site Characterization of the Central Area can be done**





# Technically Driven Timeline



**Siting Plan being Developed**

Site Prep

Site Select

All regions ~ 5 yrs

R & D -- Industrialization



# The Task Forces

- The Task Forces were put together successively over a period of five months:

S0/S1-Cavities, Cryomodule

S2 -Cryomodule String Tests

S3 -Damping Rings

S4 -Beam Delivery System

S5-Positron Source


S6-Controls, not yet active

S7-RF

- Working in close collaboration with the Engineering and Risk Assessment team.



# Technically Driven Timeline








## Cavity Gradient – Goal

- Current status: Nine 9 cell cavities have been produced with gradients  $> 35$  MeV/m. Not reproducible and needs several attempts at final processing.
- Goal: After a viable cavity process has been determined through a series of preparations and vertical tests on a significant number of cavities, achieve 35 MV/m at  $Q_0 = 10^{10}$  in a sufficiently large final sample (greater than 30) of nine-cell cavities in the low power vertical dewar testing in a production-like operation e.g. all cavities get the same treatment.
  - **The yield for the number of successful cavities of the final production batch should be larger than 80% in the first test. After re-processing the 20 % underperforming cavities the yield should go up to 95%. This is consistent with the assumption in the RDR costing exercise.**



# Cavity Gradient – Results



KEK single cell results:

2005 – just learning

2006 – standard recipe

2007 – add final 3  $\mu\text{m}$  fresh acid EP

**Note: multi-cells are harder than singles**




## Module Test – Goal

- Intermediate goal
  - Achieve 31.5 MV/m average operational accelerating gradient in a single cryomodule as a proof-of-principle. In case of cavities performing below the average, this could be achieved by tweaking the RF distribution accordingly.
  - Auxiliary systems like fast tuners should all work.
- Final goal
  - Achieve  $> 31.5$  MeV/m operational gradient in 3 cryomodules.
  - The cavities accepted in the low power test should achieve 35 MV/m at  $Q_0 = 10^{10}$  with a yield as described above (80% after first test, 95% after re-preparation).
  - It does not need to be the final cryomodule design




# Module Test – Results





# Technically Driven Timeline








## E cloud – Goal

- Ensure the e- cloud won't blow up the e+ beam emittance.
  - **Do simulations (cheap)**
  - **Test vacuum pipe coatings, grooved chambers, and clearing electrodes effect on e-cloud buildup**
  - **Do above in ILC style wigglers with low emittance beam to minimize the extrapolation to the ILC.**



# E Cloud – Results


## LER Grooved Test Chamber



SLAC



# Technically Driven Timeline





# String Test – Goal

- Build 1 RF unit (3 cryomodules + 1 Klystron) to fully check:
  - **What gradient spread can be handled by LLRF system. This test should be done with and without beam loading.**
  - **For heating due to high frequency HOMs.**
  - **Amplitude and phase stability.**
  - **Static and dynamic heat loads.**
- To partially check:
  - **Reliability**
  - **Dark current**
  - **for degradation or other weaknesses**
- The ILC cryomodule is enough different than that of the TTF that a new system test is warranted.




# Rough S2 Schedule

| Phase | Completion date | Description   |
|-------|-----------------|---|
| 0     | 2005            | TTF/FLASH, not final cavity design, type 3 cryomodule, not full gradient, has beam  |
| 0.5   | 2008            | Extra tests at TTF/FLASH with same type cryomodules as phase 0  |
| 1     | 2008            | 1 cryomodule, not final cavity design, type 3 cryomodule (and/or) STF type cryomodule, not full gradient, no beam   |
| 1.1   | 2009            | 1 RF unit, not all final cavity design, not all type 4 cryomodules, not full gradient, beam not needed for tests, but should be built so it and the LLRF are debugged for the next step |
| 1.2   | 2010            | 1 RF unit (replacing cryomodules of phase 1.1), final cavity design, full gradient, type 4 cryomodules, with beam   |
| 1.3   | 2011            | 1 RF unit (replacing cryomodules of phase 1.1), final cavity design, full gradient, type DFM cryomodules, with beam   |
| 1.4   | 2011            | Tunnel mockup above ground. 1 RF unit perhaps built with parts taken from earlier tests. Includes RTML and e+ transport, no beam  |
| 2     | 2013            | N RF units at one site (of the final ILC?) as a system test of final designs from multiple manufacturers, no beam   |
| 3     | 2013            | XFEL  |



# Technically Driven Timeline






# Cavities & Cryomodules

## Producing Cavities




## 4<sup>th</sup> generation prototype ILC cryomodule



| Subdivision                                  | Length (m)      | Number |
|--|-----------------|--------|
| Cavities (9 cells + ends)                    | 1.326           | 14,560 |
| Cryomodule (9 cavities or 8 cavities + quad) | 12.652          | 1,680  |
| RF unit (3 cryomodules)                      | 37.956          | 560    |
| Cryo-string of 4 RF units (3 RF units)       | 154.3 (116.4)   | 71 (6) |
| Cryogenic unit with 10 to 16 strings         | 1,546 to 2,472  | 10     |
| Electron (positron) linac                    | 10,917 (10,770) | 1 (1)  |


| 2007 |    |    |    | 2008 |    |    |    | 2009 |    |    |    | 2010 |    |    |    | 2011 |    |    |    | 2012 |    |    |    | 2013 |    |    |    | 2014 |    |    |    | 2015 |    |    |    | 2016 |    |    |    | 2017 |    |    |    | 2018 |    |    |    | 2019 |    |    |    | 2020 |    |  |  | 2021 |  |  |  | 2022 |  |
|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|----|----|------|----|--|--|------|--|--|--|------|--|
| Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 | Q3 | Q4 | Q1   | Q2 |  |  |      |  |  |  |      |  |







# Technically Driven Timeline






# Concept of IR hall with two detectors

may be accessible during run


The concept is evolving and details being worked out

accessible during run






# Technically Driven Timeline



# The WWS Roadmap for ILC Detectors





## After the DCR

- The WWS effort has culminated with the production of the DCR (Detector Concept Report) which results from the work developed for the 4 concepts as described in detailed documents called the DODs (Detector Outline Document)
- After the DCR, the WWS is facing a new challenge set by our colleagues of the GDE:
- To prepare EDR documents for the 2 “contrasting complementary detectors” of ILC by 2010, by the time of significant LHC results
- To work out a scenario of construction of these detectors assembled on surface, two years after the construction of ILC begins with detectors ready to go down into the pit less than five years after



# The Roadmap for Detectors

The key elements of the roadmap proposal are:

- A call for LOIs by ILCSC due for summer 2008
- These LOIs can be based on a simple extension of the existing DODs
- They will be reviewed by IDAG, an International Detector Advisory Group of experts chosen by a Research Director RD (defined below) in agreement with ILCSC
- IDAG will make recommendations to the RD on the choice of two detectors for the engineering design effort based on detector LOIs
- The Research Director will present these recommendations to the ILCSC for approval



## A Research Director

The WWSOC thinks that IDAG alone cannot accomplish the executive tasks which are needed to make this process active and viable (in particular keeping active the R&D 'horizontal' effort during the EDR phase)

- We therefore need a **Research Director** for detectors to provide the necessary managerial tasks
- Ideally one would need this RD to be nominated early enough by ILCSC to initiate the LOI procedure in collaboration with the IDAG but time seems too short
- Financial support needs to be provided for the RD
- An 'umbrella organization' defined by ILCSC is needed ASAP to coordinate the detector and machine activities until a world lab is constituted



# Achieving our ILC Timeline

## *“The other issues”*

- We need to begin a campaign to prepare the way for submitting a winning proposal in about 2010.
  - Science Motivation is very strong, but we need LHC results for validation (~2010)
  - Must convince broader HEP and science communities on the ILC
  - Must engage the global governments to take ownership and develop international governance
  - Must develop a siting strategy
- The key to maintaining our timeline will be working these issues in parallel with developing an engineering design and completing the R&D





## Endorsement from FALC?

- To promote for the ILC specifically, the coordination of resources and the conduct of an R&D program for the engineering design phase.
- To note that the ILC-GDE will directly negotiate with the laboratories and universities, for the tasks, roles and responsibilities of that institution in connection with the ILC work, subject to available funding. These agreements would be memorialized in MOUs between the ILC-GDE and the participating laboratories and universities.
- To work towards an appropriate organizational structure for the governance of the engineering design phase, a single oversight Council.
- In the interim agree to continue the central coordinating role of the ILCSC as established by ICFA.