# **Risk Management**

presented by:

Rolf Stadelmann, Head of Geotechnical Division Amberg Engineering Ltd., Regensdorf, Switzerland

# **Risk Management**

- Content
- Definition
- ITA (=International Tunnelling Association)
- ILC-Project



# **Risk Management**

Risk management is the systematic process of identifying, analyzing and responding to project risks.

**Risk management is** 

- not only a single event
- a continuous process during the entire project.

Therefore the risk control is part of the project life cycle from project initiation to project completion.



**Risk Management, Threats and Opportunities** 

Risk management covers the handling of

- project threats and
- project opportunities.

Project threats are risks which can have a negative impact on a project.

Project opportunities are risks which have a positive impact on a project.



# **Risk Management, Steps**

**Risk management consists of:** 

•Risk Management Planning


•Risk Identification

•Risk Analysis

•Risk Responding

Risk Control







# **Risk Management Guidelines**

ITA Risk Management Guidelines prepared by Working Group 2 "Research", published 2004





Tunnelling and Underground Space Technology 19 (2004) 217-237

**ITA/AITES** Accredited Material

Tunnelling and Underground Space Technology neorporating Trenchless schoology Research

www.elsevier.com/locate/tust

Guidelines for tunnelling risk management: International Tunnelling Association, Working Group No. 2 \*

Søren Degn Eskesen, Per Tengborg, Jørgen Kampmann, Trine Holst Veicherts

ITA Working Group 2, Research, ITA-AITES, do EPFL, Bat GC, CH 1015 Lausanne, Switzerland



# **Risk Identification According to ITA Guidelines**

The ITA Guidelines distinguish in general and specific hazards

Contractual disputes

General Hazards (considered for each contract)

Specific Hazards (considered for each part of the project)

- Insolvency and institutional problems
- Authorities interference
- Third party interference
- Labour disputes
- Accidental occurrences (earthquakes, flooding, sabotage etc.)
- Unforeseen adverse conditions (geotechnical, geological risks)
- Inadequate designs, specifications and programs
- Failure of major equipment
- Slow or out-of-tolerance works



# **Risk Identification: Geotechnical Risks**

Geotechnical risks on the surface

- Settlements of buildings and existing infrastructures
   cracks, inclination, damage
- Settlements of service utilities (electricity, gas, water etc.)
   > cracks, damage
- Vibrations
   > cracks

Deformations

**Geotechnical risks** 

underground

- Instability of crown and / or face
- Cave-in
- Rock fall / wedges



# **Procedure of Risk Analysis**

**Risk Score = Probability P x Risk Impact RI** 


# **Probability P**

100		1	2	3
-	Likelihood	Low	Medium	High

# **Risk Impact RI (examples)**

1		1	2	3
1	Costs	<10 MEUR	10-100 MEUR	>100 MEUR
	Schedule	< 2 months	2-12 months	>12 months







# **Classifications According to ITA Guidelines**

Probability of Occurrence (Frequency)

- Very unlikely
- Unlikely
- Occasional
- Likely
- Very likely

Impact

(Consequence)

- Insignificant
- Considerable
- Serious
- Severe
- Disastrous

The classifications can be defined according to the specific project.



# **Examples of Impact Scale According to ITA Guidelines**

		disastrous	severe	serious	considerable	insignificant
	Economic loss to owner [Mill. Euro]	> 30	3 - 30	0.3 - 3	0.03 – 0.3	< 0.03
N N	Delay [months]	> 10	1 - 10	0.1 - 1	0.01 - 0.1	< 0.01
	Harm to environment	permanent severe damage	permanent minor damage	long-term effects	temporary severe damage	temporary minor damage



# **Risk Analysis Matrix According to ITA Guidelines**

	Conse- quency Fre- quency	insignificant	considerably	serious	severe	disastrous
4	very likely	unwanted	unwanted	unacceptable	unacceptable	unacceptable
1	likely	acceptable	unwanted	unwanted	unacceptable	unacceptable
	occasional	acceptable	acceptable	unwanted	unwanted	unacceptable
1	unlikely	negligible	acceptable	acceptable	unwanted	unwanted
	very unlikely	negligible	negligible	acceptable	acceptable	unwanted



# **Risk Responding: Possible Strategies**

# Avoid:

eliminate the uncertainty or execute the project in a different way

### Transfer:

transfer the risk to another party which is then responsible to handle the impact


# Mitigate:

reduce the risk to make it more acceptable to the project by reducing the probability and/or the impact

### Accept:


accept the risk (normally done for project risk which have a low priority or a low impact)








# Example for Risk Responding: Range of Geological Risks 2005 and Accuracy of Cost Estimation +/- 25%



### ILC - International Linear Collider

CERN, 2007-09-03






### ILC - International Linear Collider


### CERN, 2007-09-03

# **Investigation Gallery, Piora Basin**





# **Risk Responding: Range of Geological Risks 2005** and Accuracy of Cost Astimation +/- 10%





# **ILC Initial Risks: Examples**

# **Risk factors during approval project**

e.g. delay in <u>permitting process</u>, insufficient project management, <u>objections</u> raised by the public etc.

# **Risk factors during the tendering process**

e.g. <u>financial uncertainty</u>, insufficient project basis information, engineering and tender document errors, <u>insufficient quality</u> of the bidding contractors etc.

# **Risk factors during project realization**

e.g. unstable working face conditions, more numerous and longer <u>fault zones</u> than predicted, heavy <u>water</u> inflow, water pressure, project optimizations negatively influencing project requirements, inadequate contracts, <u>insufficient</u> <u>control and monitoring</u> of construction process, insufficient authority of site manager, insufficient preparation, lack of financial strength of the contractor, sabotage, environmental disasters etc.



Risk Analysis Matrix: Examples of ILC Risks							
uence/ Impact							
Consequence, Impact	<ul> <li>More numerous and longer fault zones than predicted</li> <li>Insufficient preparation</li> </ul>	• Strained situation of the job market in the building industry impairs the rekruitment of qualified personnel	<ul> <li>Lack of financial strength of the contractor</li> </ul>				
medium	<ul> <li>Insufficient project management</li> <li>Sabotage</li> </ul>	<ul> <li>Clogging /Blocking of cutter head, excavation chamber and conveyor system</li> <li>Tunnel climate</li> </ul>	<ul> <li>Deadline and cost pressure upon contractor</li> <li>Delayed delivery of construction drawings</li> </ul>				
low	<ul> <li>False interpretation of geology</li> <li>Insufficient, unsuitable advance investigation systems</li> </ul>	<ul> <li>Delay in permitting process</li> <li>Insufficient definition of interfaces</li> </ul>					
1102	low	medium	high Probability of o	ccurrence			



# **Risk Responding: Example**

### **Risk Factor: Tunnel Climate**

The tunnel climate, apart from the construction work (exhaust gases), is affected by the influence of the rock (gas, radioactivity). Climate loading affects in particular the job safety (work conditions) and health of the underground workers.

### **Initial Risk Assessment:**

Probability of Occurrence: medium / Impact: medium

# **Risk Reduction Measure:**

Molasse can have gas deposits, ventilation must be designed accordingly, gassensors and measurement. Correct working temperature and vision shall be ensured.

# **Residual Risk:**

Probability of Occurrence: small / Impact: medium



# **Risk Responding: Example**

# **Risk Factor: Lack of the financial strength of the contractor:**

Deficient financial stability of a JV (liquidity problems, financial stability, creditworthiness) can lead to the loss and/or bankruptcy of a contractor and so disturb work continuity.

# **Initial Risk Assessment:**

Probability of Occurrence: high / Impact: high

### **Risk Reduction Measure:**

Only allow JV's with 3 - 4 equal partners. Intensive verification of financial stability of the individual JV partners.

### **Residual Risk:**

Probability of Occurrence: medium / Impact: small



# **Risk Responding: Example**

# **Risk Factor: Insufficient Preparation**

Insufficient, unsatisfactory preparations can lead to inappropriate processes and / or unsuitable installations. Thus efficient and goal-oriented construction processes are obstructed.

### **Initial Risk Assessment:**

Probability of Occurrence: low / Impact: high

# **Risk Reduction Measure:**

Set up of a "Board of Experts" from construction-oriented specialists for the function of co-authoring


### **Residual Risk:**

Probability of Occurrence: small / Impact: small




ILC - International Linear Collider

CERN, 2007-09-03









# Thank you very much for your attention