# **KEK Experiences of CFS**

Masakazu Yoshioka

(KEK, J-PARC Project Office)

September 10, 2007 @ CFS-AS Kick-off Meeting

**Acknowledgement:** 

Masanobu Miyahara, Tsunehiro Hanayama, Terunori Shibahara, Shigeru Takeda





	1960	1970	1980	199	0	2000		2010	2020
1.3 GeV INS-ES									
12 GeV KEK PS									
TRISTAN		••••							
KEKB			• • •					•••••	
Super KEKB						• • • • • •	-	••••	
<b>J-PARC</b>					••/••				
ILC			•	••••	• •/• • • •		•		
2.5GeV PF	•				7				
6.5 GeV PF-AR									
1.3 GeV ATF									

INS: Institute for Nuclear Study, University of Tokyo, KEK's Mother Institute

In Japan, TRISTAN was the first large-scale facility (1980s) 20 yeas later, J-PARC construction is underway.

Now

## INS-ES in '60s








# **J-PARC**

# J-PARC Facility



Joint Project between KEK and JAEA





**JAEA responsibility:** 

Linac, RCS and MLF

**KEK responsibility:** MR, Hadron and Neutrino

# **Construction Budget**





**Budget allocation** 


# At J-PARC civil engineering work, we have experienced every kind of problems


## **▶**Bad geology:

- **➤** No scientific site selection
- **▶** Deep bedrock, sandy mudstone with undulation
- ➤ Thick sand gravel with flowing and abundant groundwater
- **▶**Poor preliminary survey → need design change because of groundwater
- > Remains of salt farm
  - **▶**need additional budget and delay of schedule
- > Reserve forest area
  - >strong constraint for the construction method and procedure
- ➤ Goshawk (wild bird, a kind of falconine)
  - **▶**break of construction during child-raising
- >Strong constraint related with the site problem with nuclear facility
  - **▶unexperienced gate control, unexperienced confusing regulations, etc. etc......**
- > Contracts for civil design and real construction must be separated
  - ➤Incomprehensible law to keep "transparency", poor feed back from reality to design
- ➤ Segmentalized construction zone due to the budget schedule
  - **≻**Complicated construction management, extra-cost, etc. etc......

## Very bad geology

Bed rock, deep underground, sandy mudstone with undulation Thick sand gravel with flowing and abundant groundwater








# Remains of salt farm

- >400 years ago
- ➤ Need additional budget
  ➤ 5 million dollar
- **≻one year delay**






**Tunnel Circumference** 1.6km w5.0m, H3.5m **Tunnel inner size Tunnel floor level** -2m from sea-level **Excavation volume** 0.8 Million m<sup>3</sup> **Back-filling volume** 0.72 Million  $m^3$ **Number of PHC pile** 1400 **Volume of concrete (MR)**  $0.11 \text{ Million m}^3$ **Reinforcing steel 12000 ton** 

Ground total concrete volume of J-PARC: 0.48 Million m<sup>3</sup>


Thickness of concrete of arc section floor 1.2m, wall 0.8m, top 1.0m **Maximum thickness of concrete** 

5.5m

50GeV標準断面図 (大断面部)



50GeV標準鋼矢板断面図 (標準部)





Groundwater problems

Original design Design changes pumping-up with kettle hole → design debacle! ←poor preliminary survey Deep well and seepage control method (SMW and/or grouting) volume of pumped-up water > 20kton/day





A: Kajima JV


B, N-Arc: Taisei JV


C, DV-1: Shimizu JV


TS: Kumagai JV

HH: Takenaka JV

International bidding for the contract with >720 M Yen. But no proposal tender from abroad.









Ground motion at J-PARC site Earth-tides are clouded by ocean-tides

Thanks, J-PARC is not the collider

## Work done by Shigeru Takeda





JF	<u></u>	01	JYF2002					JF`	Y20	03		JΥ	YF2004		JFY2005			05	JFY2006					JF	Y20	07		JFY2008		
	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1
Geological survey													Ext	ern	al r	evie	w													
<b>Execution Design</b>												De	sign	сh	ang	e														
MR Tunnel																														
Zone-A																														
Zone-B																														
Zone-C																														
Zone-D1																														
Zone-D2																														
HADRON																														
Zone-S																														
Hall																														
Neutrino																														
Arc																														
TS																														
DV-1																														
DV-2																														
NM																														
Accelerator																1	Co	mpo	ner	nt ir	nsta	llat	ion			Ор	erat	ion		

Accelerator components are installed into the tunnel in parallel with civil work.

### Main problems of real civil work in the field;

- Poor finish of floor painting → a few thousand square-meter, almost fraud → delay of schedule
- **Bad concrete depositing**→a few hundred square-meter→delay of schedule
- Penetrated concrete crack → Yoshioka's view: mostly resulted by the mechanical stress → delay of schedule
- **■**Uneven settlements → *Yoshioka's* view: problem of piled foundation → repeat magnet alignment → delay of schedule

**Ironically**, we could have accumulated many experiences by the segmentalized construction zone.

- **❖**We could work together with five super- and three middle-ranking construction companies and accumulate a lot of experiences how to work together, how to keep the good quality, etc.
- **❖**The quality of the construction work does not depend on the company-size, but on the attitude and arrangement of the company and the character and ability of the head of the field site.
- **❖**The construction management is essentially important to keep the good quality.

# Lessons from experiences,

- **❖**Site selection should be done based on the science; geology, geography, groundwater, animals and plants, etc. (Japanese infrastructures are excellent)
- **Separation** of contracts for design and real construction makes poor interaction between the design team and reality  $\rightarrow$  We should find out the better way!
- **Ordering** party should have a well-qualified team to make the design by its own ability and find out the effective relation with the consulting company (companies).
- **❖Bidding** with engineering evaluation is efficient to introduce better technology and to reduce the cost and term of works.

		JΥ	F19	80		JFY1981				JΥ	F19	82		JFY1983				JF`	Y19	84		JFY1985				JF`	Y 1 9	86
	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1	4	7	10	1
Baseline Design																												
Execution Design																												
Survey for MR																												
AR civil																												
AR buildings																												
MR civil																												
MR builings																												
AR accelerator																												
MR acceelrator																												



TRISTAN is the 32GeV+32GeV e+e- collider consisting of a linac (500m long), an AR synchrotron (480m) and a MR synchrotron (3km)

Outline of the civil engineering work

- **■Piled foundation** → Experimental halls and straight sections
- **■**Raft foundation → Arc sections
- **■**Excavation volume → 1.2 million m<sup>3</sup>
- **Number of piles**→2400
- **■**Volume of concrete → 0.25 Million m<sup>3</sup>


Powerful headquarter led by Tetsuji Nishikawa Powerful civil engineering team was newly created at KEK

#### Lessons for J-PARC from TRISTAN experiences;

- **■**No expansion joint at MR
  - **Expansion joint makes many troubles**
- **■**No steel base-plate for magnets on the tunnel floor (floor concrete is strong enough)
  - **■**There is a superstition in Japan that magnets should be fixed on the steel plate.
- **Water-tight tunnel using catalytic agent from outside of the wall.**
- **Choose special concrete with slow hydration reaction to avoid too big temperature difference in the mass-concrete between the interior portion and surface.**
- **Choose special aggregate to avoid activation of the concrete itself (no sodium).**

Thermal expansion of the tunnel due to the temperature rise of 12 degree C (no expansion joint).

By Nikken Sekkei



# Yoshioka's comments for ILC EDR Asian effort based on the TRISTAN, KEKB and J-PARC experiences

Even though there are many differences between KEK's experiences and ILC, I try to find out useful case examples.

#### Main differences;

- $\bullet$ O(km)  $\rightarrow$  O(10km)
- •Site is inside of the laboratory campus  $\rightarrow$  outside  $\rightarrow$  we can learn from SPring8 experiences They established the new facility at the green field working closely with local government.
- **■**Domestic → international project
- **No site selection** → site selection
- **Shallow underground** → deep underground

### Ordering party should be consisted in

- Accelerator scientists
- Civil engineering experts

Strong team should be created, which is organized by accelerator scientists and civil engineering experts, at KEK, for example. Well-qualified team only can manage and/or operate the contract with consultants and general construction contractors.

We should find out or we should cultivate experts, who understand requirements from the ordering party, both at the

- **Consulting companies of civil engineering design.**
- **General construction contractors.**

The existent budget system does not fit with ILC, which is the large-scale international project.

We should avoid to break into too small-size contracts, and negative effect due to the single-year budget.

Substantial preliminary survey for geology, groundwater, environment, etc. are needed.

Scientific review by the outside experts is important.

## Thank you for your attention