



Cryomodules & Cryogenics – KOM:

Cryogenic experience from CERN LHC

Laurent Tavian
CERN, Accelerator Technology Department


KEK, 13 September 2007



- Overview of the LHC cryogenic system
- Construction experience
- Commissioning / Operation experience
- Preliminary results for measured static heat loads.
- Conclusion



Overall layout of LHC and its detectors






The LHC accelerator in tunnel

p-p collision -> $10^{34} \text{ cm}^{-2} \cdot \text{s}^{-1}$, 14 TeV c.m., 0.5 GJ stored energy



24 km of superconducting magnets @1.9 K, 8.33 T

Cryogenic system layout



- 5 cryogenic islands
- 8 refrigerators
 - 2 at **P4, 6 and 8,**
 - 1 at **P2**
 - 1 at **P1.8**
- 1 refrigerator serves 1 sector (18 kW @ 4.5 K, 600 kW pre-cooler)
- possibility to couple two refrigerators via the interconnection box → 2 refrigerators for 1 sector

Legend:

- QRL (distribution line)
- QUI (interconnection box)
- Refrigerator
- Arc
- ▭ Dispersion Suppressors
- ▭ Long Straight Section



LHC cryogenic system layout 2/2




Even point

Odd point

MP Storage


W
K
erator

Interconnection Box






Historical milestones of the LHC




- Overview of the LHC cryogenic system
- **Construction experience**
- Commissioning / Operation experience
- Preliminary results for measured static heat loads.
- Conclusion



Series production of LHC components








Production and test rates

- The planned production or test rates were generally reached and often overcome,
→ but always after a “learning” period.
- The main difficulty is to assess the duration of this learning period and to have it agreed by all the stakeholders.
- For the LHC cryogenics, this learning periods were often too optimistic.
Examples: the cryomagnet cold test, the quench valve production and the cryogenic distribution line (QRL)



12 benches, rate: ~15 magnets per week

Cryodipole cold tests




Updated 31 August 2007

Data provided by D. Tommasini AT-MCS, L. Bottura AT-MTM

Delays: mixing of sub-contractor insolvency and learning period for efficient test bench operation (cog-wheeling).

Quench valves




Updated 31 August 2007

Data provided by V. Fontanive AT-ACR


Delays: Finalization of the design



QRL Dashboard



The LHC cryogenic distribution line (QRL) problem:
Elements equivalent to two sectors to be repaired and one sector to be reinstalled (by CERN).



Composite material (Neonite®) fabricated with short fibers instead of long ones → insufficient resistance to impacts



Example of achieved production rates

Fabrication of QRL modules

	Pipe elements	Fixed points/ Special pipe elements	Service modules	Service modules	Service modules	Steps/ Elbows
	Air Liquide- 2C (FR)	Tuboplan (PT)	SIMIC (IT)	FCM (SP)	Air Liquide (FR)	Tuboplan (PT)
Contract (old target) <i>[element/week]</i>	15	3	1.5	1	0.1	0.5
Contract (new target) <i>[element/week]</i>	25	6	2.5	1.7	1	1.5
Produced (average) <i>[element/week]</i>	30	7	2.3	1.8	1	1.85
Produced to-date <i>[number of elements and %]</i>	1714	447	168	106	39	66
	100%	100%	100%	100%	100%	94%



How to deal with construction problems?

- For large and ambitious projects, everyone is convinced that, in view of their complexity, some problems will definitely arise.
- But when a problem happens, everyone (except the ones who have to deal with the problem) asks: How is it possible to make such a mistake ?
- General rules to avoid construction issue:
 - Do not specify something for which you have no solutions.
 - Do not mix prototype, pre-series and series production. Be sure that when the series production starts, all developments are completed.
 - Put sufficient independent resources on quality control. (Mandatory for large series). Do not trust the internal quality control of a manufacturer even with ISO qualification.
 - For LHC a contract for quality inspection has been placed with only 2 “itinerant” inspectors foreseen to follow cryo-equipments → 7 inspectors were required to follow correctly the QRL quality inspection.
 - Put sufficient effort to test the critical components, but the difficulty remains in the risk assessment. (Always easier to do after the problem detection).

Splitting or not splitting ?

- Splitting of contract for the procurement of equipment is generally a good decision:
 - To secure the production: If one supplier has difficulties, part or totality of the remaining production can be transferred to the other suppliers.
 - To get some competition within the suppliers (performance, delays...)
 - For political reason (Funding return in several places / countries / continents)
- But:
 - a known splitting before tendering could generate less commercial competition, i.e. higher offer prizes. (In cryogenic refrigeration only two suppliers are on the market)
 - splitting generates more contract follow-up needs which are generally not anticipated in the manpower plan.

Following difficulties identified on a contract:


- **If time is available:**

- Ideal case for the project as some pressure can be put on the supplier to fulfill the contractual terms.
→ **Time is contingency**

- **If no time is available (supply already on the critical path):**

- In this case, extra resources (i.e. money) have to be allocated by the project to solve the difficulties:
 - Via a second contract in case of splitting of contract
 - Internally in case of re-internalization of part of the supply
 - Directly to the firm via “justified” claims.
- **Money is contingency**


Cost breakdown



- Overview of the LHC cryogenic system
- Construction experience
- **Commissioning / Operation experience**
- Preliminary results for measured static heat loads.
- Conclusion

From commissioning to operation staging:

- Starting from surface equipment (4.5 K cryoplants)
- Following by cavern equipment (interconnection box then 1.8 K refrigeration units)
- Finishing by tunnel equipment (QRL, machine)





Commissioning of the first LHC sector

- The 1st LHC sector, sector 7-8, began to be cooled down for the first time on Jan. 15th, 2007
- After about 2 months, the temperatures of all the magnets were below 2 K, i.e. more than 10 tons (70'000 liters) of pressurized superfluid helium distributed along 3 km have been produced (about 20 times higher than Tore Supra).
- Nevertheless, to reach this successful milestone, several problems were encountered:
 - Unbalanced cool-down
 - Unexpected long cool-down
 - Problems with ex-LEP cryoplant
 - Problems with 1.8 K refrigeration units
 - Longer tuning of the tunnel cryogenics



Before

After



Kapton bits


Metal strips



*≈ 50 h
+ 8 L of Water*



First sector (S7-8) commissioning



Cooldown of first sector (4625 t over 3.3 km)





Unloading of LHe & LN2



600 kW precooling to 80 K with LN2:

- up to ~5 t/h
- 1250 t of LN2 in total
- 6 LN2 trailer per day during 10 days



Cool-down generic flow scheme



Two neighboring standard cells supplied by one valve





Unbalanced Cool-down (Measurement)







Unbalanced Cool-down (Simulation)




Unbalanced Cool-down (Analysis)




Evolution of ratio of ΔP of TNC at different positions

How avoiding unbalanced cool-down ?




**Periodic switch-over (every 12 hours) of QV valves:
The available cool-down flow goes in one cell, then in
the other with no increase of the total cool-down time.**

Unexpected long sector cool-down




- Longer cool down time: 36 days instead of 15 days (without electrical QA plateaus)
 - Learning and tuning of the process (unbalance, ...)
 - Reduced available cooling power:
 - LN2 logistic during nights and week-ends
 - Limitation on turbo-expanders not working at nominal conditions
 - Flow restriction in the cold part of the 4.5 K refrigerator

Simulation of 300-80 K cool-down



Calculated and measured results of the 1st normal CD from 300 K to 80 K




Calculated and measured results of the 1st normal CD from 80 K to 4.5 K



Learning process: better agreement for 2nd sector cool-down

- Effective cool-down started on Thursday 5 July 2007


Slow-down
during week-end
(LN2 logistics)



Leak in the
first R4 sub-sector
(cold-mass circuit)
→ Stop of CD on
14 July 2007



Problem with Ex-LEP cryoplant




Sub-cooler recovered from LEP undersized:
→ too high tunnel supply temperature






Problem with Ex-LEP cryoplant



— 4.5 K refrigerator supply temperature
— Magnet temperature (average over sector)
— 1.8 K refrigeration unit cooling temperature


Too high temperature w/r to specification:
→ Important gas fraction in final expansion

Flash by isenthalpic expansion of He from 3 bar to 1.3 bar, saturated



— 1.8 K refrigeration unit cooling temperature


Problem with the driving system of one cold compressor



CC2 frequency-drive stops on « overload » after some time above some load



Cold compressor cartridge



Switch of refrigerators: Validation of redundancy




Configuration before switch

Configuration after switch

Odd point – P7


Even point – P8

Odd point – P18





Improvement after refrigerator switch









2.3 - Cold compressor tuning

Problem with control algorithms which have to be adjusted to deal with faulty instrumentation (inlet temperature).

The use of mixing chamber and phase-separators to adjust the flow and the temperature was mandatory






First tests
Second tests
"Normal"



$$Mr = \frac{M}{M_0} \times \frac{P_0}{P} \times \sqrt{\frac{T}{T_0}}$$

$$Nr = \frac{N}{N_0} \times \sqrt{\frac{T_0}{T}}$$




- No cold tests of these boxes before sector commissioning (skipped for time and resource saving).
- Condensation problems at the top of chimneys (very humid condition in tunnel).
- Identical problem for the 60 A leads distributed in the tunnel







DFB Commissioning – level validation

Good global behaviour
of level sensors DFBAO






- Extensive calibration program for the liquid helium level gauges
- Once commissioned, successful operation at nominal conditions




Validation of cell cooling redundancy !!






JT valves: Flow characteristics






Availability during arc powering test




CW23: Deactivation of Cryo-start during the night and instrumentation (heater) problem
CW24 & 25: Mainly ELQA and powering w/o quenches
CW26: Problem with electrical supply on the PLC of the 4.5 K refrigerator
CW27: down-time due to quench recovery

First sector warm-up




- Overview of the LHC cryogenic system
- Construction experience
- Commissioning / Operation experience
- **Preliminary results for measured static heat loads.**
- **Conclusion**

Typical LHC cross-section




LHC cooling flow-scheme





Heat inleaks on cold-mass circuits


Measurement by global assessment



Total heat load 961 W including 401 W of additional electrical heating


→ 560 W of heat inleaks at 1.9 K, i.e. 0.2 W/m (0.21 W/m calculated w/o contingency for a standard cell by the Heat Load WG)

Vacuum sectorization:



Bad vacuum (Helium leaks)

Cold-mass sectorization:




20 % of the sector was not operating at nominal insulation vacuum creating extra heat inleaks (factor 2 to 3 according to valve opening), i.e. nominal sub-sectors have probably smaller heat inleaks than expected by the HLWG.



Heat inleaks on cold-mass circuits

Local measurement on sub-sectors



Measurement by variation of internal energy during a natural warm-up of a sub-sector in superfluid state.

Applying a known power allows to assess also the He content

Sub-sector	Q [W]	q [W/m]	V [l/m]
Q27_29 R7	27.0	0.13	24.8
Q23_25 R7	26.9	0.13	25.4
Q15_17 R7	27.9	0.13	24.3

Uncertainty: +/- 2 %

- He content: in accordance with the calculation and warm measurements
- Distributed heat inleaks: 33 % lower than expected by HLWG (but the shields were colder in average by about 5 K)




Heat inleaks on thermal shield circuit

- Global measurement by enthalpy balance at the cryoplant interface:
 - 19.8 kW measured to be compared to the 23.5 kW assessed by the HLWG.
 - i.e. 6.6 W/m measured to be compared to 7.7 W/m assessed by the HLWG (15 % lower than expected)




QRL heat inleaks measurement

Measured done on a QRL sector (S8-1) without magnets



Thermal shields
About 2.7 W/m



Cold headers
About 0.19 W/m



Distributed static heat in-leaks in a standard cell [W/m]

Temperature level	50-75 K		4.6-20 K		1.9 K LHe		4 K VLP GHe	
	C	M	C	M	C	M	C	M
Magnet side	4.5	3.9	0.14	?	0.19	0.13*	N/A	N/A
QRL side	3.2	2.7	0.09	0.09	0.02		0.11	0.10
Total	7.7	6.6	0.23	?	0.21	0.13*	0.11	0.10

C: Calculated (HLWG)

*: with colder thermal shield temperature

M: Measured

Very good agreement between calculations and measurements.

- But a lot of effort in component testing (thermal model, pre-series, string tests...)
- And a global management in a Heat Load WG (2 years of active work)

- LHC enters its last exciting commissioning phase.
- The construction phase confirms that contingency are mandatory to deal with the learning process and problems. Do not forget quality inspection and contingency.
- Cryogenic commissioning of the first LHC sector done:
 - **No “big” surprise / mistake, but some “small” consolidation identified.**
 - **Tuning of cryogenics of this complex system takes more time than foreseen/allowed**
- Heat inleaks are as expected thank to the preliminary work on the thermal validation.
 - **Waiting for dynamic heat load measurement to have the complete picture. (e-clouds remains a big uncertainty)**