



Construction Experience of the LHC Cryostats



Vittorio Parma


CERN, AT-MCS Cryostats Section
CH-1211 Geneva 23, Switzerland

Outline:

- Design principles
- Main cryostat components
- Cryostat Assembly
- Costs
- Performance
- Summary


Acknowledgements:

*I wish to acknowledge the work of **all colleagues** who have contributed to the LHC cryostats, in particular the members of CERN's former **AT-CRI group** (now part of AT-MCS) for the work done **between 1996 and 2006**.*




LHC cryostats. Key figures:

- 8 continuous cryostats ~ 2.7 km each (80% of the ring)
- 36 individual cryostats (excluding triplets) in the LSS
- 1232 cryo-dipoles
- 474 Short Straight Sections (SSS):
 - 360 main quad SSS in the arcs
 - 114 insertion quad SSS in the DS and LSS regions



From a simple artist's view...




...to a complex reality



The LHC interconnections



Overall progress



LHC Progress Dashboard

Accelerator Technology Department


Interconnection overview



Data provided by J. Ph. Tock AT-MCS

J.Ph. TOCK
(AT-MCS-IC)

Layout



LHC cryostats

- 8 continuous cryostats in Arcs and DS (21.6 km):


SSS

Cryo-dipole



Cryo-dipole

Cryo-dipole

SSS



- Individual cryostat assemblies in the LSS (36 units, ~300 m):





LHC cryostat functions




Recalling Basic Functions:

- **Mechanical housing of cold masses:**
 - Supporting of heavy superconducting magnets in their cold masses
 - Accurate & stable positioning of cold mass in vacuum vessels
 - Allow precise magnet alignment capabilities (via external jacks)
- **Thermal insulation:**
 - **1.9 K** cold masses housing the magnets
 - Cryogenic piping and components

Other functions:


- Magnetic shielding
- Integrate various equipment: BPMs, cryogenic and vacuum H/W, magnets and cryogenic diagnostics instrumentation...
- Allow (limited) maintenance: ex. exchange of diodes
- Allow interconnecting magnets
- Permit handling and transport of cryo-magnets throughout CERN activity sites

Typical LHC Cross-section





Cryostats: main features

LHC Main Cryostat
(Cross-Section)



Cryostats: SSS variety



LHC SHORT STRAIGHT SECTION

(technical service module side)

Connection to cryogenic distribution line

He phase separator

Thermal shield

Beam tubes

Diode

Cryogenic tubes & pressure gauge connection

Instrumentation connections outlet


BPM

Electrical feeds to Corrector magnets

Vacuum vessel

Vacuum barrier


Magnet helium enclosure




The LHC interconnections

❖ Space constraints

Space constraints :



Typical cross-section of the LHC tunnel




Typical longitudinal section of a LHC interconnection



The LHC interconnections



- ❖ Optimised interconnexion ; before, during and after






The LHC interconnections

- ❖ 40 000 leak tight TIG welds in crowded places




Cryo-dipole:

- 3 supports
- central support fixed
- extremity supports slide




Arc SSS:

- 2 supports
- left support fixed
- right support slides




Longest SSS (in LSS):

- 3 supports
- left support fixed
- other 2 slide



LHC arc half-cell (top view)

SSS




Cryo-dipole



Cryo-dipole




Cryo-dipole



○ Jack


□ Central jack ("crutch" for vertical sag adjustment only)

SSS






The Way to Series Production



- **Concepts & technical choices** suited to a large-scale series production
- **Available and Affordable** industrial production processes
 - Technically adequate to a large series production
 - Limited development costs
 - Cost effectiveness from economy of scale
- **Confidence gained** from prototyping extensively tested on full-scale strings of cryo-magnet
 - String 1 (53 m half-cell, 1994-1997). first prototypes; **10-m dipoles**
 - String 2 (106 cell, 1998-2000); validation of **quasi-final cryostat design**
- **Cryostat components procurement policy:**
 - **Market survey:** Pre-selection of widest panel of companies with technical competence and production potential
 - **Call for tender:** Competitive tendering on "build-to-print" technical specifications
 - **Splitting** on more than 1 supplier for critical risk components
- **Assembly of cryostats at CERN** based on a "**Result-oriented**" execution contract.



Vacuum Vessels

Main features:

- 36-inch OD, 12-mm thick, low carbon steel (DIN GS-21 Mn5) tubes
- Resilience: 28 J/cm² at -70°C
- Forged cradles, welded rings reinforcements
- St. steel extremity flanges
- Stress relieving by vibration for dimensional stability
- Final machining to achieve tolerances at interface

Production (including spares):

- 1250 units for dipoles
- 500 units for SSS
- 2 firms for dipoles
- 1 firm for SSS
- 4 yrs of production
- Tooling cost: 20% of contracts value



Stress relieving



Forged cradle



Final lathe machining





3-D dimensional control in Industry



Out-doors storage at CERN

Dipole vacuum vessel





Main lessons learned:

- Started on 1 supplier....
-then splitting on 2 suppliers for dipoles, (+1 supplier for SSS) to ensure production
- Suppliers (small/medium size sheet-metalwork companies) had to learn the "cryostats culture":
 - Leak-tight welding
 - Leak detection ($<10^{-9}$ mbar.l/s) using helium mass spectrometry
 - Cleanliness
- Technical issues:
 - Dimensional and shape tolerances at flanges
 - Other but minor issues

Aluminum Thermal Shields



Main features:

- Al 6060 double-walled extruded tray with cryogenic cooling channel
- Al-st. steel transitions at cryogenic channel's ends
- Al rolled sheets with longitudinal welds to tray

Production (including spares):


- 1250 units for dipoles
- 500 units for SSS
- 2 suppliers
- 4 yrs of production
- Tooling cost: 15% of contracts value





LHC Progress
Dashboard

Accelerator
Technology
Department




Updated 31 August 2007

Data provided by A. Poncet AT-MCS



Main lessons learned:

- Started on 1 supplier which became insolvent
- New Call for Tender and splitting on 2 suppliers
- Technical issue:
 - Al-Al weld quality of Al-st.steel transitions
 - CERN in sourcing of activity...
 - ...then outsourced competence to firms





Features:



- **4-mm thickness**, single-part composite column (integrating interface flanges)
- Manufactured by **Resin Transfer Moulding (RTM)**:
 - Suited to a large-scale industrial production
 - High reproducibility in quality
- Limited machining at interface, for tight dimensional tolerances (H7/g6 at assembly) without undermining mechanical integrity
- 2 aluminum **heat intercepts** at 5-10 K and 50-75 K to enhance thermal performance

Assembly interface (SSS)

Fixed support



Sliding support





Cutting the fabrics to length



Lay-up stacking



Sealed closing of mould



RTM processing
(complete manufacture cycle: 4 hrs)



Columns as de-moulded



Composite material



Constituents:

- Epoxy resin system (DGEBA type) :
 - 823 RTM by *Cytec-Fiberite*
 - Curing: 1 h dwell at 125°C
- E-glass dry fabric braids by *A&P Technology*
 - 232-mm diam. tubular tri-axial braid for column wall:
 - 51% fibre volume at 0°
 - 49% fibre volume at $\pm 45^\circ$
 - Mass/area: 1199 g/m²
 - 19-mm diam. tubular bi-axial braid for flanges:
 - fiber orientation $\pm 45^\circ$
 - Mass/area: 1041 g/m²


Composite material:

Property	Value	Comment
Glass-fibre volume fraction (Vf)	46.3%	Standard ISO 11667
Maximum void content	0.8%	1% specified


The lay-up



Braid of glass fiber




Fiber fractions




Braid layer stacking sequence


- Material sample measurements
(longitudinal direction, ASTM C-518-98)




- Support posts measurements
 - $49 \pm 10\%$ mW @ 1.9K
 - $450 \pm 10\%$ mW @ 4.5-10K
 - $7.1 \pm 5\%$ W @ 50-65K



Heat flow-meter measurements






Dimensional control of columns with *go/no-go gauges*



Dimensional control of complete support with *go/no-go gauges*


- 5% of produced columns tested
- About 2 columns over 40 produced per week, chosen randomly
- Average stiffness: **23.5 GPa**, dispersion within acceptance
- Failure to pass test (occurred on 4 supports only):
 - Segregation of resin batch production
 - 100% testing of production concerned



Shear test



Compression test






LHC Progress
Dashboard

Accelerator
Technology
Department

Support post sets



Updated 30 June 2007

Data provided by A. Poncet AT-MCS

- 4700 support posts manufactured
- 1 year for development and pre-series of 80 units
- ~3 yrs of manufacture
- 10 RTM sets (including spares for repair and maintenance)
- 7 FTE RTM operators, single shift 5 days/week
- No contractual nor technical issues

Multi Layer Insulation (MLI)



Interleaved reflectors and spacers



Velcro™ fasteners




Blanket manufacturing

Features:

- 1 blanket (10 reflective layers) on cold masses (1.9 K)
- 2 blankets (15 reflective layers each) on Thermal Shields (50-65 K)
- Reflective layer: double aluminized polyester film
- Spacer: polyester net
- Stitched Velcro™ fasteners for rapid mounting and quality closing

Production:

- ~2 km² of reflecting film
- *Ready-to-use* packaging: specific kits for cryostat type:
 - 10 blankets per dipole
 - 10 to 20 blankets per SSS
- 1 supplier for cryostats
- 1 supplier for interconnects (collaboration with IHEP-Protvino)
- 4 Yrs of production.



1 blanket on CM, 2 on thermal shield

Mock-ups for complex geometries





Diode box



Vacuum Barrier

Photo gallery of some SSS-specific components




Instrumentation feed-through pipe







Functions:

- Segmentation of insulation vacuum compartments (200m long)
 - Piece-wise installation/commissioning of LHC vacuum systems
 - Ease localisation of leaks
 - Containment of accidental vacuum degradation
 - Allow local intervention for machine maintenance
- ~ 100 Vacuum Barriers required



Vacuum Barrier (cont.d)






Main Jack

Main Requirements (main jack)

Requirement	Value
No. of Units	7000
Vertical Load	17000 kg
Transverse Load	8000 kg
Setting Resolution	0.05 mm
Adjustable range	$\geq \pm 10$ mm
Max. operating torque/force	60 Nm/25 kg
Long term stability	< 0.1 mm/year




Central Jack ("crutch")


- Developed/Supplied in the frame of a **collaboration between CERN and India's Dept of Atomic Energy (DAE)**
- Design/follow-up by the Center of Advanced Technologies (**CAT-Indore**)
- **2 series of prototypes** made first. Only minor technical difficulties in the development phase (e.g. plating and casting quality)
- Manufactured in India by **2 suppliers**
- Industrial **follow-up and QA by CAT**
 - "Smooth" seen from our side
 - Some logistics and customs difficulties
- **Full technical satisfaction** so far
- The same jacks were **motorised** for remote alignment of the **Low β triplet**



SSS Cryostat with Cold-to-Warm transitions



- “Result-oriented” assembly contract (87% contract value):
 - “Work packages” → suited to well defined work
 - Not suited to handle unforeseeable (and certainly occurring!) additional work



- ...it included provisions for hourly-rated work (13% contract value)
- Performance through shared incentives

→ Partnership is a key to success.


Assembly of dipole cryostats




Key Figures:

- 1232 units in 4 yrs
- 30 FTE workers
- 3 hydraulic assembly benches
- Peak rate of 45 units/month (on 2 shifts)

F422- Dipole assembly in cryostat (cryostating)
learning curve - SMA18



Dipole cryostat assembly



Cryo-dipole assembly tooling






Cold mass reception




Bottom tray + supports assembly



Al thermal shield rolling machine





Thermal shield + MLI assembly



Assembly bench




Outdoors storage




Key figures:

- 474 units and 136 variants
- 370 component types
- 60 FTE workers at peak production
- > 6 km of leak-tight welds
- 3300 leak detection tests
- 3.5 yrs of production

SSS assembly tooling



SSS assembly: Organization



Co-activity of 3 contractors + CERN

Assembly Activity	No. FTE	Quality assurance	No.FTE	Components center	No.FTE
Supervision	3	SSS configuration control	2	Logistics	3
Mechanical workers	6	Vacuum technicians	5	Storage	2
Welders	6	Welding inspectors	1	Components inspections	1
Electro-mechanical workers	10	Electrical checks	2		
Electricians	7				
Sheet metal workers	3				
Handling operators	3				
Totals	38		10		6

Photo Gallery of SSS





Quality Assurance: Non-Conformities (NC)



Dipole cryostat assembly:




250 NC on 1232 units:

- Mechanical: 95%
- Electrical: 3%
- Welds: 1%
- Leaks : 1%



SSS assembly:

600 NC on 474 units








QA : number of non-conformities per quarter





Weld defects by type



- 20'000 welds, (mostly manual)
- 2% of defective weld rate
- 3300 leak detection tests (40% more than initial plans)
- ~ 100 leaks (0.5% of welds)
- No "cold leaks" (but a few leaks broke open at cold)
- Some very difficult leaks to localise → several months stop for some SSS !
- Some leaks "appeared" in the tunnel → very difficult to localise



Range 10^{-2} mbar.l.s⁻¹




Material Quality


- Material defects (AISI316LN with inclusions) in a batch of material supplied by CERN to industry
- Helium leaks in flanges

Could have been avoided by:




- More severe quality control
- or 3-D forged flanges (costly!)



The cold bore tube to welding flare fillet weld The requirements



Visual defects observed in the Main Dipoles




Types of defect:

- corrosion at root
- root concavity
- root porosity
- full penetration+ corrosion

→Risk of leaks in Beam vacuum



Storage of cryostat components



- ~ 370 different components
- ...size: from several meters to a few cm!!
- **Storage space** set-up lately in the project (we hoped in "just-in-time" supply, just an illusion!!)
- **Logistics platform** (also lately set-up):
 - Prepare "kits" of components ahead of need
 - Follow-up of used parts, scraps, remaining stock and need for spares

→ **Setting-up a storage/logistics platform is a must:**


Space, resources, and methodology



A Logistics Endeavour



From "Google Earth",
Aerial view of CERN sites (~2005)




CERN, Preessin

Stored SSS

Stored Cold masses

Stored vessels



Stored Cryo-dipoles



Dipole cryostat
Assembly Hall

Magnet cold
testing facility

CERN, Point 18




Surface transports:

- Between 100 and 150 cryo-magnets transported per week
- 12000 truck journeys, **40000 km driven**
- 4 road trucks, 3 mobile cranes, 7 over head traveling cranes, 3 "ROCLA"
- 15 operators
- At one point up to **800 cryo-magnets stored** on surface


Underground:

- 47000 t of cryo-magnets installed in LHC tunnel
- 21000 km driven
- 50 operators 24h/24h, 7 days/week



Each transport equipped with transport restraints and Shocklog device


Costs of Assembled Dipole Cryostat



- 100 kCHF (~81.4 kUSD) per cryo-dipole assembled cryostat (2007 value)
- Cost/m: 6.85 kCHF/m (5.6 kUSD/m)
- Overall cost (1232 units): 122.3 MCHF (100.3 MUSD)
- Compared to 1996 costs estimates:
 - 25% cost saving on Vacuum vessels
 - 60% cost saving on MLI


(1 CHF = ~0.82 USD)

Cost break-down




- Unit cost: 114-136 kCHF (93.5-111.5 kUSD) depending on SSS complexity (2007 value)
- Average cost/m: 16.3 kCHF/m (13.4 kUSD/m)
- Overall cost (474 units): 56.6 MCHF (46.4 MUSD)

Cost break-down




- SSS positional stability and reproducibility at cold


Arc SSS (392 units)	Horizontal		Vertical	
	Mean [mm]	St.Dev. [mm]	Mean [mm]	St.Dev. [mm]
Positional reproducibility after 1 cool-down/warm-up cycle	-0.08	0.42	0.04	0.43
Cool-down movements	-0.17	0.22	-1.3	0.36



- Cryo-dipole positional stability after transport to tunnel
- Cold mass stability w.r.t. fiducials measurements on 20 cryo-dipoles



• Mean: +0.1mm; St.dev.: 0.17mm



• Mean: +0.08mm; St.dev.: 0.11mm





Arc Thermal Performance: preliminary results from sector 7-8





Static Heat In-leaks: Budget Break-down

Cryostat component	Q.ty	Overall length (m)	Overall budgeted static heat loads		
			50-75 K [W]	4.6-20 K [W]	1.9 K LHe [W]
<u>LHC continuous arc cryostat (sum of 8 sectors):</u>		22,564			
Dipole vacuum vessel (14.6 m unit length)	1232	17,938			
SSS vacuum vessel (6 m average)	438	2,617			
Interconnection sleeve (1.185 m average)	1695	2,009			
Service Module QQS	438			4	53
Longitudinal Vacuum Barrier VB	104		5,081	13	186
Magnet support post	4620		32,890	2,053	225
Thermal shield sub-assembly	3365		62,278		
Radiative insulation sub-assembly	3365			178	2,329
Instrumentation feedthrough system (IFS)	1670				888
<u>Other components (not described in this paper):</u>					
Beam Screen	3340				334
Beam vacuum feedthrough	432		526		92
Dipole corrector feedthrough (DCF)	324		2,786	526	117
Beam position monitor (BPM)	680			203	132
TOTAL [W]			103,052	2,976	4,355


- 0.2 W/m @ 1.9 K
- 0.13 W/m @ 1.9 K
- 4.5 W/m @ 50-75 K (thermal shield)




Arc Thermal Performance: preliminary results from sector 7-8 (cont.d)



- HL to Thermal Shield lower than estimated




Arc Thermal Performance: preliminary results from sector 7-8 (cont.d)



- HL to 1.9 K:
 - in average lower than estimated...
 - but some peaks still to be understood (due to leaks?)



Summary



- The **basic functions** of the LHC cryostats were recalled
- **Conceptual and technical choices** were made for an **affordable** cryostat, taking advantage from economy of scales and selecting firms on a competitive basis and on "build-to-print" specifications
- The series **production** of the **cryostat components** lasted between 3 and 4 years
- The **assembly of cryostats** was made at CERN in the frame of a "result-oriented" contract
- **Industrial-type learning curves** allowed the assembly of the about 1700 cryostats in less than 4 years
- An analytical **cost break-down** of components and assembly was presented and discussed
- Linear cost of assembled cryostats: 8 kCHF/m (**6.5 kUSD/m**)
- A larger than expected economy of scale achieved on the vacuum vessels
- Survey measurements confirm the **mechanical stability** of the cryostats
- Preliminary heat load assessments on the first LHC commissioned sector, indicate a **good thermal performance** of the cryostats



What did we get wrong (or could have done better) ?



...among the tens of stories and lessons learned we have in mind:

Contract management: surviving in the "business jungle"

- Insolvency of firms: can we avoid it? No but...
 - Risk management → reaction plans
 - Needs high reactivity
- Choose splitting contracts for risk-critical supplies: costs more but pays back at the end

Cryostat design:

- Avoid Al-Al welding if possible
- Improve design of welds for easy execution and checks

Technologies:

- Leaks in components from industry → QA
- Leaks in materials → Manufacture, QA
- Leak detection: a key competence in cryostats
 - Lack of competent personnel (in particular for localisation of leaks)
 - Industrial leak check methods is a must: "clam-shells" for example
- Welding:
 - Weld execution:
 - Proper backing (specific tooling)
 - Qualified welders
- Brazing of copper to st.steel
 - Use of acid cleaning agents → slow corrosion leading to leaks
 - A CERN qualified brazing flux exists

Production follow-up:

- QA inspections in industry:
 - Never believe blindly in paper work (certificates of conformity): repeat tests, it costs but it pays back!
 - Requires qualified and well trained inspectors
- Logistics & storage



Thank you for
your attention!