


Expected vacuum performance in CMS

Adriana Rossi AT/VAC

- CMS geometrical layout
- Vacuum calculations assumptions and parameters
- Vacuum stability results
- Residual gas density results
- Summary and conclusions
- Pure gas injection
- Baking procedure



◆ Beam pipe between sector valves



- NEG coating except bellows and pumping ports
- Approximated to cylinders

◆ Lumped pumps

- Sputter Ion Pumps at $\sim \pm 13.3$ m from IP: 3 x 8 l/s nominal.
(the size of the pump fits within the available space in the experiment)
- Sputter Ion Pumps at the two sides of TAS: 75 l/s nominal.
($\sim \pm 18.87$ m and ± 21.74 m from IP)

◆ Geometry for calculations

- Section between 2 cold magnets + Q1
- Inner diameter of TOTEM pipe = $\varnothing 50$ mm
- Pipe between 16.6 and 18.6 m from IP replaced with $\varnothing 56$ mm (modified to reduce RF losses)



◆ Synchrotron radiation

Flux to the wall assumed uniform along chamber

- $\sim 5 \cdot 10^{15}$ photons/m/s in experimental area [FZ], $\epsilon_c \sim 12\text{eV}$
- $\sim 10^{16}$ photons/m/s in LSS, $\epsilon_c \sim 12\text{eV}$

◆ Photoelectrons with energy at wall $\sim 100\text{eV}$ [AR]


◆ 2 operation periods considered when electron cloud can be neglected [VB] (physics)

- **machine start up** $\gt 7\text{ TeV} \sim 3 \cdot 10^{10}$ protons/bunch (below electron cloud threshold), 25ns bunch spacing
- **after machine conditioning** $\gt 7\text{ TeV}$, nominal beam intensity $\sim 1.15 \cdot 10^{11}$ protons/bunch, 25ns bunch spacing


◆ Ions from residual gas ionization

Ion energy

- experimental area $\sim 500\text{ eV}$ except central region ($\pm 6\text{ m}$ from IP) due to detector magnetic field
- $\sim 300\text{eV}$ in LSS





- ◆ **NEG coated sections: activated to 200°C for 24h**
 - $\eta_i = 1/10$ baked Cu surface, η_e , η_{ph} from measurements
 - **No η reduction during machine conditioning**
 - Pumping reduced 1/10 H₂, 1/3 CO and CO₂ after machine conditioning
- ◆ **Bellows and pumping ports: baked Cu at room temperature**
 - η_{ph} reduced 1/100 by photon during start-up
+ 1/100 by electrons during machine conditioning (scrubbing period)
 - η_e only reduced 1/100 by electrons during machine conditioning
 - η_i only reduced 1/100 by electrons during machine conditioning
- ◆ **Superconductive magnets: unbaked Cu**
 - η_{ph} reduced 1/10 by photon during start-up
+ 1/10 by electrons during machine conditioning
 - η_e only reduced 1/10 by electrons during machine conditioning
 - η_i only reduced 1/10 by electrons during machine conditioning



Vacuum stability


- ◆ Critical current = pressure runaway.
- ◆ $I_c > \text{ultimate current } (0.85 \text{ A}) \times 2 \text{ beams} \times 2 = 3.4 \text{ A}$



Vacuum stability

- ◆ Critical current with **reduced NEG pumping** speed to simulate partial or total saturation of the surface
- ◆ **With and without pumps @ 13.3 m** to simulate failure

NEG pumping	Pumps @ 13.3 m	Critical current	Max. stored current (A per beam)	Pre-shutdown re-activation
1 %	yes	22.1	> 0.85 (ultimate)	not required
1 %	no	9.4	"	"
0 %	yes	1.8	0.45 (0.56 nominal)	required ??
0 %	no	0.6	0.15	required




Vacuum stability

- ◆ Critical current with **reduced NEG pumping speed** to simulate partial or total saturation of the surface
- ◆ **With and without pumps @ 13.3 m** to simulate failure.

NEG pumping	Pumps @ 13.3 m	Critical current	Max. stored current (A per beam)	Pre-shutdown re-activation
1 %	yes	22.1	} > 0.85 (ultimate)	not required
1 %	no	9.4		"
0 %	yes	1.8	} 0.45 (0.56 nominal)	required ??
0 %	no	0.6		0.15

Critical current limited by CO


Critical current limited by CH₄



Vacuum stability : comments


- ◆ **Considering that if ion pumps @ ± 13.3 m fail**
 - Stored LHC current < 3 w.r.t. nominal
 - NEG reactivation time consuming (detectors opening)
 - Ultra-pure gas injection (< few tens of ppb impurity) procedure is delicate
- ◆ **and that neon or krypton (not pumped by NEG)**
 - Ne gas injected to bring beam pipe to atmospheric pressure
 - Kr (in very small quantities) released from NEG during activation
 - Cannot be pumped by turbo-molecular pumps < 10^{-10} Torr
 - More ion pumps = lower the residual pressure
= and the higher the capacity
- ◆ **it is highly recommended to keep these pumps**

◆ **NO baking = zero pumping + higher desorption**
 → NOT possible





- ◆ **Gas expected in a baked UHV system**
 - Hydrogen (H_2)
 - Methane (CH_4)
 - Carbon monoxide (CO)
 - Carbon dioxide (CO_2)
- ◆ **Hydrogen equivalent density: sum of gas densities weighted by total beam-gas scattering cross section (σ_{gas})**



$$n_{H_2equiv.} = n_{H_2} + \frac{\sigma_{CH_4}}{\sigma_{H_2}} n_{CH_4} + \frac{\sigma_{CO}}{\sigma_{H_2}} n_{CO} + \frac{\sigma_{CO_2}}{\sigma_{H_2}} n_{CO_2}$$





Machine start-up: comparison between geometries





After machine conditioning: comparison between geometries





After machine conditioning: comparison between different NEG pumping





After machine conditioning: comparison between different NEG pumping





After machine conditioning: comparison between different NEG pumping



LSS 5 @ machine start-up



LSS 5 after machine conditioning




New CMS-TOTEM beam pipe geometry where the pipe enlargement between ~ 16.6 and ~ 18.6 m from the IP

- ◆ The vacuum is stable even if the NEG pump saturates to 1/100 of its initial pumping speed
 - If the NEG is completely saturated, stored current close to nominal value
 - If the ion pumps @ ± 13.3 m fail, the stored current in the LHC will have to be limited further by a factor of > 3
 - It is strongly recommended to keep the pumps

The density profile is presented for the 2808 bunch-filling scheme

- ◆ The resultant density is higher in the region close to the modified geometry, but is understood not to be detrimental in terms of background to the experiment




[VB] V.Baglin, Chamonix XII, 2003.

[AR] A.Rossi and N.Hilleret, LHC Project Report 674

[FZ] F.Zimmermann and A.Rossi, LHC Project Report 675


These results are published in:

A. Rossi, EDMS : 536503 (AT-VAC Technical Note 04-15)



Pure gas injection

starting time	duration	activity
01/07/07 8:00	2h	transport of equipment (including bake-out)
01/07/07 10:00	2h	connection of flanges, electronics, bake-out, bottle, valves
01/07/07 12:00	1h	leak detection
01/07/07 13:00	2d	system baking + cartridge activation
03/07/07 13:00	1h	check gas quality
03/07/07 14:00	2h	injection (0.1 l/s)
	56h	
	2h	pumping
	4h	dismantling + transport



Bake-out: general procedure

