

# The DHCAL Vertical Slice Test



José Repond



SiD Meeting, by phone, October 4, 2007

# Vertical Slice Test

Necessary step before beginning construction of prototype section

Where possible use identical hardware for what is needed for prototype section

Validate RPC/GEM approach to finely segmented calorimetry  
Validate concept of electronic readout

Used some of the 104 front-end ASICs (DCAL)  
from the 2<sup>nd</sup> prototype run

Equiped 9 chambers with 4 chips each

Chambers are 20 x 20 cm<sup>2</sup>, rather than 30 x 100 cm<sup>2</sup>


→ better exposure to showers in test beam

256 channels/chamber → **2300 channels total**

**System designed such, that extension to 1 m<sup>2</sup> 'natural'** (but expensive)

Chambers interleaved with 20 mm steel-copper absorber plates  
20 mm PVC plates with hole in middle (rate measurement)

Electronic readout system (almost) identical to the one of the prototype section



## A short history

**T970**

MoU with FNAL – signed on July 16, 2007

Moved to FNAL – July 18<sup>th</sup>

Setup of experiment – July 19<sup>th</sup> (am)

Safety review – July 19<sup>th</sup> (pm)

Safety approval – July 20<sup>th</sup> (am)

First beam – July 20<sup>th</sup> (pm)

First events – July 21<sup>th</sup> (am)

Shutdown – starting August 4<sup>th</sup> (pm)

**Record  
Time**

# Setup - configurations

## Movable table

x – y motion (in 1(?)mm steps)  
With remote control (from counting house)

## RPC layer

(Default) Absorber

16 mm Steel + 4 mm Copper

Absorber for rate measurement

PVC with hole cut out

(Default) RPC with 2 glass plates

One (exotic) RPC with 1 glass plate only

Each layer 16 x 16 cm<sup>2</sup> (256 channels)

Thickness of individual layer:

Absorber	16+4 mm = 20.0 mm
RPC	3.7 mm
Pad- and FE board + ASICs	4.6 mm
Air	5.1 mm

---

Total	33.4 mm
-------	---------



## Stack with 6 – 9 layers

Maximum number of channels → 2304

## High Voltage

Using 1 Bertan unit for all default RPCs


HV = 6.2 – 6.5 kV

Using separate Bertan unit for exotic RPC


HV = 5.9 – 6.1 kV

## Gas system

Individual lines to each chamber  
Premixed gas brought from ANL



# Electronic Readout System



Attempt to be as similar as possible to what's needed for the PP







## Components

- DCAL ASIC
- Pad-boards
- Front-end boards
- Data concentrators
- Data collectors
- Timing and trigger module

- ANL/FNAL
- ANL
- ANL
- ANL
- Boston
- FNAL

## Prototyping and commissioning

Used 2<sup>nd</sup> round of DCAL prototypes  
 All other components: 1<sup>st</sup> prototypes  
 → all worked very well



## Trigger counters

Two 19 x 19 cm<sup>2</sup> scintillator panels  
Initially used three 1 x 1 cm<sup>2</sup> finger counters  
(imaging calorimeter makes these redundant)

## Additional Fe Absorber

For muon runs at 2 GeV/c stacked additional  
Fe blocks in front of RPCs

~ 50 cm deep corresponding to  $3 \lambda_I$   
→ 97% of  $\pi$  interact  
→  $\Delta E_\mu \sim 600$  MeV



## Running conditions

Beam between 6:00 – 18:00 daily  
1 spill every minute with 4 sec flat top  
Interruptions due to Tevatron shots/machine problems  
(rare...)

Rate adjusted to RPC recovery time

# MTBF

Very positive experience

Machine people very cooperative!

Beams reliable and only short interruptions

Roof still leaking, but fixed in the meantime

New laser alignment system (very useful)

Nicely labeled cable panels in test area and counting house

User area greatly improved

## Pictures from the past...






# (Some) people



Ed Norbeck (HV, ga)



Tim Cundiff (Pad-, FE-baords)



Carolyn Adams (assembly)



Dave Underwood (trigger, data taking)



Shouxiang Wu (DCOL)



José Repond (coordination, offline)




Georg Mavromanolakis (event display)



Bill Haberichter (DCON)



Eric Hazen (DCOL)



Gary Drake (electronic system)



Xia (RPC, data taking, offline)



Andrew Kreps (slow control)



Ed May (DAQ, data taking)

# Problems

## Scanning table

Sagging  
→ solution


## Humidity

Rain into the bulding (roof being repaired)  
Very humid conditions  
→ changes in the surface resistivity  
→ a few HV break downs

## Noise

Resetting slow control constants  
→ running slow control every 30 seconds  
→ new grounding scheme

**No show stoppers**



# Beams and data taking

## A) Muon runs

120 GeV protons  
Beam blocker in (1 meter of Fe)  
Steel+copper absorber plates

**Chamber efficiency/pad multiplicity**  
as function of HV and threshold

## B) Pion/positron/muon runs

1,2,4,8,16 GeV/c secondary beam  
Included Čerenkov in trigger

Requiring Čerenkov signal (positrons)  
Vetoing on Čerenkov signal (pions/muons)  
Additional Fe-absorber (muons)

**EM and hadronic showers**

Steel+copper absorber plates

## C) Proton runs

120 GeV protons  
No beam blocker  
Variable rates  
PVC absorber plates

**Rate capability measurement**

# Data Quality Monitoring

## A) Online event display and monitoring

Extremely useful for quick turn around  
Made shorter test runs redundant

## B) Offline event display

Useful to understand beam  
detect noisy layers



**Available <30 seconds after EOR**

Binary → ASCII (x,y,z,t) ntuple

## C) Offline data analysis

Useful to detect hardware problems  
obtain quick preliminary results  
decide on further runs




**Plots available <60 seconds after EOR**


# A few events... $\mu$ Calibration Runs

120 GeV protons with 1 m Fe beam block  
no  $\mu$  momentum selection


One of many perfect  $\mu$  event




$\mu$  at an angle or multiple scattering



$\mu$  event with double hits in x




$\mu$  event with  $\delta$  ray or  $\pi$  punch through




# A few events... $e^+$ Run

1 - 16 GeV secondary beam  
Čerenkov signal required


8 GeV  $e^+$  event




8 GeV  $e^+$  event



8 GeV  $e^+$  event with satellites




8 GeV  $e^+$  event




# A few events... $\pi^+$ Run

1 – 16 GeV secondary beam  
Veto on Čerenkov signal


8 GeV  $\pi^+$  event (typical)




8 GeV  $\pi^+$  event (early shower)



8 GeV  $\pi^+$  event (early shower)




8 GeV  $\pi^+$  event (early shower)



# A few events...Multiple particles


120 GeV protons without beam block

2- $\pi$  event (upstream shower?)



5 cm

3- $\pi$  event (upstream shower?)





# Conclusion

## The Vertical Slice Test was a big success

The RPCs  
Electronic readout system  
Data acquisition  
Beam

} worked very well

Expect 4 – 5 papers

**We validated the DHCAL concept and our technical approach**

→ **We are ready for the next step**

i.e. prototype

To be completed in 2007?

Larger RPCs  
Cheaper Pad- and Front-end boards  
Final data concentrators

**Identical to what's needed for the PP**

## Physics prototype

Gas and HV system ~ complete  
DCAL ASIC design finalized (no more prototyping needed)  
Data collector only need assembly  
Timing and trigger modules are done

## Test beam experience is invaluable

Much more difficult environment than lab

We were faced with many problems we did not necessarily anticipate

- Noise
- Humidity
- Grounding
- Failures

→ **We are still learning about the system**

(a 1% problem might be fatal when extrapolating by x200)

→ **Our experience is feeding back into the final design for the PP**

## Physics prototype

Necessary step before technical prototype (ILC wedge)


Can't solve all problems at once

Leave out: power pulsing, thickness optimization, maximum multiplexing,  
integrated gas and HV/LV supplies, wedge shaped geometry...

Trying to do everything at once leads to

Slow progress, no intermediate experience with detectors, many iterations, high cost...



Backup slides



x 1-12



x 12



x 10

