Updates on Shintake monitor Status

Takashi Yamanaka The University of Tokyo

2008/5/28

Nanobeam 2008 Workshop/ATF2 Project meeting

Contents

- Overview
- Schedule
- Current Status
 - Installation
 - Vibration Measurement
- Summary

Overview of Shintake monitor

- Shintake monitor
 - a beam size monitor to be installed at the ATF2 IP.
 - uses Compton scattering from laser interference fringe and electron beam in measurement
 - σ_v =37 nm measurement aimed
- Main components

 Pulsed Nd:YAG Laser
 - use 2nd harmonic 532 nm
 - Vertical Optical Table
 - Gamma-ray Detector



Schematic of Shintake monitor

Schedule

				June	July	August	September	October	November
Task	Start	Duration	End	12345	12345	12345	12345	12345	12345
Installation	4/1		6/9	6/9					
Laser Operation & Alignment	6/9	1 week	6/16	[] 6/16					
Contrast Check	6/16	3 week	7/7	6/16 3	7/7				
Position Stability Measurement	7/7	3 week	7/28	7/7	3	7/28			
Phase Stability Measurement	7/28	3 week	8/18		7/28	3 8/1	8		
Transfer of Laser Table	9/12	1 week	9/19			9/12	2 1 9/	19	
Long Distance Alignment	9/19	1 week	9/26			9/	19 🚺 9	9/26	
ATF2 Beam Operation	10/27							10/27	_

Installation status

- Now we have installed the laser and the optical table into the ATF2 beam line.
- We need to construct the actual optics before ATF2 beam operation and test the performance of the optics.



Vertical Optical Table



Pulsed Laser

Layout of Shintake monitor (in optics test)



Vibration Measurement

- measured the vibration of the optical table and the floor
- estimate the effect to the laser position jitter
- used acceleration sensors

acceleration sensor TOKKYOKIKI Corp. MGS-102S range : 0.1 – 400 Hz



Measurement Condition



Displacement Amplitude



Vibration Gain



Attachment of the Optics

• Now we have started the mount of the optics like these pictures.







Summary

- We are developing IP-BSM (Shintake monitor)
- We have started the installation of Shintake monitor
- Vibration condition is not so bad for the moment.
- We will test the optics performance by the ATF2 beam operation.