




The cosmic trigger for the Large Prototype

Th. Chaminade, P. Colas, K. Dehmelt, G. De Lentdecker, X.
Janssen, Y. Kato, H. Kuroiwa, Y. Kudenko, T. Matsuda, F.
Pierre, J.M. Reymond, S. Turnbull



The Large Prototype



Cosmics in March 08

Beam summer 08


7 panels mid 09




RECENT CHANGES

Go to U-shape fiber groove

Slab width changed to 167 mm
(better extrusion)




Y. Kudenko



Mechanics can be simple: wrapped
slabs maintained by bars (S. Hervé
for the wrapping, a drawer to be
identified for the mechanical design)

Tyvec diffuser to be ordered



Present layout:

12 slabs (+ 3 spare)

Many possible combinations, for instance:

1 top + 1 bottom : central region of central panel


3 top + 1 bottom : radial tracks on central panels

3 top + 3 bottom : vertical tracks on most of the central region

Requires a 'bridge' to support the magnet and its movement system.



Mechanics to be discussed on site

5 slabs on top




3 slabs at bottom

+4 perpendicular to limit the triggers to the detector length



First step : hands on MPPC

- Build a box with 1MPPC and one diode and a readout circuit (T. Chaminade, S. Turnbull)
- Advices from J Ch Vannel (Polytechnique), H. Kuroiwa and Y. Kato, and KEK/IPNS R&D



Second step : choose supplies

- Must be accurate and stable, low-ripple, especially around 70 V. Candidates:
 - Keithley 2612, Keithley 237
 - Modules from NIKHEF (Jos Steijger) in a Caen SY527 crate (K.Delmeht). But maybe not accurate enough
- Need also 24 channels of PMT amplifiers (if long signal cables possible) and discriminators, coincidence units

Third step : design readout and temperature control (J.-M. Reymond)

- 3 parts top, bottom parallel, bottom perpendicular.
- In each box: thermistance, peltier device
- In a central place : controler
- Design mechanics, system, cables
- Light-tightness vs accessibility

Conclusion and plans

- Need a robust system: temperature control
- Characterize MPPC, decide on supplies, Finalize design.
- Slabs delivered from mid-January
- Wrapping in Saclay 2 weeks after
- Installation in February or March
- Connexion to DAQ in March