

ILC Cavity and Cryomodule (S0-S1-S2) R&D in USA


**Shekhar Mishra
Fermilab**



High Gradient Cavity Activities

- **Cavity inventory:**
 - Fermilab in collaboration with Jlab, Cornell and ANL has 5 high gradient cavities already processed.
 - Fermilab has 26 (ILC length, 9-cell) cavities on order. 20 from ACCEL and 6 from AES. They will start arriving in March 08.
- In FY08, with remaining US-ILC funds Fermilab is going to **restart** 1.3 GHz cavity processing in spring 08.
 - We are planning ~15 cycles total using the cavities coming from ACCEL and **will be used to populate CM2.**
 - These processing will use S0 recipe but will not be “Tight Loop”
- US proposes a plan of about 60 processing and testing cycles for FY09 in support of S0 (40 R&D) and CM (20) fabrication.
- FY10 and beyond is proposed at this level in support of the High Gradient R&D.

9-cell Test Results



Average A6-8, AES2,4 = 32 MV/m

A9 reprocess at Jlab



High Gradient Cryomodule Plans

- **Fermilab has ordered all the parts for the CM2 except He vessel.**
 - This will be Type-III+ Cryomodule. **Goal is to make a S1 Cryomodule.**
 - We are going to use already existing 5 high gradient cavities plus 3 from the batch we will process in 08 and early 09.
 - Cold Mass and Tuners are being fabricated under Fermilab-INFN MOU
 - All hardware except He vessels will be here by end of summer 08.
- **Two (9-cell, 1.3 GHz) cavities will be dressed and Horizontally tested in FY08.**
- **Build CM2 in FY09.**
- **Order cold mass parts for CM3 in FY09.**
 - We already have cavities (not processed),
 - Couplers.
 - CM hardware (He Vessel, Tuner etc.) are being fabricated under the Fermilab-India laboratories collaboration.
- **Build CM3 in FY10**

- **US will provide 2 cavities for the S1 Global program.**
 - **These will be from the current batch of ILC cavities to meet the schedule.**
 - **Standard TESLA Shape cavity just the symmetric end tubes.**
 - **Fermilab could make it available to KEK without processing late FY08.**
 - **If it is needed to be processed and tested in US these two cavities could be available by end of FY09.**
 - **In our current funding guidelines (FY09) we do not have funds allocated to dress these two cavities.**
 - **We would have an internal US discussion.**
 - **Should have a plan by the Fermilab meeting.**




Cryomodule and RF Unit Test

- **ILCTA_NML will test 3 Cryomodule with beam.**
 - **Goals are much reduced to allow RF Unit beam test earliest date.**
 - **Hooks will be in place for ILC beam test later if desired.**
- **Status**
 - **DESY Cryomodule CM1 is ready.**
 - **We are preparing the safety and other necessary document to start cool down at ILCTA_NML at Fermilab.**
 - **A 10 MW Klystron is at SLAC. (US-Japan Collaboration)**
 - **Modulator (Fermilab) and RF distributions (SLAC) are under fabrication.**
- **Proposed Plan**
 - **Cool down the Capture cavity 2 and CM1 in CY08.**
 - **RF power FY09 using the 5 MW Klystron**
 - **High Gradient (>30 MV/m) CM2 should be deliver to ILCTA_NML by end of CY09.**
 - **Deliver the first Type-IV CM to ILCTA_NML in 2010-11.**




New Phase-1 Layout of ILCTA_NML





New Overall Layout of ILCTA_NML





Current Picture of NML



- **Continue Working Towards Phase-1 Goals**
 - **Complete Infrastructure to Cooldown, RF Power, and operate Capture Cavity-2 (CC2)**
 - Vacuum, RF, Cryo, Interlocks, LLRF, Controls, etc.
 - **Move CC2 to NML when infrastructure is ready**
 - **Commission Cryogenic System using CC2 and begin operation of CC2**
 - **Complete RF Infrastructure for Cryomodule-1 (CM1) - RF Power System (5 MW) and Distribution (SLAC)**
 - **Move CM1 to NML and Install**
 - **Prepare Cryogenic Infrastructure for CM1**

- **Complete Phase-1 Goals**
 - Cryogenic and RF system for CM1 Operational
 - Cooldown and RF Test CM1
- **Begin Work Towards Phase-2**
 - Begin Procurement of Injector (gun, magnets, etc.) and Test Beamline (dumps, magnets, etc.)
 - Delivery and Installation of CM2

- **US plan for ILC Cavity and Cryomodule remains same as projected during the RDR phase with the following exception**
 - **We have considerably reduced the number of Cavities we will fabricate, process and test.**
 - **We have reduced the number of CM to ~1/yr.**
- **We would continue to develop infrastructure to test 1 RF Unit with electron beam (not ILC beam)**
- **We would continue to develop infrastructure for**
 - **Cavity processing and testing**
 - **Cryomodule fabrication and testing**
- **Our goal is to be ready for “a” project by 2012**