



Cornell University
Laboratory for Elementary-Particle Physics



CESR-TA Wiggler Chambers and RFA Diagnostics

Yulin Li

Cornell Laboratory for Accelerator-Based Sciences and Education


Dawn Munson

Lawrence Berkeley National Laboratory

Work supported by NSF & DoE



1. RFA wiggler beampipe design
 - Design parameters and criteria
 - The design
2. Wiggler beampipe fabrication @ LBNL
3. RFA assembling
 - Description of the RFA assembly
 - RFA assembly process
 - Final assembly and Installation
 - Device performance




- *12 8-pole superconducting wigglers were successfully operated for CESR-c program*
- *Up to 2.2T peak field, meeting ILC-DR requirements*




RFA Diagnostic Requirements

- Measure *E*-cloud growth and suppression in wiggler field
- There RFAs located at strategic locations along longitudinal direction
- Each RFA to have capability to measure *E*-cloud distribution in transverse (*X*-axis) direction.
- The retarding field grids to be biased to >300 V, with independent potential adjustment




E-Cloud in Wiggler
(L. Wang, ILC'DR'06)






- *Must fit within the space within the cold-mass thermal shield.*
- *Install the RFA diagnostic beam pipe without disassembling and without disturbing the wiggler magnet structure*
(*Huge saving without disassemble/re-assemble the magnets !!*)
- *Ultra-high vacuum compatibility*








The Thin RFA Structure



*Reduced beam vertical aperture
by 6.5 mm to 'squeeze' in the
2.5 mm-thick RFAs*





Beampipe Design

RFA Pockets

720 (20x12x3) \AA 0.030"
holes through 0.090" wall

*SLAC Quad Cu pipe split into two half to
reduce height.*


*This provides opportunity to machine both
sides of the top half*

*Dock-under for
Flex-circuit*



The Delivered Beampipe

- *All the heavy welds are done and leak checked , by the LBNL Team, prior to the RFA assembling*



- *Two beam pipes were constructed*
 - Plain copper
 - TiN thin film (D. Wright, etc. SLAC)
- *Beampipes were received on Sept 5th at Cornell*



BERKELEY LAB
LAWRENCE BERKELEY NATIONAL LABORATORY



Fabrication of Two CESR-TA RFA Wiggler Chambers at Lawrence Berkeley National Lab

Presented by Dawn Munson

**International Linear Collider Workshop 2008
LCWS08 and ILC08**

November 17, 2008





International Linear Collider – Damping Ring Test at the Cornell Electron Storage Ring (CESR)


- Lawrence Berkeley Lab (LBNL) in collaboration with Cornell built two Wiggler Vacuum Chambers for Electron Cloud Suppression and CESR-TA Studies.
- Two wiggler chambers were fabricated, assembled, and dimensionally measured at LBNL, Summer 2008.
 - Longitudinal slitting of chambers
 - Machining of all chamber details and peripheral hardware.
 - Facilitated the electron beam welding of the chamber halves and water cooling channels
 - Performed welding of exterior hardware
 - Zeiss measurements of the chamber profiles

Wiggler Chamber Cross Section Schematic

Electron Beam
Weld – Two Seam
Welds

Chamber Split &
Weld Prep

Electron Beam
Weld – All Around
Cooling Channels




Cooling Channels

Chamber Machined
Features


Step 1: Inspect and Measure Extrusions as Delivered

Extrusion QC-4-2-Left Side




Straightness and Flatness of Y Axis Line and Bottom Plane



Flatness of Plane Left Side




Step 2: Split and Machine Extrusion Chambers



Step 2: Split and Machine Extrusion Chambers




Step 2: Split and Machine Extrusion Chambers




Detail of 0.030" Ø holes
for the RFA.

Two wiggler chambers, RFA covers and water channels. Parts are completely machined and UHV cleaned.




Step 3A: Measurement of Split Chambers

Extrusion QC-4-2-Left Side- After Cutting



Straightness and Flatness of Y Axis Line and Bottom Plane


Flatness of Plane Left Side



Step 3: Electron Beam Weld Test


- LBNL machined, prepared and cleaned two scaled sample chambers to validate the electron beam welding process.
 - Sample chambers:
 - 10 inches in length.
 - Machined from the same extrusion material
 - Small diameter holes drilled for electronics, for proof of process
 - Water channels:
 - Scaled to match the $\sim 1/7$ size of the chambers
 - Copper material identical to material used for full size
 - Inlet/outlet holes for pressure testing

Step 3: Electron Beam Weld Test



Fit up of weld test chamber


Step 3B: Electron Beam Weld Test



Step 4: Electron Beam Weld Wiggler Chambers

- All welds completed in vacuum with CNC electron beam welder.
- Chambers held in vacuum to minimize oxidation.
 - No oxidation was found.
- Electron Beam Weld Process:
 - ‘Duck Under’ cover welded and visually inspected by LBNL.
 - Longitudinal seam welds
 - Leak check of chamber
 - Water channel welds
 - Leak check of chamber and water channels
 - Pressure test the water channels to 90 psi

Step 4: Electron Beam Weld 'Duck Under' Cover, Chamber Seams and Water Channels





Machined detail

'Duck Under' cover,
welded internally

Electron beam welded joints

Step 5: Dimensional inspection on Zeiss Coordinate Measuring Machine






Step 6: Copper to stainless transition profile cut to match the chamber profile.

Each transition is pedigreed to the chamber.


Step 7: Welding of External hardware



Step 7: Welding of External hardware



All welding was performed in an isolated environment with an Argon purge.



Final Steps:

- Steam cleaned chambers.
- Properly packaged and wrapped both chambers.
- One was chamber sent to SLAC for TiN coating.
- Upon completion, both chambers were sent to Cornell for installation.





BERKELEY LAB

LAWRENCE BERKELEY NATIONAL LABORATORY



Special Thanks to the LBNL Main Machine Shop Personnel

Guy Pulsifer

Rick Kraft

Dan DeBoer

John Haugrud

Machinists

Brian Bentley

Mark Campagna

Kit Mui

Dave Paulson

Manny Pereira

Welding

Tim Williams

Bob Conroy

Leak Checking

Jim Dougherty

Frank Zucca

Dan Colomb

Inspection

Bob Connors

Cleaning

Chris Redding






Dennis Paiva

Support Hardware

Paul Knopp




Prepare the Wigglers - Extract Old Beampipe



- Cut off beam pipe flange
- Cut through SST flexible disk with a hole-saw
- Remove large insulation vacuum flange
- Cut off residual flexible disk
- Pull out the remaining beampipe
- Magnet check out




The Thin RFA Structure



- *Three RFAs at strategic wiggler field locations*
- *Each RFA consists of 12 'pads'*
- *Retarding grids bias individually*
- *Collector made of Cu-Kapton flexible circuit*




Retarding Field Grid






Flexible Circuit as Electron Detector



- *1-mil copper on both sides of 4-mil Kapton strip, 35" in length*
- *Minimize collect-side dielectric surface area*
- *Guard electrodes around collectors, biased at the same as collectors*
- *Locating pin-holes for precise positioning of the collector pads, w.r.t. the holes on the beam pipe*




Flex-Circuit Preparations



- *Having lots of problems with Au-based UHV solder. End up using Sn63Pb37 Flux cored solder. (Vacuum tests were done to confirm its UHV compatibility.)*
- *Circuit connect pads (and all wires) were tinned, and solvent cleaned, then followed by 150°C-24hr bakeout in vacuum.*
- *The fully prep-ed circuits were taped with UHV Kapton tapes (with silicone adhesives), with only collector pads exposed, to prevent electric shorts. Carefully 'roll' out all air bubbles under the tapes.*




Install the grids



- *Small Ni-pads were spot-welded to the Au-coated SST grids, and tinned, cleaned*
- *The sandwiched grid assemblies were screwed to the chamber*
- *Three grids were individually connected using Kapton coated wires, soldered to the Ni-pads*




Insert the collector Flex-Circuit




Through the "Tunnel"




RFA Connections




Soldering Table



42 soldered wires and strain-relieve




Final Connections through three 15-pin D-type vacuum feedthroughs



Flex Circuit pinned down to the grid ceramics




Checking, Checking and Checking




Leak checking before EB-Weld



RFA Vacuum Cover EB-Welding



Test welds for E-beam parameters
and temperature control




- *RFA vacuum cover thickness was increased at Cornell to increase safety factor*
- *EB-weld parameters: 35 mA (Sharp focusing ~0.5 mm beam spot) @ 30 IPM; 1-mm penetration*
- *$T_{max} < 100^{\circ}\text{C}$ during E-beam welding*







Final Trimming to Length





- *After successful RFA vacuum cover EB-weld, both beampipes were leak checked and followed by 120°C/48hr bakeout to degas from the RFA components*
- *The beam pipes were then trimmed to their final length for insertion into the SCW magnets. Large flow of dry N₂ to keep pipe clean, and clean lint-free clothes were used to stop metal shavings*
- *Final parts dry-fit and adjustment before insertion into the SCWs*




Beampipe Insertion and Survey




- *Trimmed beampipe was wrapped with super-insulation, and insert into the warm-bore of the wiggler magnet*
- *And the beam pipe was adjusted and locked at desired position w.r.t. the wiggler magnet by the survey screw*



*Heat control and N2 purge
throughout many steps of
welding*










Finally Done

Final Leak checking and
hot-water bake on 10/22




Swapped wigglers on 10/24



*Both RFA wigglers were reached
full field (@140 Amp) with only
a few 'training'*




Vacuum Performance in CESR



→ Vacuum beam conditioning similar for the RFA wiggler chamber to the 'regular' wiggler chamber

→ All RFA devices are working





- *Many thanks to the LBNL team for fabrication of two chambers, on schedule*
- *The project is also a results of dedicated work by a Cornell Team, including*
 - *Brian Clasby - All the welding (EB, TIG, BT)*
 - *M. Carrier - RFA Electric work*
 - *Eric Smith - Wiggler preparation, final assembling*
 - *J. Sikora, S. Greenward - RFA Assembling*
 - *Tobey Moore - Vacuum support, and last-minute modifications*
 - *Newman Machine Shop - Specially N. Alexander*
 - *And many other technical supports*