



ILC 08 Final Plenary Summary

CFS - CONVENTIONAL FACILITIES AND SITING GROUP

V. Kuchler, J. Osborne, A. Enomoto



CFS Parallel Session Topics

- ***Process Cooling Water and HVAC Review***
- ***Klystron Cluster Design***
- ***CLIC/ILC and XFEL/ILC Collaboration Planning***
- ***Minimum Machine Design***
- ***Alternate Site and Tunnel Configuration***



Process Cooling Water and HVAC Review

Session Objective: Select one of the alternatives presented as the baseline to be included in the Technical Design Report (pending Klystron Cluster R&D results).

- ***Alternative Process Water Configurations were Presented by FNAL and KEK***
- ***Talks were also Presented for ILC HVAC Design, CLIC Process Water and HVAC Design and Life Safety Aspects of Ventilation Systems Design***
- ***An Alternative was Selected by M. Ross as a Back-up Design to the Klystron Cluster Alternative***
- ***This will Conclude the Current Value Engineering Exercise for the ILC Process Cooling Water System***



Global Design Effort - CFS

RF Water Delta T	25C DT (45F DT)									40C DT (72F DT)						Kly Cluster-Aug 2008		
	Scheme 5			Scheme 6			Scheme 7			Scheme 5			Scheme 6				Scheme 7	
	SS	CPVC	CS	SS	CPVC	CS	SS	CPVC	CS	SS	CPVC	CS	SS	CPVC	CS		SS	
Impact / Issues (by others)																		
Cost to be added (could be by others?)																		
Major IMPACT/ Issues?																		
SS=Sch 10 304 Stainless in Tunnel only ; CPVC=Sch 80 CPVC plastic pipe; CS= Std Sch (40) Carbon Steel																		
Overall Water Delta T	°DC	16.7			16.5			18.1			20.3			19.6			22.4	22.1
	°DF	30.1			29.7			32.6			36.5			35.2			40.4	39.8
"First-Cost" Savings in % - Process/Air Treatment WBS 1.7.3. & 1.7.5		28%	30%	31%	23%	25%	26%	30%	32%	33%	31%	33%	32%	26%	28%	27%	35%	-47%
RF Loads and Circulators reduced flow																		
RF Modltrs and Plse Transfm-flow/temp																		
Watercooled wvgde cooling design (by others)																		
Kly Clstr's RF Pipe Cooling by others																		
High Space Temperature ok?		~45°C (113°F)									~45°C (113°F)							
Equipment Insulations??																		
50% reduction in air heat load possible?																		
Finalize HLRF Heat Load table? Collector issue?																		
Rack chiller impact ok? / Rework rack arrngmt??																		
Confirm reduced Heat load from racks?																		
Cost for increased maintenance due high space																		
Cost of portable cooling for maintenance																		
Pump Recirc loop at Collector- \$2M??																		
Pump Recircloop (modul/P.Transfmr)- \$2M ??																		
Electrical Reduction		~ (-2.3 MW)									~ (-2.3 MW)							
Operational cost reduction		~ (-??)									~ (-??)							
Electrical addition					~ +3 MW			~ +1 MW						~ +3 MW			~ +1 MW	??
Operational cost addition					+ ??			+ ??						+ ??			+ ??	
Pipe Press & Temp limit issues																		
"Clean Water" Compatibility Issue																		



Klystron Cluster Design

Session Objective: Establish an understanding within the technical groups of the CFS design and cost savings associated with this Klystron Cluster alternative.

- ***CFS Analysis of Klystron Cluster Alternative was Presented***
- ***Discussion with Main Linac Area System and Technical System Representatives Followed***
- ***Agreement was Reached that CFS Analysis was Adequate and Acceptable as Provided***



CLIC/ILC Collaboration Planning

Session Objective: Develop plans of action with milestones for the ILC/CLIC collaboration efforts in the coming year.

- **Several Items were Identified for 2009**
 - **3D Modeling for ILC Using CATIA Software**
 - **Collaboration on Alternate Tunnel Configuration**
 - **Drawings for ILC RF Cluster Design**
 - **Assist in Shallow Site Studies**
 - **Study for ILC Installation Methods**
 - **Continuing Collaboration on Process Cooling and HVAC Design**
 - **Development of a Common Document Describing Underground Safety Considerations for ILC and CLIC**
- **Specific Resources will be Identified in the Weekly CFS Video/Webex Meetings**



XFEL/ILC Collaboration Planning

Session Objective: Develop plans of action with milestones for the ILC/XFEL collaboration efforts in the coming year.

- ***Discussion Centered on Upcoming CFS Visit to DESY in December, 2008***
- ***Agenda Items Identified:***
 - ***Process Water Systems***
 - ***Electrical Requirements***
 - ***HVAC Design***
 - ***Civil Construction Process***
 - ***Criteria Identification and Configuration Control***
 - ***Safety Issues***
 - ***EDMS***
- ***6 ILC CFS Members and 1 ILC Project Manager will Participate***



Minimum Machine Design

Session Objective: Identify specific tasks and milestones for CFS evaluation of the Minimum Machine Design concept and how it might be included in the TDP

- ***CFS has Re-established the Area System Points-of-Contact***
- ***3D Software will be Employed to Facilitate the Analysis of the New Machine Configuration and Alternatives***
- ***Cost Analysis for CFS Impact of Various Alternative Configurations will also Need to be Completed***



Alternate Site and Tunnel Configuration

Session Objective: Develop the CFS plan to evaluate all tunnel configuration alternatives with specific emphasis on what can be completed by the AAP Review in April, 2009 and through 2010.

- **Work Completed to Date was Presented**
- **The Entire CFS Group will Contribute to this Effort as well as Collaboration Partners**
- **Substantial Progress is Anticipated by the AAP Review in April, 2009**
- **Work will be Completed in 2009**



Global Design Effort - CFS

