

Helical Undulator Status


Jim Clarke ASTeC, STFC Daresbury Laboratory





- STFC are building a full scale 4m undulator module which is needed for the positron source
 - → 2 x 1.75m undulators
 - → RDR parameters
 - → Stand-alone cryosystem
- Previously several short prototypes were completed and focus is now on manufacture and testing of 4m cryomodule.





- Undulator I
 - Manufactured and fully (vertically) tested
 - Now being e-beam welded to bellows
- Undulator II
 - Manufactured and magnet tests have started
- Cryomodule
 - All major components and tooling at RAL except helium bath (delivery 2 to 3 weeks)
 - Turret undergoing trial assembly
 - Module trial assembly to start when bath delivered
- Plan
 - Complete end June bath and Und II tests on critical path



Vac Vessel, Turret, Und II



(ASTEC. Vertical test stand






(ASTEC. Helium Bath at Manufacturers





(ASTEC. Thermal Radiation Shield



(ASTEC. Turret (trial assembly)





Undulator Measurements

- 1.75m module mounted vertically in liquid helium bath
- 2m carbon fibre rod with two hall probes mounted orthogonally to each other and undulator axis
- Logging system controls a stepper motor to move the probe through the undulator and then take voltage readings from the two hall probes
- Probes can be orientated in 8 directions (0, 45, 90, 135, 180, 225, 270, 315 deg)






(ASTEC. Measurements Taken - Magnet 1

- Have taken two measurements (at least) of whole undulator in each of 4 probe directions (0, 90, 180, 270), each measurement is with two probes so we therefore have at least 4 sets of data in each direction.
- Also have repeated measurements of each end (50mm long, top and bottom) in each of the 8 directions.
- Have also quench tested the magnet.

(ASTEC) Example Field Map




Field measured at nominal current of 215 A RDR Field level (0.86 T) achieved for the first time in a full length magnet (peak field is 0.88 \pm 0.014 T)



Undulator Period


- Undulator periods measured by identifying positions in fieldmap where B=0T
- Mean period length found to be 11.48mm with std dev 0.02mm
- RDR period length is 11.5mm





Trajectories


- Trajectories were modelled using SPECTRA
- Trajectory models show good repeatability when probes are in the same orientation
- Using uncorrected raw data trajectories see curvature due to biases in the hall probes






Trajectories

- Have corrected for voltage offset by looking at average voltage values in zero field regions before the probe enters and after it exits the undulator's field
- Assumed linear variation in offset along undulator's length
- This correction improves the trajectories, however further improvements are expected after taking measurements with no magnet in the cryostat





- Peak field strength when magnet quenched during training shows that the superconductor is stable up to ~1.1T
- Also shown is the RDR field specification (0.86T)
- Good safety margin for long term operation of ILC



- The 4m full scale cryomodule is in the final stages of manufacture
- It will be completed this summer
- The vertical magnet tests for the first ever 1.75m undulator are excellent