



# ATRO based readout Design overview



## Need at testbeam:

- 80 FEC (~10000 channels)
- 4 RCUs (modified)
- 2 DRORCs
- 1 DAQ computer
- 1 local control computer
- 1 DBOX (local trigger/distributor box)
- 1 TLU (common trigger box)
- 1 Interface to Common DAQ/monitoring

# Current standalone test setup in Lund



### **NEXT STEPS:**

second FEC prototype mid July (need input from CERN about reference voltages)  
interface to DBOX  
updated RCU firmware (40MHz clock...) - ready in ALICE mid june (not got it yet)

### **FURTHER STEPS:**

cables FEC – pad planes  
mechanics  
need 10000 channels (PCA+ALTRO 20/40MHz) – all not yet available/tested/bought  
final RCU/DRORC/PCs for test beam - not yet ordered (list sent to CERN...)  
80 FEC to be produced after second prototype found working  
ALTRO backplane  
Local test with > 1 DRORC  
Implementation in a common DAQ framework