



Comments from LLRF

Shin Michizono (KEK)

Brian Chase (FNAL)


Stefan Simrock (DESY)

- LLRF performance under large dead time
- Questionnaire



Klystron cluster

- The configuration of klystron cluster introduces total 10~15us latency.
 - > larger latency than our current model (<1us)
 - 3.5us (rf transmission)
 - 1us (ADC detection at each 26 cavities in the tunnel and conversion to optical signal of 26 vector sum)
 - 6us (optical transmission)
 - 1us (conversion and vector sum of 27 units)
 - 1us (DAC outputs to 27units)
- LLRF detectors will be located in the tunnel (and process each 26 cavities).
 - > risks of high availability and maintainability



With extra transmission loss, feeds ~27 RF units = 1.026 km. (shaft serves 2.052 km)

03/09/2008

SCRF meeting (Sep.3, 2008)



Background (required stability)

- Lrf stability requirements (@ ML and BC) are $< 0.07\%$, 0.24deg .
- In order to satisfy these requirements, FB with proper FF control will be carried out.
- Each error source should be $< 1/3$ of requirements ($< 0.02\%$, 0.08deg .)

TABLE 3.9-1



Summary of tolerances for phase and amplitude control. These tolerances limit the average luminosity loss to $< 2\%$ and limit the increase in RMS center-of-mass energy spread to $< 10\%$ of the nominal energy spread.

Location	Phase (degree)		Amplitude (%)		limitation
	correlated	uncorr.	correlated	uncorr.	
Bunch Compressor	0.24	0.48	0.5	1.6	timing stability at IP (luminosity)
Main Linac	0.35	5.6	0.07	1.05	energy stability $\leq 0.1\%$



Operational gain and bandwidth

- Error is only compressed by a factor of gain
- Current proportional (P) control + FF is not sufficient due to lower gain
- PI (proportional and integral) control will be necessary
- Gain margin is calculated from Bode-plot.




Latency	1us	10us	15us	15us PI
Maximum gain	200	25	15	15
Bandwidth [kHz]	230	25	17	17

Maximum operational gain is defined as 1/5 of gain margin. (taking account of the FLASH's gain margin (200) and operational FB gain (40)).



Step response of Ilrf control

- 15us delayed system has slower response.
- Blind time of 15us and slower response degrades the total FB performance.







External perturbations

■ Assumption

- Cavity Q: 3×10^6 -> decay time constant = $462 \mu\text{s}$ and $f_{1/2} = 217 \text{ Hz}$
- All signals change in this time constant
- After $15 \mu\text{s}$ of blind time, system changes 2% of perturbation (still large even though the time constant is slow).
- Rough estimated delay would be $30 \mu\text{s}$ dead time (4%) including the slow response time.

■ Example 1: Detuning changes (microphonics or Lorentz force) by 20 Hz (5 deg in phase) during rf operation.

- Cavity phase changes by 0.2 deg . ($= 5 \text{ deg} \cdot 4\%$) and all the error budget is used for this.






FB latency and lrf performance (2)

- Example 2: Kly HV change (1%, ~1.25% in amplitude) during rf operation.
 - Cavity amplitude changes by 0.034 % (=1.25%*4%).
- Example 3: Kly HV change (1%, 12 deg. in phase) during rf operation.
 - Cavity phase changes by 0.48 deg. (=12*4%) far from our goal of <0.1deg.
- We can not know the perturbation for first 15us and we need another 1us to detect error and >15us to recover. So total **performance is poorer in case of 15us delay.**
- Despite slow rf time constant of SC cavity, blind time of 15us is large enough for the difficulties in field regulation.

Questionnaire



- (1) What kind of power combiner is used?
 - Hybrid-type power combiner lose 20MW in case of one klystron failure.
- (2) Strategy of cavity configuration
 - How will you locate the cavities of lower quench limits?
 - How much the residual errors of loaded Q and tap-off control (<+/-3%?)?
- (3) Upstream rf distribution is not suitable for the beam loading compensation.
 - because rf and beam timing is not synchronized (7us difference).
 - vector sum is not correct due to the different beam timing.



Comments from LLRF(1)

1. Field regulation

- field regulation **worse but may be still ok**
- higher stability of all subsystems required
- **robust** against perturbations or parameter changes
significantly **reduced**
- operational **field/current limits will be lower**
- difficulties with feedforward due to delay between rf and beam (upstream rf distribution)
- should use fast klystron loops to reduce HLRF errors.



Comments from LLRF(2)

2. Availability

- **exception detection** and handling severely limited
- **hot spare concept** cannot be implemented

3. Operational

- Cannot simply turn on-off (or by-pass or manipulate) individual rf stations for commissioning, operational or diagnostic purposes.
- Setting up linac cannot be done by incrementally adding or controlling rf stations
- Operation close to performance limit (cavity quench, field emission, klystron saturation) will **become much more challenging.**