



# **Global R&D Effort of Superconducting RF Technology for the International Linear Collider**

**Akira Yamamoto, Marc Ross, and Nick Walker**

**ILC-GDE Project Managers**

**and**

**Kaoru Yokoya**

**ILC-GDE Asian Regional Director**

Visiting Institutions in Beijing, China, December 9-10, 2008



# First of all

- **We would thank** for the opportunity to visit to
  - Beijing University (北京大学),
  - Tsinghua University (清华大学),
  - IHEP (高能研)
- today, representing ILC-DGE with
  - **Kaoru Yokoya (横谷馨; KEK) : Asian Reg. Director**
    - Leading KEK LC Office and Programs
  - **Marc Ross (Fermilab): Project Manager**
    - Global system and Conventional Facility,
  - **Akira Yamamoto (山本明 : KEK) : Project Manager**
    - Superconducting RF and Main Linac Technology,




# Outline

- **Introduction**
- **R&D Status**
- **Plan for Technical Design Phase**
- **Global Plan and Project Management**
- **Summary**



# Particle Physics to study Early Universe



## ■ Particle Physics

- Study history of early Universe


## ■ Particle Accelerators

- A tool to investigate high-energy particle interactions in early Universe






# GDE ILC Timeline






# GDE ILC Timeline





# Towards a Re-Baselining in 2010



- **Process**
  - **RDR baseline & VALUE element are maintained**
    - Formal baseline
  - **Formal review and re-baseline process beginning of 2010**
    - Exact process needs definition
    - Community sign-off mandatory



# ILC08 Working Groups

## 1. Sources

- Axel Brachmann (SLAC)
- Jim Clarke (STFC DL)

## 2. Damping Rings

- Mark Palmer (Cornell)
- Andrzej Wolski (CI/UL)
- Junji Urakawa (KEK)

## 3. Main Linac

- Chris Adolphsen (SLAC)
- Hitoshi Hayano (KEK)

## 4. BDS/MDI


- Deepa Angal-Kalinin (CI DL)
- Andrei Seryi (SLAC)
- Hitoshi Yamamoto (Tohoku U.)

## 5. CFS

- Vic Kuchler (FNAL)
- John Andrew Osborne (CERN)
- Atsushi Enomoto (KEK)

## 6. Simulations

- Kiyoshi Kubo (KEK)
- Daniel Schulte (CERN)
- Nikolay Solyak (FNAL)





# Fields and the Roles of Superconductivity in Particle Accelerators

## Acceleration

- **Electric Field:  $E$**


- Static,
- RF

## Beam Handling

- **Magnetic Field :  $B$**


- Bending  
( Dipole Magnet )
- Focusing  
( Quadrupole Magnet)

Superconductivity takes  
an essential role






# Development of H.E. Accelerators



■ With high magnetic field required



$$p = q \cdot \rho \cdot B$$

$$P [\text{TeV}/c] = 0.3 \cdot \rho [\text{km}] \cdot B [\text{Tesla}]$$



# Progress in H.E. Proton Accelerators with Superconducting Magnets


Accelerator	Tevatron	SSC	HERA	RHIC	LHC
Lab.	FNAL	SSC	DESY	US	CERN
Energy [TeV]	0.9	20	0.82	0.1/anm	7
Radius [km]	1	14	1	0.5	4.5
Ring	1 (p+p-)	2 (p+p)	1 (e+p)	2 (p+p) &	p+p-
B-dipole [T]	4.4	6.6	4.7	3.5	8.36
G-quad [T/m]	76	205	91	72	220
R-coil [mm]	38	25	37.5	40	28
#Dipoles	774	7986 (676)	422	288	2x1232
Temperature [K]	4.5	4.4	4.5	4.5	1.9
Complete year	1985	Canceled	1990	2000	(2007)
Note	First SC large Accelerator	Few training quench	First industrial contribution	Economical	Highest field SF-He





# Progress in H.E. Proton Accelerators with Superconducting Magnets

Accelerator	Tevatron	SSC	HERA	RHIC	LHC
Lab.	FNAL	SSC	DESY	US	CERN
Energy [TeV]	0.9	20	0.82	0.1/anm	7
Radius [km]	1	1.1	1	0.5	4.5
Ring	1 (p+p-)				p+p-
B-dipole [T]	4.4				8.36
G-quad [T/m]	76				220
R-coil [mm]	38				28
#Dipoles	774				2x1232
Temperature [K]	4.5				1.9
Complete year	1985				(2007)
Note	First SC large Accelerator	Few training quench	First industrial contribution	Economical	Highest field SF-He









# LHC Superconducting Magnets

- Diameter: 27 km
- Energy 2 x 7 TeV
- SC Magnets
- Dipole field 8.4 T,





LHC DIPOLE : STANDARD CROSS-SECTION



Successful international collaboration including Asia



# CERN-LHC Interaction Region Focusing Magnets





081209

CERN KEK-Fermilab Collaboration  
ILC Global Design Effort






# Superconducting Magnets for for CERN-LHC Experiments



**CMS**

**ATLAS**




Al-stabilized NbTi  
SC Magnets



ILC Global Design Effort



- International Linear Collider (ILC)





# Particle Accelerators

## beyond limit of circular accelerators



Energy loss must be replaced by RF system  
cost scaling  $\$ \propto E_{cm}^2$

Electron machine

Ring accelerator

>> Linear Accelerator





# Outline



- Introduction
- **R&D Status**
- Plan for Technical Design Phase
- Global Plan and Project Management
- Summary




# Reference Design

**Released in Beijing, Feb. 2007**

- **SC linacs: 2x11 km**
  - for 2x250 GeV
- **Injector centralized**
  - Circular damping rings
- **IR with 14 mrad crossing angle**




Parameter	Value
C.M. Energy	500 GeV
Peak luminosity	$2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Beam Rep. rate	5 Hz
Pulse time duration	1 ms
Average beam current	9 mA (in pulse)
<b>Average field gradient</b>	<b>31.5 MV/m</b>
# 9-cell cavity	14,560
# cryomodule	1,680
# RF units	560





# Technical Design Report to be completed by 2012



Reference Design, 2007 >> Technical Design Phase, 2008-2012  
We are now at the stage of progressing from the RD to TD





# TDP Goals of ILC-SCRF R&D

## ■ Field Gradient

- 35 MV/m for cavity performance in vertical test (S0)
- 31.5 MV/m for operational gradient in cryomodule
  - to build two x 11 km SCRF main linacs

## ■ Cavity Integration with Cryomodule

- “Plug-compatible” development to:
  - Encourage “improvement” and creative work in R&D phase
  - Motivate practical ‘Project Implementation’ with sharing intellectual work in global effort

## ■ Accelerator System Engineering and Tests

- Cavity-string test in one cryomodule (S1, S1-global)
- Cryomodule-string test with Beam Acceleration (S2)
  - With one RF-unit containing 3 cryomodule



# Why Field Gradient Limited in SC Cavity ?

## Current major reasons

### ■ Field Emission




- due to high electric field
- around “Iris”

### ■ Quench

- caused by surface heating from dark current, or
- magnetic field penetration.
- around “Equator”

### ■ Contamination

- during assembly





# R&D Efforts Required

## ■ Fabrication:

- Forming and welding (EBW)

## ■ Surface Process:

- Chemical etching

- Electro-polishing

- Cleaning



- Ethanol, Detergent, Micro-EP

- High pressure water rinsing

## ■ Inspection/Tests:

- Optical Inspection (warm)

- Thermometry (cold)







# Progress in Single Cell Cavity

TABLE II. CAVITY SHAPES STUDIED FOR THE ILC.


Parameter	TESLA	LL/IS	RE
Iris aperture (mm)	70	60/61	66
$E_{\text{peak}}/E_{\text{acc}}$	1.98	2.36/2.02	2.21
$B_{\text{peak}}/E_{\text{acc}}$ (mT/(MV/m))	4.15	3.61/3.56	3.76
Char. shunt impedance: $R/Q$ ( $\Omega$ )	114	134/138	127
Geometric factor: $G$ ( $\Omega$ )	271	284/285	277
$G \times R/Q$ ( $\Omega \times \Omega \times 10^5$ )	3.08	3.80/3.93	3.51



- Record of **59 MV/m** achieved with the RE cavity with EP, BCP and pure-water rinsing with collaboration of Cornell and KEK



# Status of 9-Cell Cavity



## ■ Europe

- “Gradient” ( $<31.5>$  MV/m) with Ethanol rinse (DESY):
- Industrial (bulk) EP demonstrated ( $<36>$  MV/m) (DESY)
- Large-grain cavity (DESY)
- Surface process with baking in Ar-gas (Saclay)

## ■ America(s)



- Gradient distributed (20 – 40 MV/m) with various surface process (Cornell, JLab, Fermilab)
- Field emission reduced with Ultrasonic Degreasing using Detergent, and “Gradient” improved (JLab)

## ■ Asia

- “Gradient”, 36MV/m (LL, KEK-JLab), 32 MV/m (TESLA-like, KEK)
- Effort in Chinese laboratories in cooperation with KEK, Fermilab, Jlab, and DESY
- Effort in Indian laboratories in cooperation with Fermilab, KEK



# Field Gradient progressed at TESLA



ILC operation :

- $\langle 31.5 \rangle$  MV/m

R&D Status :


- $\sim 30$  MV/m to meet XFEL requirement

• 20 % improvement required for ILC



## 6th cavity production – rf results

- excellent + promising first results including first Plansee nine-cell (AC115)
- Z141 as first cavity with surfaces damages after fabrication under investigation




Detlef Reschke, DESY  
MAC DESY, May 08, 2008



- The average gradient, **36 MV/m, achieved** with AC115-118



# Progress in American Laboratories with Japanese contribution for ICHIRO-5




A (Accell), AES: TESLA shape, ICHIRO: LL shape




# Progress at KEK



Coupler Processing at room temp.



Comparison of achieved  $E_{acc,max}$   
Vertical tests and Cryomodule tests




Ave.  $E_{acc,max}$  (V.T) = 22.7 MV/m

Ave.  $E_{acc,max}$  (Cryo.) = 23.0 MV/m



# SCRF Activities in Asia

- **Participation in STF at KEK**
  - Cryomodule and coupler design (IHEP)
  - 9-cell cavity fabrication (PAL)
  - LL single cell (IHEP)
  - Cavity design/processing (PNU/KNU)
  - Joining STF operation (RRCAT)
- **China**
  - Cavity fabrication (Deep drawing, EBW, CB) (IHEP, PKU.)
  - Large grain cavity (Ningxia, PKU)
- **Korea**
  - Works other than SCRF (RTML design, cavity BPM, DR)
- **India**
  - Nb material investigation
  - Cavity fabrication in cooperation with **FNAL**
  - Cavity process in cooperation with **KEK**





# Combined Yield of Jlab and DESY Tests Reported at TTC (Delhi, Oct. 2008),



summarized by H. Padamsee

48 Tests, 19 cavities

ACCEL, AES, Zanon, Ichiro, Jlab

23 tests, 11 cavities

One Vendor



Yield 50 % at 35 MV/m being achieved by cavities with a qualified vender !!  
***We would thank Technical Guidance given by TTC***



# Outline

- Introduction
- R&D Status
- **Plan for Technical Design Phase**
- Global Plan and Project Management
- Summary



# Plan for High Gradient R&D

1: **Research/find cause** of gradient limit

**high resolution camera**

**surface analysis**

2: **develop countermeasures**

**remove beads & pits,**

**establish surface process**


3: **verify and integrate** countermeasures

**get statistics**



# A New High Resolution, Optical Inspection

For visual inspection of cavity inner surface.




Camera system (7µm/pix) in 50mm diameter pipe.






# Progress in Profile Measurement




## Stripe Illumination(SI)




- Fourteen Electro-Luminescence(EL) strip sheets are 10mm in axial direction and cover 100mm in azimuthal direction.
- These fourteen strips can be turned ON/OFF one by one.
- Assuming that cavity's interior surface is a complete mirror, we can measure wall gradients of the cavity's interior surface with these ELs.



TTC Meeting at DESY, January 14 - 17, 2008




TTC Meeting at DESY, January 14 - 17, 2008




TTC Meeting at DESY, January 14 - 17, 2008

## Wall Gradient Measurement




TTC Meeting at DESY, January 14 - 17, 2008




TTC Meeting at DESY, January 14 - 17, 2008

## Wall Gradient of spot at #3 cell 168°



TTC Meeting at DESY, January 14 - 17, 2008

## Wall Gradient of spot at #7 cell 325°




TTC Meeting at DESY, January 14 - 17, 2008



# Consistent with Thermal Measurement at FNAL

3<sup>rd</sup> Test Results






84 $\mu\text{m}$  height




60 $\mu\text{m}$  height

~21mm

43 $\mu\text{m}$  height



AES01 has hard quench at 15MV/m,  
its location was identified by Cernox at FNAL,  
(M. Champion et al., This conference)




Kyoto camera found 3 spots in their exact location

ILC Global Design Effort



# DESY: Field Emission Analysis




Cavity gradient shifted to High Gradient by 'ethanol rinse', except for "lowest two" (due to different reasons)






# TESLA cavity Z110: #8 cell equator

#8 equator,  $t=288 \sim 299$  deg



T-map data in test 2, 14.2 MV/m



group of beads(?) with 10mm wide were observed.

Similar beads group were also observed in several places. see following slides.

Z110

summary

08/05/12

cell equator

Group of spot

Scratch

Iris

equator

T-map  
Heat spot

081209

#9

#8

#7

#6

#5

#4

#3

#2

#1

Iris

#8-#9i

#7-#8i

#6-#7i

#5-#6i

#4-#5i

#3-#4i

#2-#3i

#1-#2i

LC Global Design Effort

0

90

180

270

360 deg








# Efforts at JLab and LANL

- Jlab
  - Thermometry and tele-scope

- LANL
  - Thermometry and videoscope





Scale seen by the  
videoscope



# Guideline: Standard Procedure and Feedback Loop

	Standard Fabrication/Process	(Optional action)	Acceptance Test/Inspection
Fabrication	Nb-sheet purchasing		Chemical component analysis
	Component (Shape) Fabrication		Optical inspect., Eddy current
	Cavity assembly with EBW (tumbling)		Optical inspection
Process	EP-1 (Bulk: ~150um)		
	Ultrasonic degreasing (detergent) or ethanol rinse		
	High-pressure pure-water rinsing		Optical inspection
	Hydrogen degassing at 600 C (?)	750 C	
	Field flatness tuning		
	EP-2 (~20um)		
	Ultrasonic degreasing or ethanol	(Flash/Fresh EP) (~5um))	
	High-pressure pure-water rinsing		
	General assembly		
	Baking at 120 C		
Cold Test (vertical test)	Performance Test with temperature and mode measurement	Temp. mapping	If cavity not meet specification Optical inspection

# Comparison with each treatment







# Cavity Integration and Tests

- **Europe (EU)**
  - Cryomodule assembly plan for XFEL (DESY/INFN/CEA-Saclay) □ □ □
  - Input-coupler industrial assessment for XFEL (LAL-Orsay)
  - Cryomodule design for S1-global (INFN/KEK)
  - TTF- 9 mA Test
- **America(s) (AMs)**
  - Cryomodule design
  - Cryogenic engineering (FNAL in cooperation with CERN)
  - SCRF Test Facility (FNAL)
- **Asia (AS)**
  - Cryomodule engineering design (KEK/INFN, KEK/IHEP)
  - Superconducting test facility (KEK)
- **Global effort for Cavity/Cryomodule Assembly**
  - Plug-compatible integration and test :





# Plug-compatible Conditions




Item	Can be flexible	Plug-comp.
Cavity shape	TeSLA/LL/RE	
Length		Fixed
Beam pipe flange		Fixed
Suspension pitch		Fixed
Tuner	Blade/Jack	
Coupler flange (warm end)		Fixed
Coupler pitch		fixed
He –in-line joint		TBD

Plug-compatible interface nearly established



# Study of the “plug-compatible” cryomodule cross-section



**Two shields model based on  
TTF-III**

**One shield model to  
save fabrication cost<sup>46</sup>**





# Why and How Plug-compatibility ?

- **Cavity**


- Necessary “extended research” to improve field gradient,
- Keep “room” to improve field gradient,
- Establish common interface conditions,

- **Cryomodule**

- Nearly ready for “system engineering”
- Establish unified interface conditions,
- Intend nearly unified engineering design
- Need to adapt to each regional feature and industrial constraint



# Global Cooperation with Plug-compatible Design and R&Ds





# Plug-compatibility in R&D and Construction Phases

- **R&D Phase**

- Creative work for further improvement with keeping replaceable condition,
- Global cooperation and share for intellectual engagement


- **Construction Phase**

- Keep competition with free market/multiple-suppliers, and effort for const-reduction, (with insurance)
- Maintain “intellectual” regional expertise base
- Encourage regional centers for fabrication/test facilities with accepting regional features/constraints



# Cavity and Cryomodule Test with Plug Compatibility

- Cavity integration and the String Test to be organized with:
  - 2 cavities from EU (DESY) and AMs (Fermilab)
  - 4 cavities from AS (KEK (and IHEP))
  - Each half-cryomodule from INFN and KEK





# Major Fabrication\*/Test Facilities


Regional central facilities to be very important and encouraged:

Facilities	Host Lab	Operation start
<b>TTF/FLASH</b>	<b>DESY</b>	<b>1997~, (9mA, 2008~)</b>
<b>Cryom. Ass.*</b>	<b>CEA/Saclay</b>	<b>2010~</b>
<b>STF</b>	<b>KEK</b>	<b>2007~2008</b>
<b>ILCTA-ML</b>	<b>FNAL</b>	<b>2008~2009</b>



# TESLA/FLASH at DESY

Experiences  
being  
gained from  
TESLA/FLASH  
are critical



081209


ILC Global Design Effort

52





# 9mA Experiments in TTF/FLASH




		XFEL X-Ray Free-Electron Laser	ILC	FLASH design	FLASH experiment
Bunch charge	nC	1	3.2	1	3
# bunches		3250*	2625	7200*	2400
Pulse length	$\mu$ s	650	970	800	800
Current	mA	5	9	9	9




# Preliminary Results (2008)

All RF stations with 800us flat top



550 bunches at 1MHz, 3nC/bunch, 890MeV



## FLASH operations records

- Long bunch trains with 3nC per bunch:
  - **550 bunches at 1MHz**
  - **300 bunches at 500KHz**
  - **890MeV linac energy**
- All modules running with 800us flat-top and 1GeV total gradient
- Limited to 1MHz (3mA) during first (preparatory) experiments
- 6 kW achieved
- 2009 goal: 36 kW (9mA)



# First nine-cell electro-polishing performed at ANL, May, 2008

## Fermilab/ANL Collaboration

- ACCEL cavity A7 electro-polished at ANL, and
- Further process and tested at Jlab.



Photos courtesy of Mike Kelly








# New Vertical Test @ FNAL

- Recently commissioned (IB1)
  - Existing 125W@ 1.8 K Cryogenic plant
  - RF system in collaboration with JLab
  - Evolutionary upgrades:
    - Thermometry for 9-cells
    - Plan for two additional VTS cryostat

VTS Cryostat:IB1




081209




New RF &  
Control Room

Nine-cell Tesla-style cavity



Plan for 2 more  
VTS pits





# Assembly Facility at FNAL



**ICB clean: Final  
Assembly fixtures installed**



**MP9 Clean Room**



**String Assembly**




**Cavity string for 1<sup>st</sup> CM**





# SC Test Facility (STF) at KEK





Cryogenic System (from AR-East)



Cryogenic Compressor (from AR-East)

## New STF Facilities

STF棟 (旧陽子リニアック棟) 平面図



V7.2 H. Hayano, 7/10/2006



# Process at STF



Flange-CP



EP

$H_2O_2$   
Hot bath  
(Alcohol)  
(Degreasing)

Rinsing



HPR



Assembly  
(Class 10)

Infrastructure in STF Hall

System check with AES cavity, now.



Pre-tuning  
fo adjustment



Inspection of  
Inner Surface



Vertical Test



Hanging  
Stand



Baking  
(Class 1000)



# Cavity Sting Assembly with Cryomodule at KEK/STF



String assembly of four cavities and cryomodule assembly were carried out in January ~ March, 2008.





# General Plan for SCRF at KEK

## STF1

**May-Dec. 2008** Cryomodule-A with for 4 base-line cavities: 2K cold test is now continuing.



**Jan-Dec. 2009** Cryomodule-B without cavities: Thermal measurement at 2K



## S1-Global

**May 2008 – Dec.2010** Cryomodule with 8 cavities (FNAL, DESY and KEK cavities, INFN cryostat and STF cryostat)

## STF-Module A + Module-C



**Operation: June-Dec. 2010**  
**Target: 31.5MV/m**

## STF2 (ILC 1 RF unit + 1 capture module)

**2009-2010** Design work (SC cavity, Cryomodule, Cryogenic system, RF system, etc)

**2010-** Construction of the components and infrastructure




Quadrupole





# Beam Acceleration Test Plan with RF unit at KEK






# Superconducting Magnets for Beam Focusing and Transport

- **Components in Cryomodule**
  - **G-integral : 36 T**  
**Aperture: 78 mm**
  - **Alignment: < 100 nm**

TABLE IV QUADRUPOLE SPECIFICATION.



Parameter	Value
Integrated peak gradient	36 T
Aperture	78 mm
Effective length	660 mm
Peak gradient	54 T/m
Field non-linearity at 5 mm radius	0.05 %
Dipole trim coils integrated strength	0.075 T-m
Magnetic center stability	5 $\mu$ m
Vertical/azimuthal offset in cryomodule	0.3 mm/0.3 mrad
Quantity required	560







# Quadrupole R&D Work at Fermilab and SLAC/CIEMAT




- Fermilab: V. Kashikhin et al.,
  - Test results of superconducting quadrupole model for linear colliders
  - This conference, 4LPA01,
- SLAC/CIEMAT: C. Adolphsen et al



# 2K Cryogenics Engineering

Scale is equivalent to the LHC cryogenics!!




Volumes	Numbers	Liq. He (liter) equivalent	Tevatron eq.	LHC Eq.
One module		346.1		
String	12 modules	4,153	0.1	
Cryo. unit	14-16 strings	62,992	1.0	0.1
ILC ML	2 x 5 cryo. units	630,261	10.5	0.8



# Klystron Cluster RF Distribution Scheme

Chris Adolphsen  
Chris Nantista



## Summary

Surface klystron clusters can save ~ 300 M\$ (~ 200 M\$ from eliminating service tunnel and ~100 M\$ from simpler power and cooling systems).

The GDE Executive Committee encourages R&D to pursue this idea.

The proposed CATO tap in/off design is likely to be robust breakdown-wise. Have a plan to demonstrate its performance, although with only 1/5 of the worst case ILC stored energy after shutoff.

### Need to better study:


Waveguide fabrication and tolerances – too large to be drawn, but don't want seams (KEK working with industry on this).

Bend design – mode preserving; low-loss; support 350 MW, 1.6 ms; compact enough for tunnel


Impact on LLRF control, energy spread minimization, & efficiency.

Modifications to accelerator tunnel to accommodate waveguide plus other systems from tunnel systems.

- RF power “piped” into accelerator tunnel every 2.5 km
- Service tunnel eliminated
- Electrical and cooling systems simplified
- Concerns: power handling, LLRF control coarseness





## Concept Development Steps







# Proposal of Distributed RF-source Scheme (DRFS)

One Klystron feeds power to



Total amount  
X 26 X 650  
=16900

BCD	DESY	Shallow Tunnel	RF Cluster	DRFS



## Likely Plan


There are several merits in DRFS.

- Complete single tunnel scheme and simple configuration. (Cost benefit is expected)
- Klystron failure doesn't give a serious effect to beam operation since failures are scattered. (cf. BCD, RF Cluster)
- Adoption of MAK leads to the cheap LLRF system and introduction of power handling is possible for klystron.
- Direct connecting of about 60kV to klystron eliminates pulse transformer and use of huge insulation oil.
- LLRF control is easy and vector sum of 2 cavities are better than BCD plan.
- By coupling two cavities with same performance, circulators are possibly eliminated.
- There are lots of advantages for the operation and control.


- Circulator elimination by power feeding to 2 cavities from one klystron. Output power is 732kW.
- Modulated Anode Klystron (MAK) is adopted.
- Anode modulation pulser does not need the high power and cost efficient pulser is manufactured.
- DC Power Supply is common for 26 cavities and voltage drop during the pulse is compensated with appropriate circuits at the level that LLRF can feed back.

Cost estimates Under going





# Distributed RF Source Concept (Fukuda, KEK)


$$X \ 26 \ X \ 650$$
$$=16900$$






# Outline

---

- Introduction
- R&D Status
- Plan for Technical Design Phase
- Global Plan and Project Management
- Summary



# ILC-GDE Organization Chart






# SCRF Area Organization in TDP

as of Sept., 2008

Regional Effort: Harrison, Foster, Yokoya			SCRF Technical Effort: Yamamoto, Shidara, and Kerby					
	Institute	Institute Leaders	Cavity: Process Lilje	Cavity: Integ. Hayano	Cryomod ule Ohuchii/C arter	Cryogenics Peterson	HLLRF (LLRF) Fukuda	M LI Adolphsen
<b>A M S</b>	Cornell Fermilab SLAC ANL J-lab	Padamsee Kephart Raubenheimer Gerig Rimmer	Padamsee Champion  Kelly Reece/	Champion Adolphsen	Champion n	Peterson	Adolphsen	Adolphsen
<b>E U</b>	DESY CERN Saclay Olsay INFN CIEMAT	Brinkmann Delahaye Dael Wormser Pagani	Lilje	L. Lilje  Prat Pagani	Parma  Pierini	Tavian		
<b>A S</b>	KEK Korea IHEP RRCAT/BAR C IUAC VECC	Yokoya  Gao Sahni (Sahni) Roy Bhandari	Hayano  Gao	Hayano	Tsuchiya/O huchi	Hosoyama / Nakai	Fukuda	Hayano

ILC Global Design Effort





# How Cooperate/Work Together?

- **Project Managers are responsible for:**
  - Coordinate/lead the world-wide technical development effort,
  - Setting technical direction and executing the project,
  - Day-by-day technical coordination/execution,
- **Regional Directors and Institutional Leaders are responsible for:**
  - Promoting, funding and authorizing the cooperation program.
  - Periodical reviewing of progress,





# Project Management in 2007-2008

- Technical Coordination and Leadship (by PMs)
  - Encourage “**extended R&D** for cavity gradient (S0)” and integration with establishing “**Plug-compatibility**”
  - Propose “**Cavity-string test with global effort (S1-Global)**”
  - We are developing practical plan for cryomodule string test with accelerator beam (S2)
  
- Start to prepare for AAP review in spring, 2009,
- We are establishing good communication by visiting world-wide SCRF/RF laboratories
  - DESY, CEA/Saclay, LAL/Orsay, CERN, (INFN, CIEMAT)
  - Fermilab, SLAC, Jlab, Cornell, LANL (TRIUMF)
  - KEK, **IHEP**, **Beijing U.**, **Tsinghua U.**, IUAC, RRCAT, TIFR, VECC  
**BARC**, KNU, PAL,



# Project Management Plan in 2008-2010

## Actions Required:

- Field gradient (S0)
  - To be re-optimized, based on the R&D progress (2010),
- Plug-compatibility
  - Common interface conditions to be agreed in LCWS-08 (2008) ,
  - Overview document in preparation
- System engineering/test plan, (S1, S2)
  - Work sharing in cavity string in global effort (S1-Global)
  - Accelerator system test with beam
    - Necessary detailed study and re-coordination under limited resources, including schedule
- Effort for “minimum machine” in view of SCRF (by N. Walker),
  - RF power sources and distribution,
- Prepare for AAP Review in April, 2009
- Global Communication and cooperation with Laboratories & Industries

# ilc

## TD Phase 1 Schedule

Published in:  
*ILC Research and  
Development Plan  
for the Technical Design  
Phase*

Release 2, June 2008  
(next release 6 months)

Near term effort on  
these activities →

Value  
engineering

Value  
engineering

Global  
Project Plan


High  
Gradient

Cryomodule  
test

Systems  
Test

Electron  
Cloud

Precision  
beam control





# Plug-Compatibility Document

Draft: Sept. 4, 2008

revision: October 12, 2008

updated by AY, Oct. 13, 2008

## **Plug-compatibility in the ILC Technical Design Phase (SCRF)**

ILC-GDE Project Managers

Marc Ross, Nicholas Walker, and Akira Yamamoto

### **Purpose of this document**

This document is an attempt (draft) to describe how we would 'more explicitly' define plug-compatibility for the R & D Phase. We are planning to include it in the next release of the R & D Plan. Advice and comments are appreciated.

The document has the following sections:

1. Introduction
2. Goals and Guidelines for Plug-compatibility in the Technical Design Phase (TDP)
3. Scenarios outlining the impact Plug-compatibility has on project phases following the TDP
4. SRF Technical Group example – the ILC cryomodule



# SCRF Major Goals

<b>High-gradient</b> cavity performance at 35 MV/m according to the specified chemical process with a yield of 50% in TDP1, and with a production yield of 90% in TDP2	<b>2010 2012</b>
<b>Nominal Cryomodule design</b> to be optimized: <ul style="list-style-type: none"><li>- plug-compatible design including tune-ability and maintainability</li><li>- thermal balance and cryogenics operation</li><li>- beam dynamics (addressing issues such as orientation and alignment)</li></ul>	<b>2009</b>
<b>Cavity-string</b> performance in one cryomodule with the average gradient 31.5 MV based on a global effort (S1 and S1-global)	<b>2010</b>
<b>An ILC accelerator unit</b> , consisting of three cryomodules powered by one RF unit, with achieving the average gradient 31.5 MV/m (S2)	<b>2012</b>






# Global Plan for SCRF R&D

Calendar Year	2007	2008	2009	2010	2011	2012
Technical Design Phase	TDP-1			TDP-2		
Cavity Gradient R&D to reach 35 MV/m		Process Yield > 50%		Production Yield >90%		
Cavity-string test: with 1 cryomodule			Global collab. For <31.5 MV/m>			
System Test with beam 1 RF-unit (3-modulce)		FLASH (DESY)			STF2 (KEK) NML (FNAL)	



# TD Phase Priorities – A Summary





## TD Phase 1 Stated Priorities (R&D Plan)

### Risk Mitigating R&D

- SCRF Technology (e.g. gradient)
- Damping ring electron cloud
- ...

### Beam Test Facilities


- ATF / ATF 2 (KEK)
- CsrTA (Cornell)
- TTF/FLASH (DESY)

### Machine Design / Cost

- CFS / Value Engineering
- “Minimum Machine” concept

# SRF Test Facilities

FNAL



NML facility  
Under construction  
first beam 2010  
ILC RF unit test


DESY



TTF/FLASH  
~1 GeV  
ILC-like beam  
ILC RF unit  
(\* lower gradient)



KEK, Japan



STF (phase I & II)  
Under construction  
first beam 2011  
ILC RF unit test



# Cooperation with EuroXFEL and Other Projects

## European X-ray Free Electron Laser Facility

- EuroXFEL SRF design gradient : 23.6 MV/m
- Machine designed: 28 MV/m
- ~ 100 SCRF cryomodule, based on the experience at TTF, DESY,
- Leading SCRF industrialization (scale: **1/20** of ILC, in coming 5 years)
- Keep close cooperation with XFEL, on-going project.




## Further SCRF Accelerator Project Plans investigated:

- Project X at Fermilab, SC Proton Linac at CERN, and ERL at KEK
- Best effort for common design and cost-effective design








# TTF/FLASH at DESY




TTF/FLASH: currently a unique facility world-wide

				FLASH design	FLASH 9mA experiment
Bunch charge	nC	1	3.2	1	3
# bunches		3250*	2625	7200*	2400
Pulse length	$\mu$ s	650	970	800	800
Current	mA	5	9	9	9

# European XFEL




- 101 Cryomodules
- 808 cavities
  - plus auxiliaries
- Gradient:
  - 23.5 MV/m
  - (28 MV/m)
- Industrialisation & mass production
  - 1 CM / week
- “In-kind” international model
- Major Chinese contribution





# GDE & XFEL Timelines





# 2009 – 2010

Proposed meetings and reviews:

- TDP1 Interim Review, Tsukuba – April 17-21, 2009 (Accelerator Advisory Panel, AAP)
- ALCPG Autumn 2009
- ILC Baseline update – January 2010
- TDP1 Final Review, April 2010 (AAP)
- ECFA Workshop, CERN – April 2010 (TBC)
- TDP1 presentation, ICHEP Paris - July 2010



# Summary

## ■ Technical Design Phase in progress:

### ■ Phase-1: Technical reality to be examined,

- 35 MV/m with yield 50 % in surface process and

- $< 31.5 \text{ MV/m} >$  with the cavity-string in a cryomodule

- Plug-compatible cryomodule to be examined with global effort.

### ■ Phase-2: Technical credibility to be verified

- 35 MV/m with the yield 90 % for 9-cell including fabrication

- System engineering and beam acceleration with the field gradient  $< 31.5 > \text{ MV/m}$ .

## ■ We aim for

- Global cooperation with having plug-compatibility, and with a smooth transition to the construction/production phase.

- Cooperation with world-wide Institutions critically important






# Backup



# Cavity Shape Design Investigated

TABLE II. CAVITY SHAPES STUDIED FOR THE ILC.

Parameter	TESLA	LL/IS	RE
Iris aperture (mm)	70	60/61	66
$E_{\text{peak}}/E_{\text{acc}}$	1.98	2.36/2.02	2.21
$B_{\text{peak}}/E_{\text{acc}}$ (mT/(MV/m))	4.15	3.61/3.56	3.76
Char. shunt impedance: $R/Q$ ( $\Omega$ )	114	134/138	127
Geometric factor: $G$ ( $\Omega$ )	271	284/285	277
$G \times R/Q$ ( $\Omega \times \Omega \times 10^5$ )	3.08	3.80/3.93	3.51





- TESLA
  - Lower E-peak
  - Lower risk of field emission
- LL/IS, RE
  - Lower B-peak
  - Potential to reach higher gradient

LL: low-loss, IS: Ichiro-shape, RE: re-entrant



# S1-Global: Cryomodule Assembly



Cryogenic system

Module C



Module A

**Plug-compatibility to be examined**



# Vertical Test Commissioning at KEK

- cool-down test of cryostat was done July 3 – 5, using AES01 cavity.
- EP at STF-EP facility, vertical test again in September.






AES01 cavity with T-map



Installation into vertical cryostat



# Plug-compatible Development




Plug-compatible interface to be established





# Plug compatible conditions at Cavity package (in progress)




Item	Can be flexible	Plug-compatible
Cavity shape	TeSLA/L/RE	
Length		Required
Beam pipe dia		Required
Flange		Required
Tuner	0	
Coupler flange		Required
He -in-line joint		Required
Input coupler	TBD	TBD



# Eacc,max, and average, in Cryomodule

KEK, Nov., 2008



RF FB / ON

Eacc,max  
(Cryo.)  
= 32 MV/m  
(max)  
> 23 MV/m  
(average)




# What's in a Name?

- “Minimum” a bad choice of word!
  - historical – now part of the language!
  - does not convey what we are attempting to achieve
- Need a better word!
  - we are really discussing conceptual studies for specific alternative designs
- Will change it soon – but for now...
  - 110 hits on Google!!
- **最も効果的な加速器**

# “??????? Machine” Philosophy

- *Direct performance*
  - considered a ‘physics figure of merit’
    - centre of mass energy
    - luminosity
  - physics of the

**Global Value Engineering**



- *Indirect performance*
  - into which we place margin, redundancy, etc.
  - tend to impact operation
  - performance risk
    - potentially affecting integration within a given time frame


“Minimum Machine” refers to a set of identified options (elements) which may simplify the design and be cost-effective

- Concentrate on Indirect
  - **Do not change basic physics parameters**

Margin, risk reduction, redundancy, ...  
(*indirect performance*)



# Identified Design Study Elements



Additional Elements  
being considered  
(resource  
limitations!)





# Minimum Machine Document in Preparation



## *The ILC Minimum Machine Definition*

Release 1

November 2008


Prepared by the Technical Design Phase Project  
Management

To communicate our ideas to the  
broader community and form a  
blue-print for studies in 09

- Draft document is preparation
- (One) Focus of ILC08 workshop
  - **Study planning**
  - **Resources**
- Final publication end of year



# Project Implementation Plan





Preparing for a rapid transition to a construction project

Critical to engage **FALC** in this process




# Transition to Construction Project





## Global Cooperation: Plug-compatible Design and R&D




- Cost driven R & D process
- Technology transfer to Industry
- Innovation
- Intellectual engagement
- Expert base



## Global Production: Plug-Compatible Production



- Testing (QA/QC)
- Free 'global' market competition (lowest cost)
- Maintain intellectual regional expertise base







# Plug-compatible Conditions



Item	Can be flexible	Plug-comp.
Cavity shape	TeSLA/LL/RE	
Length		Fixed
Beam pipe flange		Fixed
Suspension pitch		Fixed
Tuner	Blade/Jack	
Coupler flange (warm end)		Fixed
Coupler pitch		fixed
He –in-line joint		TBD

Plug-compatible interface nearly established