Parallel session summary ML/SCRF

L. Lilje, H. Hayano, N. Ohuchi, S. Fukuda, C. Adolphsen (with help of Chris Nantista)

Overview S0 Session


- Vendor qualification using temperature mapping and highresolution optical inspection
 - Example on optical inspection from Asia
 - Example of single cells in new preparation facility from the US
- Very good series with good results on initial test
 - At II ab
- Sample tests of rinsing methods
 - Choices of either ethanol or ultrasonic degrease are validated
- Industrialization in Europe for XFEL
 - Preparation for call for tender
 - Streamlining procedures
 - Improving quality control
 - International process:
 - CEA, INFN, DESY
 - ILC participation via M. Champion and H. Hayano

MHI-05 2nd V.T.: #5 cell equator, 29.2MV/m @ 7/9

superconducting rf test facility =



Heating area #5 cell equator : 120° ~ 180° : Sensor 120° ⊿T=1 K, 150° ⊿T=10 K, 180° ⊿T=5 K




эн

10


EP single cell cavity performance

FNAL, ANL



	ВСР	EP	Ethanol	Eacc [MV/m]	Notes
NR-1	150	93		26.5	Oxidation by acid residual
TE1AES004	107	65		39.2	Equator large pit present
TE1AES005	104	100	Yes	36.3	Oxidation by HPR water
TE1ACC002		112	Yes on second	37.1	
TE1ACC001		99		41.3	FE appeared after 120°C baking
TE1ACC003		119		42.1	Pit present
TE1ACC004					


One vendor cavity in past 6 months EP processed and RF tested at JLab



T. Saeki

KEK

Rinse Effect to Remove Sulfur precipitation/contamination





Evolution of defects: through full preparation

Systematic inspection process

Equator #7 at 44 deg.



Before treatment


After 108 μm main EP


Pits at weld interface removed by main EP

S. Aderhold **DESY**


Cavity integration Session

- KEK-STF cryomodule tests, etc
 - 4 cavities module test (STF1.0), with one cavity of 32MV/m operation.
 - magnetic shield evaluation
 - TTF-V coupler test
- Slide-Jack tuner: Lorentz detuning meas. and compensation
 - LD meas. by pulse-cut method,
 - optimization of LD compensation at 31MV/m
 - response meas. in room temp.
- Blade tuner : qualification tests
 - LD compensation, mechanical backlash, piezo response are qualified.
 - fabrication for FNAL-CM2, S1G, ILC-Higrade
- Plug-compatibility
 - boundary of input coupler





Input coupler boundary



Cryomodule parallel session(April 20 9:00-12:30)

- Main target (Construction of S1-G cryomodules)
 - Discussion of S1-G cryomodule (Module-C) after DESIGN WORK
 - Confirmation of the general schedule of S1-G cryomodule
 - FNAL cavities will be supplied with being jacketed and helium supply pipe after vertical tests in the end of this fall.
 - The installation of cryomodules into the STF tunnel is scheduled at the end of May, and the cold test will start at June 2009.
 - Starting to make the list of the Module-C components and the responsible institute.
 - Strategy to understand the thermal performance of S1-G cryomodules and to define the heat load of ILC cryomodule by the cold test.
 - Analysis of thermal characteristics of S1-G cryomodules by INFN.
 - Measurements of heat loads and thermal behaviors of the modules
 - » Defining the number of thermal sensors and locations, WPMs and the other sensors.
 - Preparation of assembly of FNAL/DESY cavities and KEK cavities.
 - Comparing the assembly procedures in the clean room, and alignment tools.

Cryomodule Design Optimization

Plug-compatible and Cost reduction

Thermal design (based on TTF-type III)

- Thermal performance of the components
 - Thermal intercepts
 - RF cables
 - Input couplers (Tesla type, KEK type)
 - Quadrupole package and BPM
- Evaluation of heat loads at 31.5 MV/m
- Temperature profile in the module
 - Module design with or without 5K shield
 - Cooling scheme in the cryomodule

Mechanical design

- Assembly process and tooling
- · Alignment method

2009/4/17-20 TILC09 at Tsukuba

Tests and measurements


Cold test of cryomodule with or without 5K shield at KEK-STF

CM1 at FNAL-NML S1-Global at KEK-STF

Dynamic heat load measurements at FLASH

Design of ILC proto-type
Type IV or V at FNAL
STF2 module at KEK


Longitudinal behavior




Thermal analysis of S1-G cryomodule (Module-C) by the INFN group.

Assembly study for FNAL/DESY/KEK cavities

KEK alignment tools of cavities



FNAL alignment tools of cavities



Rotational Alignment fixture

X-Y Alignment fixture

HLRF Session


- New phase shifter design, hybrid design
 - SLAC design.
 - KEK design.
- circulator elimination test
 - successful operation by vector sum control, need to study hybrid isolation.
- cavity grouping by gradient for fixed coupling coupler
 - proper grouping leads no tunable coupler.
- Klystron cluster concept
 - new design of coaxial tap off.
 - cost analysis
 - LLRF comments
- Distributed RF concept
 - cost study of 1 klystron for 2 cavities is on a way.
- Single tunnel study of these concept at KEK
 - DRFS likely in Asia site.

Phase Shifter for New phase-shifter Remote Controllable and Variable Hybrid VTO Alternate **Christopher Nantista** SLAC S.Kazakov moving inner waveguide pressurized Variable H-hybrid 1040mm outer box magic-T's Working zone 2" travel Conclusion springy New tape of all metal phase shifter was designed, built and tested. Phase shift range - 130°, air breakdown limit ~ 5.5 MW finger stock ф Phase shifter was tested till 2.9 MW without breakdowns. New design of more powerful phase shifter is made. Air breakdown limit ~ 12MW · takes advantage of required U-bends; Design of full range variable H-hybrid is made. · match ideally unaffected by position; Air breakdown limit ~ 12MW - makes maximal use of commercially available parts and is remote-controllable.

Elimination of circulators at STF-1

Shin Michizono (KEK)


- System configuration at STF-1
- LLRF stabilities without circulators
- Forward and reflection rf fields
- Low power measurements
- Comparison between low-power and high-power




(0			mm, 10 mm, 0 m	m)	(-5 mm, 10 mm, 0 mm)	
		low-level	w/circulators	w/o cir.#1	low-level	w/o cir.#1
Port 1	S11	-44	-45	-29	- <u>2</u> 2	-20
Port 1-2	S21	-29	-43	-30	-27	-26
Port 1-3	S31	-34	-42	-31	-34	-31
Port 1-4	S41	-35	-49	-34	-33	-34
Port 1-5	S51	-6			-6	

- When the isolation is worse, high-power and low-power results agree well
- Stabilities of the Acc fields are almost same. Vector sum amplitude: 0.038-0.037%rms. Vector sum phase: 0.02-0.018 deg.rms
- Due to reflection wave, Detune and Q_L can not be determined accurately.
- High power and low power results agree well in case of poor isolation. High power effects (temperature, high-rf fields) induce the difference in isolatiion(?)

Coupler Tune-ability **Power Distribution System**





	Optimum Coupling	ML costs 4000 MILC, Assembly & Tuning Cost are not evaluate				valuated.
 Limit		Tuning	Energy	Extra	Devise	Total
			Reduction	Cost	Cost	Cost-Up
_	Matched Condition	No Tuning	> 10 %	> 400	0	> 400
		Full Tuning	0	0	60 + 60	120
_	Over Couple 1.3	Coupling	1.8 %	72	60	132
1	Over Couple 1.5	$2.5 - 6.7 \times 10^{6}$				
_	Pg = 350 kW	Power	1.5 %	60	60	120
	Power Limit	227 - 347 kW	1.6 % (5mA)			

Summary

- Cavity Grouping Scheme is Proposed. Power Effective, Small Tuning Range & Less DLD Effect.
- If we use this scheme, and assume the following number, the coupling tune-ability may be not cost effective.

Coupling Error: 15 % RMS

Vc (MV)

Gradient Distribution: 1.5MV RMS

Input Coupler must have a capacity of 400 kW.

Precise Evaluation of cost performance is necessary. TILC2009, Tsukuba, Aprile 20, 2009

Klystron Cluster Concept Distributed RF-source Scheme for ILC High-Power (DRFS) RF Power Distribution First Design Christopher Nantista Shigeki Fukuda (KEK) Chris Adolphsen 2x35 klystrons housed in SLAC surface building. **Dummy Load Directional Coupler** 350MW feeds via 0.5m Magic Tee diameter circular waveguide Phase Adjustment Frequency Output Power RF pulse width MA Klystron (dB) Beam pulse width Average RF power Peak beam voltage Peak beam current Beam Perveance Gun Perveance DC Gun Voltage(A-B) Tetrode MA-type Electromagnetic Focusing ■ 5 MW Water cooling Total length step taper Weight MA Klystron PDS P_c/(P_t+P_c) Cryomodule flange Cross Section Surface klystron clusters can save ~300 M\$ (~200 M\$ from eliminating service tunnel and ~100 M\$ from simpler power and cooling systems). The proposed CTO tap in/off design is likely to be robust breakdown-wise. Have a plan to demonstrate its performance, although with only 1/5 of the MA Modulator

DC PS with Droop Compensa **Design Parameters** 1300MHz 750kW 1.565ms 1.7ms 6kW 62kV 1.36mP(@62kV) 1.735mP (@Ea-k=53kV) >64kV 1.1m 70kg Control Rack Gamma ray Coil P/S & Heater P/S Shield Tunnel worst case ILC stored energy after shutoff. DC P/S RF Amplifier etc


M. Anode Modulator

X 13

Americas KlyCluster Cost Analysis Overview

(Vic Kuchler for) Tom Lackowski

Four shafts added for RF Waveguides.



Area of Refuge

Functional Requirements used in the RDR have been maintained.

Life Safety further study.

Changes in the costs are a reflection of the KLY Cluster scheme only; potential savings from other value engineering ideas have not be incorporated.

 corresponds to -4.9% savings wrt ILC RDR est

GDE ACCELERATOR ADVISORY PANEL REVIEW

CONVENTIONAL FACILITIES AND SITING GROUP

Single-tunnel scheme studies at KEK (RF Cluster and Distributed RF System)

Contents of this talk

- Two kinds of single-tunnel schemes applicable for the Asian sample site (deep tunnel).
- Pros and cons of these schemes from CFS point of view.
- Understanding of degree of cost impacts for the single tunnel scheme.

X 1 (single)

X10

X6

~ half

X10

X6

Plans of further studies.

Impacts on Main Linac civil engineering

φ4.5m, 22.3 km

X2 (double)

X6 /m X01.5m X-1.270m 1

X6

Access shaft/tunnel

Shaft-base caver

Surface building

เรเ	ISNI	Enomoto	


RDR			(D) Access Turnel (Named less than 10%)				
	Elevation		Overburden	Elevation	Drop from	Length from	
Point ID	(A) Surface	(B) Beam Tunnel	above Beam Tunnel = (A)-(B)	(C) Entrance	Entrance to Beam Tunnel = (C)-(B)	Entrance to Beam Tunnel	
7	400	80	320	204	124	1,540	
5	368	80	288	226	146	1,608	
3	488	80	408	238	158	1,706	
2	180	80	100	156	76	1,198	
4	164	80	84	117	37	652	
6	178	80	98	165	85	934	
100000000000000000000000000000000000000		2.00					

Summary of this talk


- As a study of minimum machine, two kinds of single-tunnel schemes was investigated in order to apply them for the Asian sample site (deep tunnel).
- Though both of two are considered to be applicable, from a civil-engineering point of view, "Distributed RF Scheme" seems more suitable for the Asian site.
- Further studies should cover overall CF designs such as cooling and safety issues.

LLRF Comments on the RF cluster and Distributed RF schemes

Shin Michizono (KEK)



	Baseline	Single tunnel	Klystron cluster	Distributed rf
No. of tunnels	2	1	1	1
LLRF unit	Service tunnel	Beam tunnel	Beam tunnel	Beam tunnel
Cavity/ rf unit	26	26	780	2
No. of vector sum	26	26	780	2
QI and power distribution control	Necessary	Necessary	Difficult	No need
No. of lirf cable /rf	~80	~80	~80*30 or fast optical cables	6
Loop delay	~1 us	~1 us	~10 us	~0.3 us



Disadvantage: each two-units should be operated at same power

	Klystron cluster	DRFS
FB performance	Not good	Better
QI and power distribution control	Difficult	No need
Each cavity field flatness	Worse	Best or better
Exception handling	Quite complicated	Easy
LLRF cost	Similar to baseline	13% expensive than baseline