



ILD-Workshop 21 January 2009



Design Philosophy of the CMS Experiment


A. Hervé / ETHZ@CERN



CMS Experiment

Logistics not so different than ILD

CMS
A Compact Solenoidal Detector for LHC



Based on Large
SC Solenoid

6 m diameter

13 m long

Strong Field 4T

10'000-ton
Instrumented
Return Yoke

Total weight : 12,500t.
Overall diameter : 15.00m
Overall length : 21.60m
Magnetic field : 4 Tesla

CMS-PARA-001-11/07/97 JLB.PP



Guarantee Accessibility for Maintenance



- ***Sub-detectors must be maintainable, that is detector can be opened in a reasonable time to give access to every one of them, including access to the main flanges of Tracker, ECAL and HCAL.***
- ***This opening scenario must be possible without decabling or removing services of any sub-detector, to allow fast re-commissioning before closing again the detector.***
- ***The goal is to maximize useful maintenance time to get all sub-detectors operating at their optimum.***



Request Assembly and Test on Surface

- *As seen at LEP, installation work takes 50% more time in a deep underground area for questions of access, limited space, superposed work areas and related safety precautions*
- *CMS has from the start requested an assembly on the surface followed by transfer of FULLY COMMISSIONED large detector elements (up to 2000 tons) by heavy lifting means.*
- *It was also argued, and I think this has been demonstrated, that the length of the underground cavern would be insufficient to carry out such a construction work in a reasonable time.*
- *Another important argument was that all delicate or risky operations, coil test, HB insertion, EB insertion, Tracker insertion, closing of detector etc. can be carried at least once on the surface and corrections made before final operations underground.*



Start the Integration Project Early on

- **Select a good integration coordinator.**
- **Assemble an integration and design office.**
- **Generate and maintain a “central parameter drawing” defining absolute boxes for subdetectors separated by no-go zones.**
- **Each absolute box must contain the subdetector, its electronics, cables, cooling screens and pipes, deformations, and all associated tolerances.**
- **Select compatible CAD systems, and maintain a central “up-to-date 3D model”.**



Tackle Fire-Safety Early on



- *The inside of the cryostat is inaccessible, although it contains the heart of the experiment in terms of investment in time and cost. It must be protected against fire by maintaining an inert atmosphere (enriched in nitrogen) to quench any source of fire ignition*
- *Thus, inside cryostat, gas cooling can only be natural convection. Associated cold sources must be provided by stabilizing in temperature the Vacuum Tank itself or the HCAL absorber (for example) to prevent inner temperature drifting*
- *Liquid cooling is thus mandatory to extract main part of the heat as near as possible from where it is created*



Foresee Active Cooling from the Start

- **Active cooling of front-end electronics is a must especially in confined areas like Cryostat which is under nitrogen atmosphere for fire safety**
- **Temperature stabilization is needed as temperature dependence of sub-detectors is often neglected or known quite late, light detectors, RPCs,**
- **It is good practice that each sub-detector can be considered as an adiabatic, or isothermal enclosure wrt. its neighbors, that is each one is responsible for removing its own thermal flux**
- **Air (or gas) cooling is very inefficient, it can be used at best to remove residual heat, water is still the best**




ILD Workshop 21 January 2009



Some pictures of CMS construction
to draw attention
to some applicable points



Large elements must be able to moved Connected by large cable chains






Construction of yoke used precise Jig and Keys to minimize Tolerances and allow fast re-Assembly



Effort has been made not to align dead zones

Air pads






All Pieces have been carefully Surveyed




CMS ENDCAP PHOTOGRAMMETRY

YE-1 Oct 2001






Also during Blank assy at Manufacturers



Yoke Barrel YB0 - May 2000
Photogrammetric measurement at DWIE
E. Fühnerhalsauke / R. Goudard

In Germany



In Japan



Construction of Outer Cryostat imbedded in Central Wheel to transmit Load of HB to Ground




ILD-



Supporting the Inner Detectors from Cryostat



Inner vactank supports the 1000-tonne Hadronic Barrel and 200-ton Electromagnetic barrel on 2 rails imbedded in the shell



Penetration for current leads and pumping

There is another one for cryogenics vertical on opposite side of YB0

January 2006: End of the CMS Magnet Manufacturing




The two 500-ton HBs have been assembled on Surface directly at Beam Height





HB Insertion inside inner Cryostat on Surface




**Grease pads
to adjust
axes**

**Jacks to
adjust
rail plane**



HCAL Barrel inserted to load Cryostat



Precise survey to determine **shimming and corrections** to be applied for **final installation underground** and mitigate cryostat deformation




Installation of EB modules inside HB

Compatible with maintenance scenario




**Use of a rotator
to feed modules
at correct
angle**





Installation of two EB modules inside HB

For testing on the surface






The coil has been assembled with Vertical Axis



This allows a very precise coupling

But the 220-ton coil has to be inserted inside the Cryostat with horizontal axis!





Coil swiveling requests large tooling




**The 220 ton
cold mass
was rotated
in 15 min**

**The coil is
maneuvered
cantilevered
from one end**




Sept. 2005: ready to insert!




ILD-



Coil swiveling in Surface Hall August 05



Underground
hall Detector
fully open



Same scale!




This justifies the surface assembly



- These heavy construction activities cannot be done in a reasonable time, safely, in the underground hall.
- A much longer and wider underground hall, equipped with two 80-ton cranes, would be needed, and more time....




CMS Closed mid-July 2006 4T reached on 22 August 2006






A slice of all sub-detectors has been fully commissioned on surface using cosmics





All Elements are fully Commissioned
ready to be lowered (for example YE+1)




Z-stops resist the 10'000-ton
attraction magnetic force

Elements are fully
cabled to local racks.
All services, gas and
water cooling pipes
are there.

Subdetectors have
been commissioned.
Once below they can
be connected to the
umbilical cables going
to the counting rooms
through the cable
chains.



Elements are lowered fully ionned




Disk YE+1 arriving in underground hall

Disk YE+2 already in underground hall



Coil Recommissioned in Spring 08



20 kA Bus Bars

6000-liter
dewar

Currents Leads
and pumping


Coil



HB inside Cryostat




Perfect fit & alignment wrt. Beam axis!






EB module with insertion tooling






Installation of EB Completed





Installation (removal) of Tracker determines the maximum opening in “Garage position”





ILD Workshop 21 January 2009



Conclusions



Conclusions



- **CMS has been able to maintain the principles adopted in 1991/1992 without any compromising, and it has been fully “built as foreseen”.**
- **This first (imposed) shut-down shows that the general architecture will allow an efficient maintenance as all sub-detectors can be easily accessed during a shut-down.**
- **Several technical solutions adopted by CMS have shown their validity and I am convinced a large fraction of them may be directly adopted by ILD**




The plug has been tested using
a 2500 ton dead load





Construction of Main Plug on side of Shaft Apr. 04 Used as radiation protection and lifting platform




ILD-T

LHC Point 5 - SX5 Extension - Bouchon Complete - 20 April 2004 - CERN TS-CE


UX5 before receiving Elements

The cave below is used as dispatching center for cables




Design by CMS Integration group, April 2005.

Situation of cable chains before lowering Elements






How cable chains are connected to pre-cabled Elements




Opening the plug under the 2000-ton





28 Feb. 07-YB0 at the Beginning of Descent





500-t HB beginning the descent

