


# TESLA Design & Accelerator R&D Opportunities

H. Padamsee, Cornell University



TeV  
Energy  
Superconducting  
Linear  
Accelerator

500 GeV  
Needs 24 MV/m

800 GeV needs  
35 MV/m

# Sources

## INTERNATIONAL LINEAR COLLIDER TECHNICAL REVIEW COMMITTEE SECOND REPORT

2003

---

Chair  
Steering Committee


Gregory Loew  
Reinhard Brinkmann  
Kaoru Yokoya  
Tor Raubenheimer  
Gilbert Guignard



### TESLA

The Superconducting Electron-Positron Linear Collider with an Integrated X-Ray Laser Laboratory

### Technical Design Report



March  
2001

PROCEEDINGS OF


1990

# The First International TESLA Workshop

CORNELL



Held at Cornell University  
July 23-26, 1990



Tesla



# 50 Labs, 12 Countries



Barcelona  
Spain




Yerevan Physics Institute



IHEP, Beijing  
Tsinghua University



Institute of Physics,  
Helsinki



DSM/DAPNIA, Saclay  
IN2P3/IPN, Orsay  
IN2P3/LAL, Orsay



BESSY, Berlin  
DESY, Hamburg  
Frankfurt University  
FZ Karlsruhe  
GKSS Research Centre  
Hahn-Meitner-Institut  
Berlin



CCLRC, Daresbury &  
Rutherford Appleton



INFN, Frascati  
INFN, Legnaro  
INFN, Milano  
Univ. Roma II




Hamburg University  
Max Born Institute, Berlin  
Rostock University  
RWTH, Aachen  
TU, Berlin  
TU, Darmstadt  
TU, Dresden  
Wuppertal University



DMCS Technical  
University, Lodz  
Faculty of Physics  
Warsaw University  
High Pressure Research  
Center "UNIPRESS" PAS,  
Warsaw



BINP, Novosibirsk  
BINP, Protvino  
IHEP, Protvino  
INR, Troitsk  
JINR Dubna  
MEPhI, Moscow  
ITEP, Moscow



APS/Argonne, Chicago, IL  
Cornell University, Ithaca, NY  
Fermilab, Batavia, IL  
Thomas Jefferson National  
Laboratory, Newport News, VA  
UCLA Dep. of Physics, Los Angeles,  
LA



Inst. of Nuclear Physics,  
Cracow  
Inst. of Physics Polish  
Acad. of Science,  
Warsaw  
ISE Technical University,  
Warsaw  
Polish Atomic Energy  
Agency, Warsaw  
Soltan Inst. for Nuclear  
Studies, Otwock-Swierk  
Univ. of Mining &  
Metallurgy, Cracow




Paul Scherrer Institut,  
Villingen


# Linear collider luminosity parameters

$$L [10^{34} \text{ cm}^{-2} \text{ s}^{-1}] \approx 121 (N_g H_D) \frac{P_b [\text{MW}]}{E_b [\text{GeV}]} \frac{1}{s_y [\text{nm}]}$$

| Parameter   | SLC          | TESLA     |
|---|--------------|-----------|
| Beam energy [GeV]   | 46           | 250       |
| Beam power/beam [MW]  | 0.035        | 11.3      |
| Vertical rms beam size at IP [nm]                                       | 650          | 5         |
| Beamstrahlung photons/electron $N_g$                                    | 1.1          | 1.6       |
| Disruption enhancement $H_D$  | 2.1          | 2.1       |
| <b>Luminosity [<math>10^{33} \text{ cm}^{-2} \text{ s}^{-1}</math>]</b> | <b>0.003</b> | <b>34</b> |



One Major Challenge for Luminosity



2 $\sigma$  vertical beam size (TESLA)

NLC, JLC

10 nm

# The dominant challenge to reach the desired energy is the main linac technology

- RF power and accelerating structures
- Superconducting standing-wave cavities, operating at 1.3 GHz, developed by the TESLA collaboration



# TESLA acceleration system: principal features (500 GeV c.m.)

|   |                  |
|---|------------------|
| Feature                                     | TESLA<br>1.3 GHz |
| Structure length (cm)                       | 104              |
| (loaded) accelerating gradient [MV/m]       | 24 (35*)         |
| <b>Number of structures</b>                 | <b>20592</b>     |
| Two-Linac length [km]                       | 30               |
| <b>RF pulse length [<math>\mu</math>s]</b>  | <b>1370</b>      |
| Cycle rate [Hz]                             | 5                |
| RF power/structure [MW] - all for beam      | 0.25             |
| <b>Efficiency (Beam power/AC Power [%])</b> | <b>23.8</b>      |

## Main Reasons for SC

- 1 Fill slowly =>  
Big Reduction of Peak RF Power
- 2 High overall efficiency of  
AC power to beam power

\*Required for energy upgrade



# 3. Wakefields

Low Frequency, large apertures Affordable =>

Low Wake fields to disrupt beam




## Amplitude of wakefields

Choice of technology determines radius of structure iris a:


High frequency – small a

Low frequency – large a



**Stronger wakefields (beam induced electromagnetic fields) with smaller iris radius!**

*Beam is closer to metallic walls...*




# Key Challenges

- Operate 500 GeV at  $E_{acc} \sim 24$  MV/m
- 35 MV/m for upgrade, needed at first installation
- Extensive R&D at DESY, KEK, JLAB and Cornell over the past decade, in
  - cavity design (to reduce peak surface electric and magnetic fields),
  - Nb material quality,
  - cavity fabrication, cleaning and processing techniques


**=> Production of > 50 structures with gradients > 24 MV/m.**


- The latest development in cavity processing (electropolishing) has yielded two “fully-dressed” 9-cell cavities capable of 35 MV/m
- More 35 MV/m cavities need to be made, to demonstrate the reproducibility of the process, and tested for dark current.

# Zooming in on TESLA




# TESLA Tunnel






1700 Cryomodules



## *70 K ML Isolation (30 Layers)*



## *70 K Shield before Welding*







## *4 K Shield*



*Cavity String mounted on 300 mm He Gas Return Pipe*








# Preparation of TESLA Cavity String







# Cavities and Cavity Parts




# Preparation of TESLA Cavities

Furnace treatment



100 atm jet water rinsing



Chemical Treatment



Class 100 Dust Free Clean Room Assembly




# Cavity Vertical Test


- The naked cavity is immersed in a super-fluid He bath (2 K).
- RF test are performed in CW with a moderate power (< 300W)



# Steady Improvement in Cavity Gradients and Q's




# Steady Improvement in Cavity Gradients and Q's



average gradient at  $Q_0 > 3 \cdot 10^9 = 23.9$  MV/m


1997



24 MV/m


1999

Steady Improvement in  
Cavity Gradients and Q's




average gradient at  $Q_0 > 3 \cdot 10^9 = 23.9$  MV/m

1997



24 MV/m


1999




35 MV/m

2002

# Highest Gradient Performance




# In Cryomodules




Tuner



Higher Order Mode Couplers




He Vessel





Input Coupler

# Gradient of Accelerator Modules




# Module 5






# EP 9-cell Cavities - Cryomodule “Chechia”

- Cavity is fully assembled
- It includes all the ancillaries:
  - Power Coupler
  - Helium vessel
  - Tuner (...and piezo)
- RF Power is fed by a Klystron through the main coupler
- Pulsed RF operation using the same pulse shape foreseen for TESLA




# Cavity AC 73: 35 MV/m in CHECHIA



i.e. high power test and 1/8<sup>th</sup> of a TTF Linac module




# AC 72 also reached 35 MV/m in CHECHIA




# TESLA Test Facility Linac (TTF)




# RF Systems Assembled and Tested in TTF



## F II RF test: Power distribution/measurement diagram




# TTF High Power RF



Pulse Transformer



IGBT Stack



HV Power


Capacitor Bank

Bouncer



TH1801  
Multi-Beam  
Klystron

# In Beam LINAC vs. Vertical



13,000 hours of beam time



TTF - I Complete

TTF-II under construction  
In Model Tunnel

Experimental Hall for  
UV FEL Facility



# Model for TESLA Tunnel



# TESLA Test Facility Linac – Phase II

Six accelerator modules to reach 1 GeV beam energy.


Module #6 will contain 8 electro-polished cavities.

Engineering with respect to TESLA needs.

Klystrons and modulators built in industry.

High gradient operation of accelerator modules.

Space for module #7 (12 cavity TESLA module).



**FEL User Facility in the nm Wavelength Range**


|   |
|---|
| accelerator modules   |
| <b>module test /<br/>magnets / cryogenics</b>   |
| linac components<br>(injector, bunch<br>compressors,<br>diagnostics, dumps)             |
| Photons   |
| FEL concepts  |
| Controls / Operability  |
| Infrastructure<br>(site, civil<br>construction, survey,<br>tunnel layout,<br>utilities) |
| Safety  |
| Organisation  |

|  |
|--|
| 1. RF System   |
| 2. Low Level RF (LLRF) *                                     |
| 3. Accelerator Modules                                       |
| 4. S.C. Cavities *   |
| 5. Power Coupler   |
| 6. HOM Coupler / Pick-Up                                     |
| 7. Frequency Tuner   |
| 8. Cavity Flanges / Cold Vacuum (incl.warm injector section) |
| 9. Cavity String Assembly / Clean Room Quality Assurance     |

**Help Needed from  
Collaborators!**

TTF has defined 38 Work Packages

# RF Unit 1 klystron for 36 nine-cell cavities each



Low level RF cavity control must provide gradient and phase control of the cavities through feed forward and feedback systems, detect the relative beam to rf phase, detect developing cavity problems and faults, and provide exception handling.

DSP's in conjunction with ADC's and DAC's measure individual cavity gradient and phase, and forward and reflected power.

Example for further hardware advance : use of digital receivers.

## LLRF Continued

The DSP's get their parameters from the DSP server. The server software handles: generation of set point(SP) and feedforward (FF) tables from basic settings, matrices information for each cavity, loop phase constant, startup configuration files, and exception handler control parameters. **Server software and interface to the DSP's and control system needs detailed specification and code generation.**

**Development needed: connect DSP systems of different klystrons together through an optical giga Hz link.** Such a system would allow for very fast compensation by adjacent systems if one system experienced a fault.

**Definition of system architecture and concepts, as well as code, need to be developed.**

Low level RF simulation programs are being developed to check feedback and feed forward algorithms, response to cavity quench, or beam current variations, and non linear gain behavior of the klystron. **Effort is needed to develop, test and apply these simulators to RF control.**

|  |
|--|
| 1. RF System   |
| 2. Low Level RF (LLRF)                                       |
| 3. Accelerator Modules                                       |
| 4. S.C. Cavities   |
| 5. Power Coupler   |
| 6. HOM Coupler / Pick-Up                                     |
| 7. Frequency Tuner   |
| 8. Cavity Flanges / Cold Vacuum (incl.warm injector section) |
| 9. Cavity String Assembly / Clean Room Quality Assurance     |

Invites scientists knowledgeable in **material and surface physics** into understanding important properties related to high gradient and Q.

Grain size, hardness, tensile strength, RRR, workability, quality control of inclusions, eddy current scanning, chemical treatment, electropolishing parameters....

Copper plating, TiN plating for input couplers

|  |
|--|
| <b>accelerator modules</b>   |
| <b>module test /<br/>magnets / cryogenics</b>  |
| <b>linac components<br/>(injector, bunch<br/>compressors,<br/>diagnostics, dumps)</b>              |
| <b>Photons</b>   |
| <b>FEL concepts</b>  |
| <b>Controls / Operability</b>  |
| <b>Infrastructure<br/>(site, civil<br/>construction, survey,<br/>tunnel layout,<br/>utilities)</b> |
| <b>Safety</b>  |
| <b>Organisation</b>  |

|   |
|---|
| 14. Injector                                      |
| 15. Bunch Compression and Start-to-End Simulation |
| 16. Lattice Design and Beam Optics/Dynamics       |
| 17. Standard Beam Diagnostics                     |
| 18. Special Beam Diagnostics                      |
| 19. Vacuum system (warm)                          |
| 20. Beam Dumps                                    |
| 21. Undulators                                    |







\*

\*



# Beam Diagnostics

Stripline BPM





# Remote Involvement

---


Involvement of collaborators in design, construction, operation, and maintenance of the accelerator or experiment

This includes:

- remote operation
- remote experiments
- remote solving of problems
- remote improvements and developments
- coordination, sharing of information and documentation



# Overview of remote operation around TTF



## Proven Examples

- Remote operation and tuning of SC capture cavity from Saclay (Paris)
- Remote access and tuning of beam imaging system from INFN Frascati, Rome
- Remote regular shifts from INFN/LASA Milan
- Remote experiments from DESY at the Fermilab photo-injector test facility

# Possible Global Accelerator Network Activities

Setup remote control station and become familiar with aspects of the linac control and beam analysis.

Plan and carry out beam experiments

Develop new tests or get involved in ongoing diagnostics and rf control systems, machine protection systems....


Monitor beam-inhibit incidents and causes to determine how to minimize beam recovery time for a LC. Improve reliability of sub-systems

Develop Data Acquisition Systems, DSP Servers, User displays, e-logbooks, and Web based Tools to work towards demands of

True global operation of an international facility

# One Decade of TESLA R&D

- Big success for the TESLA collaboration
- But still much needs to be done

- 
- Good support from a wide SC community
    - Interested in SC technology for
      - light sources, neutron sources, high intensity proton beams
  - German Ministry supportive
    - by approving \$\$ for the 20 GeV XFEL
  - SC Linear Collider remains an exciting global activity inviting major contributions