



# DAQ system hardware status

David Ward (Cambridge)

for UK DAQ groups: Cambridge, Manchester, RHUL and UCL



# Outline



- ❖ System overview and recent progress
- ❖ Status of the individual (hardware) components
- ❖ System tests
- ❖ Numbers of each component and availability
- ❖ Summary and issues

# DAQ system overview



**(Detector Unit: ASICs)**


**DIF:** Detector InterFace connects generic DAQ and services

**LDA:** Link/Data Aggregator fansout/in DIFs and drives links to ODR

**ODR:** Off-Detector Receiver is PC interface

**CCC:** Clock and Control Card fans out to ODRs (or LDAs)

**Control PC:** Using DOOCS



# Overall status—progress in last year



- ❖ Final hardware tweaks and production versions of relevant components.
- ❖ Hardware orders so as to have enough systems available for lab and beam tests.
- ❖ Firmware improvements and finalisation.
- ❖ Delivered a full set of components to LLR for use and testing.
- ❖ System tests getting DAQ chain running are ongoing.

# ECAL DIF




- ❖ The ECAL DIF developed by the Cambridge group; HCAL DIFs developed by other groups, but all within the DIF task force.
- ❖ Produced a prototype board which worked well, in use at LLR. Have reduced number of components, whilst maintaining functionality (e.g. FPGA).
- ❖ Two DIFs have been produced and being used in system tests. Will now produce full run of 40 ECAL DIFs—all PCBs and components in-house.
- ❖ Not time critical but will start soon.
- ❖ Firmware being debugged in DAQ system tests.



# C&C card



- ❖ Incorporates all needs and connectors requested by calorimeter groups.
- ❖ Full complement of 10 boards with power supplies tested (one of which in LLR).
- ❖ CCC link to LDA still needs to be done : simple PCB attached to LDA.
- ❖ [Functionality
- ❖ CLOCK : machine
- ❖ FAST\_OUT : transfer asynchronous triggers
- ❖ FAST\_IN : used by DIFs to “stop acquisition”
- ❖ TRAINSYNC\_OUT : synchronisation of all front-end slow clocks]



# LDA



- ❖ The LDA (from Enterpoint) consists of : a Mulldonoch2 baseboard; an add-on HDMI board to connect to 10 DIFs; and an add-on ethernet board to connect to an ODR.

- ❖ Have 20 baseboards in-house.

- ❖ Have 5 ethernet boards in-house, 20 being manufactured.

- ❖ Have 5 HDMI boards in-house, 20 being manufactured.

- ❖ Firmware development ongoing :

- ❖ get DIF  $\Leftrightarrow$  LDA link running

- ❖ general improvements (different compilers)

- ❖ new code posted

- ❖ Hardware problems have been fixed by Enterpoint and new add-on boards should be delivered in two weeks (hopefully).

- ❖ Slightly complicated by Marc Kelly's departure.



So this is an example of commercially-available, off-the-shelf equipment ... all of which needed some corrections / additions / modifications from ourselves...

# ODR and DAQ PC



- ❖ System has generally been stable for a while :
- ❖ Firmware written.
- ❖ Control software.
- ❖ Linked to LDAem, LDA, etc..
- ❖ Performance optimised.
- ❖ Working on documentation and code repository in SVN.
- ❖ Interfaced with DAQ software.
- ❖ Customised DAQ PCs.
- ❖ Have 8 ODRs in house along with 6 DAQ PCs, one of each is at LLR.





# DAQ Software




- ❖ Started development using DOOCS software mainly by V.Bartsch and T.Wu.
- ❖ They have both left and David Decotigny (LLR) has taken over.
- ❖ Discussions ongoing also within context of FP7 bid for ideas as to the best way to go.
- ❖ We (UK) will be able to provide some additional effort for next ~6 months to help.

# System tests



- ❖ Have a system set-up in UCL :  
DAQ PC with ODR  $\Leftrightarrow$  LDA  $\Leftrightarrow$  DIF :
- ❖ using network analyser and 'scope to check signals
- ❖ using both prototype and production DIF
- ❖ this highlighted bugs and improvements...
- ❖ have sent commands ODR  $\Rightarrow$  LDA and received data back LDA  $\Rightarrow$  ODR
- ❖ have sent commands all the way up to the DIF, ODR  $\Rightarrow$  LDA  $\Rightarrow$  DIF
- ❖ link DIF  $\Rightarrow$  LDA has not yet been established—firmware updated and being debugged
- ❖ hopefully just a matter of a weeks until working.



# Hardware numbers needed



- ❖ Detectors' requirements :
  - ❖ ECAL : 30 layers → 30 DIFs, 3 LDAs, 1 ODR and DAQ PC, 1 CCC
  - ❖ AHCAL : 48 layers → (48 DIFs), 5 LDAs, 2 ODRs and 1 DAQ PC, 1 CCC
  - ❖ DHCAL : 40 layers → (120 DIFs, 14 DCCs), 2 LDAs, 1 ODR and DAQ PC, 1 CCC
- ❖ In general UK DAQ groups have to provide :
  - ❖ 30 ECAL DIFs, 10 LDAs, 4 ODRs, 3 DAQ PCs, 3 CCCs;
  - ❖ sufficient spares for test-beam running;
  - ❖ additional systems for tests in labs.
- ❖ Our procurement schedule is :
  - ❖ 40 ECAL DIFs (have 2, components for 40)
  - ❖ 20 LDAs (baseboards in-house, add-on boards expected in couple of weeks)
  - ❖ 8 ODRs and 8 DAQ PCs (have 8+6)
  - ❖ 10 CCCs (have 10)

# Summary



- ❖ Progress made (firmware, purchasing, developing) for all components and system as a whole.
- ❖ We are gradually building up a stock of components which should be sufficient for lab and beam tests. Complete very soon.
- ❖ Completion of EUNET milestone, “DAQ system available” satisfied by having production versions of hardware and a system at another institute.
- ❖ We need to have a debugged system within the next few weeks, then make sure the system at LLR is also running and stable and then provide systems to other groups.
- ❖ By the end of the year, UK effort will decrease rapidly.
- ❖ Work is and will be thoroughly documented on the wiki and archived in a code repository