



AAP Review on SCRF to be prepared

Akira Yamamoto, Marc Ross, and Nick Walker

ILC-GDE Project Managers

To be presented at ILC-10, Beijing, March 26, 2010

A horizontal dotted line in a light yellow-green color runs across the bottom of the slide, mirroring the one at the top.



Global Plan for SCRF R&D

| Year | 07 | 2008 | 2009 | 2010 | 2011 | 2012 |
|---|-------------|--|---|---------------------------|------|------|
| Phase | TDP-1 | | | TDP-2 | | |
| Cavity Gradient in v. test to reach 35 MV/m | → Yield 50% | | | → Yield 90% | | |
| Cavity-string to reach 31.5 MV/m, with one-cryomodule | | Global effort for string assembly and test (DESY, FNAL, INFN, KEK) | | | | |
| System Test with beam acceleration | | | FLASH (DESY) , NML (FNAL) STF2 (KEK, extend beyond 2012) | | | |
| Preparation for Industrialization | | | | Production Technology R&D | | |



What to be reviewed?

- **Fundamental Research** to improve 'Gradient'
 - R&D status and understanding of limit
 - **Strategy** for improvement
- **Preparation** for 'Industrialization'
 - **Cost effective production and quality control**
 - 90 % (9-cell cavity) corresponding to ~ 99 % (1-cell cavity)
 - **Balance** between R&D and ILC operation parameters with beam,
- **System Design and Engineering**
 - Integration (compatibility, alignment, accuracy)
 - **Optimization** with other components,
 - CFS, HLRF/LLRF, Beam handling, and others,
 - Best Operation Gradient to be determined



ILC Gradient Goals

500 GeV: Gradient and Q

Based on BCD cavity shape (TESLA cavity)

- BCD: Linac operating performance
Eacc = **31,5** MV/m; Q = **1x10¹⁰**
- BCD: Installed performance
Eacc ≥ **35** MV/m; Q ≥ **0.8x10¹⁰**
- Required R&D
 - Reduction of field emission and multipacting
 - Reduction of scatter of cavity performance


H. Edwards, D. Proch, K. Saito,
ILC snowmass 05, Wg5

| Parameter | Value |
|-------------------------------------|--|
| Type of accelerating structure | Standing Wave |
| Accelerating Mode | TM ₀₁₀ , π mode |
| Fundamental Frequency | 1.300 GHz |
| Average installed gradient | 31.5 MV/m |
| Qualification gradient | 35.0 MV/m |
| Installed quality factor | ≥1×10 ¹⁰ |
| Quality factor during qualification | ≥0.8×10 ¹⁰ |
| Active length | 1.038 m |
| Number of cells | 9 |
| Cell to cell coupling | 1.87% |
| Iris diameter | 70 mm |
| R/Q | 1036 Ω |
| Geometry factor | 270 Ω |
| E _{peak} /E _{acc} | 2.0 |
| B _{peak} /E _{acc} | 4.26 mT MV ⁻¹ m ⁻¹ |
| Tuning range | ±300 kHz |
| Δf/ΔL | 315 kHz/mm |
| Number of HOM resonances | 2 |

2005 Snowmass BCD proposal



2007 RDR



SB2009

4.1.2 Issues of Main Linac System Design

In conjunction with the (GDE and AAP) review process in 2010, based on the current R&D results we propose to keep the cavity gradient goals at 35MV/m in vertical test, 50, and 31.5MV/m in operation in an installed cryomodule, S1. We note that as the R&D progresses, including horizontal testing of



Alternative Yield Plot Analysis



originated by N. Walker and updated by J. Kerby

Dec 2009 Data:

1st +2nd Pass, 1st pass cut 35MV/m,
vendors w/ 1 cavity > 35MV/m

Electropolished 9-cell cavities

JLab/DESY (combined) up-to-second successful test of cavities from qualified vendors - ACCEL




- Yield: estimated assuming a specific lower cut-off in cavity performance, below which cavities are assumed 'rejected'.
- Error bar: +/- one RMS value (standard deviation of the population) of the remaining (accepted) cavities (gradient above cut-off).
- Additional bars (min, max) indicated the minimum and maximum gradients in the remaining cavities.



Improvement of Cavity Gradient in two ways

Two Big Pushes Ahead...



First presented at cavity vendor meeting at FNAL, March 6, 2009

- More discussed by R. Geng in parallel session

How we may improve Gradient ?

- Yield drop at 15-20 MV/m is a major issue
 - Shared issue with XFEL and CEBAF upgrade cavities
- Solution requires actions in cavity fabrication
 - EBW QA/QC
 - Finished weld inspection
 - Early correction
- Feedback enables change and then progress expected
 - Experienced vendors
 - New vendors

Guideline: Standard Procedure and **Feedback Loop**

| | Standard Fabrication/Process | (Optional action) | Acceptance Test/Inspection |
|---------------------------|--|-------------------------|--|
| Fabrication | Nb-sheet purchasing | | Chemical component analysis |
| | Component (Shape) Fabrication | | Optical inspect., Eddy current |
| | Cavity assembly with EBW | | Optical inspection |
| Process | EP-1 (Bulk: ~150um) | | |
| | Ultrasonic degreasing (detergent) or ethanol rinse | | |
| | High-pressure pure-water rinsing | | Optical inspection |
| | Hydrogen degassing at 600 C (?) | 750 C | |
| | Field flatness tuning | | |
| | EP-2 (~20um) | | |
| | Ultrasonic degreasing or ethanol | (Flash/Fresh EP) (~5um) | |
| | High-pressure pure-water rinsing | | |
| | General assembly | | |
| | Baking at 120 C | | |
| Cold Test (vertical test) | Performance Test with temperature and mode measurement | Temp. mapping | If cavity not meet specification Optical inspection |

000528 ADI Meeting at DESY 17

- More discussed in parallel session



SCRF Gradient in 'R&D' and 'Project'

- R&D Goals set in RDR
 - 9-cell cavity: to reach **35 MV/m at $Q_0 = 8E-9$** at the vertical test, with the production yield at $> 90\%$
 - Cryomodule: to reach **$<31.5\text{ MV/m}>$ at $Q_0 = 1\text{ E}10$,**
- Project Goal/Parameter set in RDR
 - ILC operational gradient set at $< 31.5\text{ MV/m}>$ including cavity **operational margin** to the quench/field-emission limit and also accelerator control/operational margin for HLR/LLRF
- **Seek for reasonable balance** between 'R&D goals' and the 'Project Parameters' in TDP
 - Understanding the status with the global data base
 - Re-optimization of the parameters in system design


Around the World

Cryomodule surpasses ILC gradient test

European-XFEL cryomodule using SCRF technology sets new record



The cryomodule that set the world gradient record in the testbench at DESY



First XFEL prototype module exceeds 31.5 MV/m average

- Module will see beam in FLASH in 2010 (av. of 30MV/m)
- Cryostat (cryomodule cold-mass) contributed by IHEP, in cooperation with INFN



What we need to study in TDP-2

- Balance between R&D target values and Operational parameters
Will be reviewed after S1 experience
- System design should require reasonable margin for the individual component and the system operation

S1 (~ Component performance) > ILC-Acc. Operational Gradient

| | RDR/SB2009 | Re-optimization required with cautious, systematic design | |
|------------------------------|-------------|---|--|
| R&D goal: S0 | 35 (> 90%) | 35 MV/m (> 90 %) <i>Keep it, and forward looking</i> | |
| S1 (w/o beam) | 31.5 in av. | <i>need:</i> > 31.5 in av., to be further optimized | 31.5 in av. |
| S2 (w/ beam acc.) | 31.5 in av. | > 31.5 in av. | 31.5 in av. |
| ILC: operational gradient | 31.5 in av. | 31.5 in av. (+/- 10 ~ 20 %) | <i>or:</i> < 31.5 in av., to be further optimized |



What to be reviewed?

As Summary

- **Fundamental Research** to improve 'Gradient'
 - R&D status and understanding of limit
 - **Strategy** for improvement
- **Preparation** for 'Industrialization'
 - **Cost effective production and quality control**
 - 90 % (9-cell cavity) corresponding to ~ 99 % (1-cell cavity)
 - **Balance** between R&D and ILC operation parameters with beam,
- **System Design and Engineering**
 - **Integration (compatibility, alignment, accuracy)**
 - **Optimization with other components,**
 - CFS, HLRF/LLRF, Beam handling, and others,
 - Best Operation Gradient to be determined



backup

- TBD




Summary

- In SB2009, ILC operational field gradient left unchanged
 - CF&S study enables to stay at 31 km in ML tunnel length
- SCRF cavity gradient R&D Goal
 - Being kept: 35 MV/m (at $Q_0 = 8E9$) with the production yield of 90 %,
 - Spread of cavity gradient effective to be taken into account
 - to seek for the best cost effective cavity production and use,
- **Re-optimization to establish ILC operational gradient**
 - Necessary adequate balance/redundancy between the ‘R&D gradient-milestone’ and the ‘ILC operational gradient’ including sufficiently high ‘availability’ with risk mitigation.
 - Necessary engineering and cost balance b/w Cavity and HLRF/LLRF
- Further optimization for design parameters & construction.
 - Cryomodule/cryogenics, Quadrupoles, plug-compatibility, and industrialization



SCRF Technology Required

| Parameter | Value |
|---------------------------|---|
| C.M. Energy | 500 GeV |
| Peak luminosity | $2 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ |
| Beam Rep. rate | 5 Hz |
| Pulse time duration | 1 ms |
| Average beam current | 9 (or 4.8) mA (in pulse) |
| Av. field gradient | 31.5 MV/m |
| # 9-cell cavity | 14,560 |
| # cryomodule | 1,680 |





TDP Goals of ILC-SCRF R&D

■ Cavity Field Gradient (S0)

- 35 MV/m in vertical test

■ Cavity-string Assembly in Cryomodule (S1)

- $\langle 31.5 \text{ MV/m} \rangle$ in cavity string test in cryomodule
 - To be re-evaluated in preparation for SB-2009 proposal.
- Efficient R&D with “Plug-compatibility” for
 - improvement and ‘creative work’ in R&D (TDP) phase

■ Accelerator System with SCRF (S2)

- Beam Acceleration with SCRF Accelerator Unit
 - Need to discuss an reliable, operational field gradient including adequate HLRF/LLRF control margin for stable operation

■ Industrial Production R&D

- Preparing for production, quality control, cost saving
 - “Plug compatibility” for global sharing in production phase



Standard Process Selected in Cavity Production and the Yield

| | Standard Cavity Recipe |
|------------------------|--|
| Fabrication | Nb-sheet (Fine Grain) |
| | Component preparation |
| | Cavity assembly w/ EBW (w/ experienced vendors) |
| Process | 1st Electro-polishing (~150um) |
| | Ultrasonic degreasing with detergent, or ethanol rinse |
| | High-pressure pure-water rinsing |
| | Hydrogen degassing at > 600 C |
| | Field flatness tuning |
| | 2nd Electro-polishing (~20um) |
| | Ultrasonic degreasing or ethanol |
| | High-pressure pure-water rinsing |
| | Antenna Assembly |
| | Baking at 120 C |
| Cold Test (vert. test) | Performance Test with temperature and mode measurement (1st / 2nd successful RF Test) |



Improved Understanding in Quench Limit

- Routine 9-cell T-mapping and optical inspection
 - New insights from pre-cursor heating studies at JLab
 - First predictive defect study at DESY
 - Cornell 2nd sound sensors will be available for labs
 - Many labs use “Kyoto camera” (JLab just received a loan unit)
- New finding: many 9-cell is quench limited at 20-25 MV/m by only one defect in one cell with other superior cells already reaching 30-40 MV/m
 - There may or may not be observable flaw in quench site
 - This seems to suggest we need to address material aspect besides processing and fabrication in TDP-2
 - This also suggests some local repairing is needed for efficient raise of 2nd pass gradient yield




A Major Next Battle: Eliminate Yield Drop near 20 MV/m

Despite increased acceptance thanks to more flexible

HLBF


UL and DESY (combined) up-to-second successful test of cavities from qualified vendors - ACCEL+ZANON+AES (25 cavities)





Another Next Battle: Further Reduce Field Emission up to 40 MV/m

Flexible HLRF opens up possibility of some individual cavity operates up to 38 MV/m






New Production Yield

after 1st and 2nd Pass (RF) Test

Electropolished 9-cell cavities

JLab/DESY (combined) first successful test of cavities from qualified vendors - ACCEL+ZANON (22 cavities)




1st pass


Yield at 35 MV/m:
22 % at 1st pass
33 % at up to 2nd pass

Electropolished 9-cell Cavities

combined upto-second-pass test of cavities from qualified vendors - ACCEL+ZANON (21 cavities)



2nd pass



improvement

degradation

ILC Operation at <31.5 MV/m>
Yield reaching ~ 40 %

Reported by C. Ginsburg and GDB team



Progress and Prospect of Cavity Gradient Yield Statistics

| | PAC-09 Last/Best 2009-05 | FALC 1 st Pass 2009-07 | ALCPG 2nd Pass 2009-10 | To be added (2009-11) | Coming Prod. Y. (2010-06) | Research cavities |
|----------------------------------|--|---|------------------------------|-----------------------------|---------------------------------|--------------------------------------|
| DESY | 9 (AC) 16 (ZA) | 8 (AC) 7 (ZA) | 14 (AC/ZA) | 4 (Prod- 4) | 5 | 8 (large G.) |
| JLAB FNAL/A NL/Corn ell | 8 (AC) 4 (AE) 1 (KE-LL5) 1 (JL-2) | 7 (AC) | 7 (AC) | 5 (AE) | 12 (AC) 6 (AE) 2 (AC) | 6 (NW) (including large-G) |
| KEK/IH EP | | | | 0 (MH) | 2 (MH) | ~5 (LL) 1 (IHEP) |
| Sum | 39 | 22 | 21 | 10 | 25 | ~ 20 |
| G-Sum | | | | 31 | 57 | |

Statistics for Production Yield in Progress to reach ~ 60, within TDP-1.
We may need to have separate statistics for 'production' and for 'research',