# Alternative assembly option of ILD

Y.Sugimoto 2010/10/18 ILD Integration Meeting @CERN

## ILC in mountain regions

- Design study of accelerator and conventional facilities (CF) in mountain regions is one of the major activities in GDE
- Design of the detector hall in mountain regions should be done by the detector community in cooperation with GDE CF group
- We (T.Sanuki, Y.Makida, M.Miyahara, Y.Sugimoto, T.Tauchi, H.Yamaoka, M.Yoshioka, A.Sugiyama) are now involved in this activity (since Apr.2010)

#### An example of Asian mountain site



## Exp-hall in mountain regions

- For CMS-style assembly using big vertical shafts, depth of IP should be d≤100m
- This requirement restricts the location of IP in mountain regions
- By removing the constraint of d≤100m, more flexible choice of IP location and accelerator layout can be made
  - Selecting the location of the cavern with better geology would reduce the cost and the construction period
    - Exp-hall without vertical shafts may be more suitable for some candidate sites in mountain region



• In that case, access tunnels are used to carry detector and accelerator components into detector cavern or accelerator tunnel

• We have just started to study on the exp-hall design and detector assembly method without vertical shafts as an option

(n.b. It does not mean that the CMS-style assembly using vertical shafts is excluded for all candidate sites in mountain regions)



#### **Detector assembly**

- Assembly hall locates at the entrance of access tunnel where wide flat surface and wide roads exist
- Detector would be assembled to relatively small pieces (<100~200 ton) at the assembly hall, carried to the cavern through the access tunnel, and integrated to the large detector inside the cavern (Similar to "modified CMS style assembly" which was proposed by GLD group in 2006)
- Barrel iron structure would be divided in φ (and R) direction, rather than Z direction
- Solenoid coil would be wound on surface for 5 modules, and these modules are connected into one solenoid in the cavern
- Detailed study on the assembly method is necessary 6

#### Comments

- Comments at DESY ILD WS in July
  - Construction period?
  - Space for assembly of the solenoid and iron yoke?
- Comments by SiD at CFS WS @SLAC in Aug – No problem!

## **Construction period**

- Construction period is one of the most controversial issues for the shaft-less exp-hall
- Construction period of an access tunnel (L~1km) would be similar to that of a vertical shaft (φ=18m, d~100m)
- Non-CMS style assembly was once proposed for GLD as "modified CMS assembly" which can be done within the same time period as the CMS style assembly
- Assembly of the iron yoke structure and the solenoid in the cavern would take ~1y, but it does not mean that non-CMS style assembly (new modified CMS-style assembly) takes 1y more than CMS style assembly

### **CMS** Style





#### Modified CMS style

D	0	Name	Duration	2	015	2016	2017	2018	2010	2020	2021	2022	2023
1		Project approval	0d	•	01/01								
2		Beam lines construction	1955d		-								
3		Cavem/Tunnel	260w										
4		Beamline harware install	105w							·	-	<u>t</u>	
5		Start of beam commissioning	Od								•	12/29	
6		BDS pre-commissioning	26w										
7		BDS ready for detectors	Od									♦ 06/2	9
8		Detector construction	1955d	- Ý									
9		Surface assembly hall	120w										
10		Detector assembly	245w				Ĺ	1				L.	
11		Detector surface commissioning	26w									<u>É la c</u>	
12		Detector ready for BDS	Od										9
13		Final assembly & commissioning	130d									••••••••••••••••••••••••••••••••••••••	•
14		Detector underground assembly	13w					t do					
15		Final beam commissioning	13w					style					Ъ.
16		Ready for physics run	Od										🕴 12/28

D	0	Name	Duration	2015	2016	2017	2018	2019	2020	2021	2022	2023
1		Project approval	Od	 <b>∲</b> ]01/01								
2		Beam lines construction	1955d								<b>•</b>	
3		Cavem/Tunnel	260w		1			1				
4		Beamline harware install	105w								<u>h</u>	
5		Start of beam commissioning	Od								12/29	
6		BDS pre-commissioning	26w									
7		BDS ready for detectors	Od								🕈 06/2	9
8		Detector construction	1690d	-								
9		Surface assembly hall	120w									
10		Detector assembly on surface	218w			Ĺ						
11		Final assembly & commissioning	785d						Ļ			•
12		Detector underground assembly	105w								<b>L</b>	
13		Detector pre-commissioning	26w					4	f \/ -			
14		Detector roll-in	4w					19	tor Yoke a	ssembly +	Ŀ.	
15		Support tube, beam pipe, VTX ins	5w					🗖 1y	for Sub-de	etector insta	all 🛄	
16		Detector check-out	4w		Mod	dified C	MS stvl	e			L L	
17		Final beam commissioning	13w					<b>~</b>				h I
18		Ready for physics run	Od									🕴 12/28

http://www-project.slac.stanford.edu/ilc/acceldev/beamdelivery/rdr/docs/CCR\_surface/BDS\_schedule.pdf

#### New modified CMS style

ID	0	Name	Duration		$\frac{2015}{102}$			2018	2010				2023
1		Project approval	Od	¢	חר איז								
2		Beam lines construction	1955d	Ý								<b>V</b>	
3		Cavem/Tunnel	260w				-			t,			
4		Beamline harware install	105w									h.	
5		Start of beam commissioning	0d									<b>€</b> 12/29	
6		BDS pre-commissioning	26 w										
7		BDS ready for detectors	Od									- <b>+</b>	06/29
8		Detector construction on surface	1850d	Ý	¥ The second sec								
9		Surface assembly hall	120w		•	1							
10		Detector assembly on surface	250w					1					
11		Detector assembly in cavern	550d						ų	4			
12		Yoke assembly	53w							L			
13		Solenoid assembly/install/test	66 w										
14		Field mapping	4w								ų,		
15		HCAL install/cabling/test	12w								Ľ.		
16		ECAL install/cabling/test	12w										
17		TPC install/cabling/test	8w								Ĺ		
18		SIT/FTD/VTX install/cabling/test	8w										
19		Commissioning	235d										
20		Detector pre-commissioning	26 w										
21		Detector roll-in	4w										<b>L</b>
22		Detector check-out	4w										ll,
23		Final beam commissioning	13w										
24		Ready for physics run	Od										🔶 12/28

### Space for assembly

- We need enough space to assemble the iron yoke and the solenoid in parallel
- Solenoid assembly procedure and installation method have to be studied
- Exp-hall should be equipped with two 200-ton cranes: usually one for each detector, and occasionally two cranes are used together to carry heavy (>200 ton) components



## Lower risk option

- Larger (h~11m) access tunnel is an attractive option if the cost is not very high
  - Solenoid is constructed and tested on surface, and carried into the cavern through the access tunnel
  - This option has much less risk

## Summary

- Modified CMS style assembly for shaft-less detector hall will not take
  longer time than CMS-style assembly
- Underground space needed for solenoid assembly is not clear yet
- Solenoid assembly/test on surface is an attractive option if the cost of larger access tunnel is not terribly high
- There are many issues to be studied for the exp-hall optimization; some of them are common to the CMS style assembly:
  - Configuration of He system (He compressor location, piping compatible with push-pull, etc.)
  - Power supply of Solenoid (location, electricity, cooling)
  - Gas ventilation in solenoid quench
  - Power consumption (He compressor, detector, lighting, etc.)
  - Cooling water (detector, dump resister, etc.)
  - Air conditioning (cooling)
  - Drainage of ground water

- Human safety including escape route
- Vehicle for heavy (~200 ton) components through the access tunnel

14

#### **Backup slides**

A-A'

B-B'



C-C'



D-D'

E-E'







### Huge caverns in Japan

- More than 20 huge caverns with access tunnels have been constructed in Japan for hydroelectric power plants
- A 25m(W)x47m(H)x130m(L) (94,000m<sup>3</sup>) cavern can be excavated only in 14 months, and a 34mx54mx210m (250,000m<sup>3</sup>) was excavated in 21 months



21

#### Example of a cavern

- Underground hydroelectric power plant in Japan (Kannagawa power plant)
- Cavern size: 33m(W)x51.4m(H)x215.9m(L) in hard sedimentary rocks
- Construction (excavation) period: ~1y for arch, ~1y for bench
- Depth: d~600m → Heavy components of generators were carried into the cavern through access tunnels

