



FCAL task status report

Sergej Schuwalow

DESY/UNI-HH

On behalf of the FCAL collaboration

Very Forward Region of the ILD Detector



Outline

- Infrastructure:
- Probe stations, tests of LumiCal sensors
- ⁹⁰Sr setup sensor tests at the lab
- high intensity beam measurements
- LumiCal sensor prototypes
- Laser Alignment System
- BeamCal sensor tests
- Readout electronics
- ADCs recent developments
- System test at DESY testbeam, Aug 2010
- Future: full system test at the beam (FP7)



Infrastructure: Probe Stations

Tel-Aviv University



Needle contacts Inner guard ring -> Guard curcent Needle contacts one pad -> pad current or pad capacitance

DESY - Zeuthen



Backplane contacted via Al table ('+' of high voltage)

Infrastructure: BeamCal sensor tests in the lab



Infrastructure: High dose irradiation at the beam





30 September 2010

Infrastructure: BeamCal Sensors study at the beam

Setup for Beam Pumping -Measurements

scCVD diamond (E6), 5x5x0.3 mm³ Irradiated in 2007 up to 5 MGy 2008: up to 10 MGy





Infrastructure summary: EUDET-Report-2009-08 VFCAL task status report

Sensor prototypes (LumiCal, deliverable) EUDET-Memo-2009-07 J.Blocki, W.Daniluk, E.Kielar et al., Silicon Sensors Prototype for LumiCal Calorimeter

"Cracow-Design"

- High resistivity n-type Si
- 1,7mm p+ strips with an Al-metallization
- Backplane: n+ implant and an Al-metallization
- 3 Guard rings

x-Size = 10,8cm y-Size = 4...12cm (6 Inch Wafers)

40 sensors produced by Hamamatsu Photonics Hamamatsu S10938-8380



I(V) and C(V) measurements on Probestations in Tel Aviv, Cracow and DESY

Laser Alignment system (LumiCal)



EUDET-Report-2008-05 W.Daniluk et al., Laser Alignment System for LumiCal.

EUDET-Report-2009-08 VFCAL task status report, S.Schuwalow for FCAL Collaboration

EUDET annual meeting, DESY

BeamCal Sensors example Baseline: GaAs

Up to 600 kGy a MIP signal from all sensors is clearly seen

Sensors with a lower concentration of shallow donor and Cr as deep acceptor show better radiation tolerance (up to 1 MGy)





BeamCal Sensors, Sapphire

Band gap: 9.9 eV (diamond: 5.5 eV, Si: 1.12 eV) Single crystal, 1x1x0.05 cm³ Wafer: up to 30 cm diameter Metallization: Al 200 nm or 50/50/100 nm Al/Ti/Au

Normalized ratio of the detector and Faraday cup currents



Charge collection efficiency: few % for nonirradiated samples

~ 30 % of the initial charge collection efficiency after 12 MGy

Test in PITZ

Electron beam, 14.5 MeV, bunches

Diamond sensor was installed in the vacuum of the beam pipe



Moving the sensor through an electron beam,

Bunch charge 1 pC - 1 nC, Beam spot: few mm² Beam profile

EMI doesn't disturb operation





LumiCal readout architecture





Preamplifier&PZC&Shaper







- ASIC with 8 channels
- Variable gain (MIPs and high input charge up to ~ 10pC)
- □ C_{det} range ~ 0-500 pF
- □ 1st order shaper T_{peak} ~ 60 ns
- □ Power consumption < 9 mW/chan



- □ 1st prototype: 8 stages (fully functional)
- □ 2nd prototype of complete ADC (photo)
 - 9 stages + S/H
 - digital correction
 - clock and power switching
 - external reference voltages
- 2nd prototype fully functional, tests completed



EUDET annual meeting, DESY



ADC dynamic measurements









Presently power consumption about 1 mW/MHz (Nyquist input frequency, including output buffers) The tests confirmed that ADC fulfils all specifications and may be used in multichannel readout



Multichannel ADC





 The first measurements show that all 8 channels are working properly and the overall performance seem to be similar to single channel version or slightly better





System tests: testbeam @ DESY, August 2010

Precise XY-table



Detector box (BeamCal sensor installed)



Similar box for the LumiCal sensor



LumiCal testbeam results



amp =



Landau distribution

500

Time [ns]

600

800

700

LumiCal testbeam results

Data and MC : different thickness of tungsten absorber Preliminary results



MC distributions are sensitive to a value of an air gap between absorber and sensors used in simulation (a few cm)



The observed differences between data and MC are under study. Wrong value of air gap in MC?

25



Next: System test in a beam with FCAL module -> FP7

Infrastructure to verify performance simulations:

A flexible tungsten absorber structure, depth 10 X_0 , precise mechanics

Multichannel FE and ADC ASICS to instrument 10 consecutive sensor layers

Tools to assembly 10 sensor sectors

Optical position control of the sensor sectors wrt the tungsten frame

DAQ (common with other components)

Power pulsing (common developments)

Conclusions

- Infrastructure for VFCAL sensors evaluation is ready
- Prototyping of Si sensors for LumiCal successful. Sensors are tested using probe stations at Cracow, DESY and Tel-Aviv
- Laser Alignment System prototype completed
- FE ASICS are ready and tested with sensors
- System test (sensors+fanout+FE) at DESY testbeam done
- ADC ASICs second submission successful, first prototypes of multichannel version are under test
- Investigation of the radiation hardness of GaAs, Diamond and Sapphire BeamCal sensor prototypes done up to 12 MGy dose
- NEXT: FCAL Module system test at the beam in future (FP7)





Backup slides

Application at FLASH

FCAL designed, constructed and installed a Beam-Condition Monitor at FLASH (4 diamond and 4 sapphire sensors

Operation in the "9 mA" run of FLASH was successful





30 September 2010

EUDET annual meeting, DESY