## A Model for Industrialization

- Total numbers of SCRF 9-cell cavities required for ILC (Main Linac +Damping Ring + others)
  – 15,764
- A model for 9-cell cavity productions
  - 15,764 + spare + production back-up (~ 10%)
  - $\rightarrow \sim 18,000$  cavities / 4~ 5 years
- Possible models for manufacturing
  - Single consortium/vendor
  - Three regional consortiums/vendors
  - Six (or more) consortiums/vendors
    - < 3,000 > cavities / vendor
    - < 3 > cavities / day / vendor (assuming 5 yrs & 200 days/yr)

**Cavity Industlialization WS** 

#### **Industrialization Models**

- Global Vendors/Consortiums/Laboratories
  - **Research Instruments (ACCEL) and Zanon in Europe** —
  - **AES, Niowave/Roark, and PAVAC in Americas** \_
  - MHI, (Hitachi, Toshiba, and others) in Asia

Production Models and Rate of SCRF Cavities							
Project	# of Cavities assumed	# of Vendors	Production period (years)	Production Rate: (Cavities/day/vendor) (at 200 ~ 250 work-days/yr)			
SNS	~ 110 (including +20%)	1	3	0.2 ~0.15			
XFEL	(~640)	(1) (2)	(3) (3)	(1.1 ~ 0.85) (0.55 ~ 0.43)			
ILC	(~ 18,000) (including +10%)	(1) (3) (6)	(5) (5) (5)	(18 ~ 14.4) (6 ~ 4.8) (3 ~ 2.4)			

**Cavity Industlialization WS** 


# **Prepare for ILC-scale Industrialization**

- Learn from previous efforts and current status:
  - Industrialization study for TESLA (1990's)
  - Recent R&D progress (in ~ 10 years)
  - Current status in industries (in progress)
- Learn from industrialization of XFEL Project
- Encourage Laboratory / Industry partnerships
  - Realized in all 3 regions
    - Europe: XFEL, Americas: Venders manufacturing, Asia: A pilot plant at KEK
  - Prepare for cost-effective production and quality control in cooperation with industries
- Communication with Industries
  - 1st: Visit Venders (done in 2009)
  - 2nd: Workshop (done at IPAC-10 satellite meeting)
  - 3<sup>rd</sup>: Call for Response with a preliminary specification and cost estimate by industries

# **IC** SCRF-ML Technology Required

<b>RDR Parameters</b>	Value				
C.M. Energy	500 GeV				
Peak luminosity	$2x10^{34}$ cm <sup>-2</sup> s <sup>-1</sup>				
Beam Rep. rate	5 Hz				
Pulse time duration	1 m s				
Average beam current	9 mA (in pulse)				
Av. field gradient	31.5 MV/m				
<b>#9-cell cavity</b>	14,560				
# cryomodule	1,680				
# RF units	560				









**Cavity Industlialization WS** 

#### **ii** Global Plan for SCRF R&D

Year	07	200	)8	20	09	20	010	2011	2012
Phase		TDP-1				TDP-2			
Cavity Gradient in v. test to reach 35 MV/m		$\rightarrow$ Yield 50% $\rightarrow$			Yield 90%				
Cavity-string to reach 31.5 MV/m, with one- cryomodule		Global effort for string assembly and test (DESY, FNAL, INFN, KEK)							
System Test with beam acceleration			FL/					IL (FNAL start in 2	·
Preparation for Industrialization	Production Technology R&D				ology				

#### Numbers of processes trade-off

iii.

	Yield %	Fabrication of Dumb-bell with EBW	Fabrication of End group EBW	Assemble	Number of machines and processes required			
				9-cell Cavity With EBW	EB Weldin g	Vertical Test	Electro- polishin g	
Case1	100	1 seam / welding		one 2(4,8)- cell / welding cycle (9 hrs/9 cycle)	12	6		
R&D phase	90	cycle (3 hrs/3 cycle)	1 seam / welding cycle (11 hrs / 11 cycle)			7	6	
Case2 Current	100			one 9-cell / 2 welding cycle (4.7 hrs / 2 cycle)	8	6	6	
prod.	90	8 dumb-bell			$\rightarrow$ 7*	7	Ŭ	
Case3 Mass Production Study	100	/ welding cycle	8 end group / welding cycle (46.7/8 hrs/11 cycle)		5 → 4*	6	6	
	90	(6.5/8 hrs/3 cycle)				7		

\* In case of common EBW machines