


# Report from SNS on HOM Coupler

**May 18, 2006**  
**ILC technical status meeting**

**SANG-HO KIM**  
**ASD/SNS**

# SNS SRF cavity

Major Specifications:  
 $E_a = 10.1, 15.9$  MV/m  
at  $\beta = 0.61, 0.81$





# Cavity Performances

Maximum fields achieved in the installed cavities.

Operational fields are kept in general at the 75-80% of the maximum fields



High beta cavities are limited at lower Bmax and show lower FE threshold.

→implies cavities are mainly limited by other factors rather than quenching




# HOM coupler

- Baseline cavities have coaxial HOM coupler at each side
- Two cavities are not operational due to the HOM coupler
- Many installed cavities (~10) are showing abnormal signals
  - zero coupling and rep. rate dependent abnormal signal
  - electron loading
  - power level changes
- HOM coupler should not have problems with the fundamental mode







# Feedthrough & Cable



Feedthrough




FT End  
Some are  
Screwed,  
Some are  
soldered



HOM cable inside cryomodule  
Inner conductor; thermally floating  
Outer conductor; strapped

# HOM Qex's (low power measurement)





# Case (I)

Same cavity at the same gradient



1 Hz

10 Hz



# Case (II)

## Electron Loading




It is not clearly seen here, but observed big spikes only from HOM signals (blue circled)  
→ vacuum excursion (trip)




# Case (III)

## Coupling changes




# Possible Causes



## H field

On feedthru tip (Cu)  
; ~5 mT at nominal flat field




## Field enhancements

Field tilt  
gap distance uncertainty

## E field

At both ends of antenna  
~10 MV/m  
at nominal flat field




## Local Vacuum

Warm (hot) feedthrough  
Leak

## Surface Cleanliness

Electron loading



## Field emission

# Options for HOM coupler

## Option1

More robust HOM couplers  
are being developed.

Jlab; SC feedthru

Feedthru w/ Sapphire insulator

Feedthru tip geometry

Additional cooling

DESY; SC feedthru

Nb tip attached to HOM antenna

## Option2

If HOM coupler is not an essential device,  
we can think of removing it.

Physics concerns are still same

No beam dynamic issue (D. Jeon)

HOM power issue; higher beam current  
but statistically about same

**Major Concerns (other than HOM damping)**

**Evaporation of Cu**

**Damaging ceramic**

**Degradation of cavity performance**

**Benefit**

VS.

**Risk, Statistical reliability &  
impact on operational availability**

**Studies are under progress  
including prototype test**