

Beam Dumps

SNOWMASS, 15 August, 2005


R. Sugahara
KEK

These are results studied by GLC Conventional Facility Study Group.

(Study on ILC beam dump system is going to be started.)

Radiation problem was studied in detail by S. Ban et al. of KEK Radiation Science Center.


System and layout were studied and designed under the cooperation with Nikken Sekkei Ltd., Hitachi Engineering Co., Ltd. and Hitachi High-Technologies Corporation.



Apertures Shields ?

Background neutrons, photons to be estimated the BDS-SIM.

Better with large crossing angle mrad ?



Beam Dump
1.6m-dia. x

umped power of 500 GeV beam

12 MW (e+, e- 11 MW, Gamma 1 MW)

Dimension: 9 m long x 1.6 m diameter
(25 radiation length)

Water pressure: 1 M Pa

Water flow: 333 m³/h

Amount of water in the dump: 20 m³

Recovery tank: 60 m³ ... three times larger than beam dump

Amount of H₂ production in the water: 3L/s

H₂ Recombiner : 10 L/s ... three times larger than H₂ production

Recombiner must be placed higher than Beam Dump, and
Recovery Tank must be lower than Beam Dump.

estimate radioactivity in the water,

Cross Section Calculation Code : PICA3/GEM

Amount of Radioactivity in the water

Be-7: 60 TBq

C-11: 96 TBq

N-13: 72 TBq

O-15: 280 TBq

ventilation system

Exchange the air in the dump hall (3200 m³) in 1.5 hours

activation in soil around the dump hall


Na-22 in the soil is less than IAEA Exemption Level, 10 Bq/g

Amount of Radioactivity in Ion-exchangers

Estimated using the data for the KEK Proton Synchrotron
Cooling Water System

Nuclei	Half life	Amount of activity(GBq)	Dose μ Sv/h@ 1m
Be-7	53.29Day	60000	428000
Co-58	70.86Day	57.6	7550
Co-57	271.7Day	14.7	258
Mn-54	312.1Day	12.9	1430
Co-56	77.23Day	4.96	2100
Co-60	5.271Year	1.59	485

beam dump Recovery tank for beam dump water



Purifier
(10 m³/h)

H2 recombiner
cooling system

<Primary loop>

<Secondary loop>

Water pump for primary system
(333 m³/h)


Water pump for secondary system
(400 m³/h)

Third cooling
system
(500 m³/h)

Heat exchanger


一次ループ	中間ループ	冷却ループ
$\Delta T = 38^\circ\text{C}$	$\Delta T = 38^\circ\text{C}$	$\Delta T = 32^\circ\text{C}$
$Q = 13,000\text{kW}$	$Q = 13,000\text{kW}$	$Q = 13,000\text{kW}$
$W = 333\text{m}^3/\text{h}$	$W = 400\text{m}^3/\text{h}$	$W = 500\text{m}^3/\text{h}$


熱収支



Inside
建屋内
↑↓
屋外
Outside



(Two systems for safety)





the room for cooling system


Layout




Recovery tank for beam dump water

Beam dump

(b) Primary cooling system



Storage for radio-activated equipment



Detailed study on following items is needed:

Beam dump structure

Beam window

Scenario how to change the beam window

How to move used beam dump to the storage room

How to move used radio-activated equipment to the storage room

Maintenance scenario for each equipment

etc.

Need to study the case that tritium water in the beam dump leaks in the

How to remove the water from the air completely.


Need to update to ILC version

Beam power: 11MW --> 23MW

Power of bremsstrahlung-gamma: 1MW --> 2MW



GLC 1TeV



Spot
2nd FP

