Americas Region

#### HLRF RDR Cost Effort Brief Overview

Ray Larsen 16 May 2006 For the HLRF Technical Systems Group

#### HLRF Area Systems Summary

	HL	RF Area	Require	ments Su	immary	051606-1	rsl-R1				
Area	Main 1	Main Linacs		Sources		RTML		BDS		Damping Rings	
RF Stations	e-	e+	e-	e+	e-	e+	e+	e-	2xe+	e-	Totals
10 MW RF Station, 1.3	315	315	6	7	21	21					685
GHz, Cryomodules											
10 MW RF Station, 1.3 GHz, RT Cavities, 500 MeV			8	31							39
Keep alive Total 10 MW RF 1.3 GHz RF Stations											723
5045 S-Band Stations Un- sledded					2	2					4
5045 S-Band Stations Sledded					1	1					2
Total 5045 S-Band Stations											6
e- Ring CW RF Stations, 650 MHz, 5 GeV, 4MW beam power, 8 - 500kW RF Stations										8	8
e+ Ring CW RF Stations, 650 MHz, 2 Rings for 5 GeV, 4MW beam power, 16- 250kW RF Stations									16		16
Total 650 MHz CW RF Stations											24
10 -40kW CW RF Stations, Details TBD (A. Seryi)											

#### 10 MW RF Station Scope (685 Cold + 39 RT = 724 Total)

- HVAC Power Xfmr & Switchgear
- Charging Supply
- Modulator
- Output Pulse Transformer
- 10 MW Klystron
- Local/Remote controls & monitoring, interlocks, protection
- Racks, Interface w/ Controls, LLRF, Vacuum, monitoring

Note: Assume LLRF variant for RT cavities
051606 HLRF RDR Status-R1

3

# 10 MW Station Cost Model

- Components procured or built to specification<sup>1</sup>
  - Commercially available off-the-shelf
    - HV AC transformer, switchgear
    - Charging supply rack modules
  - Build to spec/print
    - Modulator, HV cables, Pulse Xfmr
  - Build to spec
    - Klystron, klystron magnet
  - Procure from Systems Integrator house
    - PLC controller, safety interlocks, controls interface
    - Integrated tested rack assembly

1. See Neubauer/Larsen presentation DESY 051106

### **S-Band Stations**

- Two versions, SLED and Normal
  - 5045 tube manufacturing, costs well established – procure from SLAC
  - Differences in distribution system for energy doubling based on SLAC model
  - Modulator will assume solid state Induction Stack (designs operational, cost estimates available)
  - Standard support systems well developed.

# Damping Rings 650 MHz RF

- DR Area group model contains 8 klystrons per ring, each driving 32 cavities (or 28 w/ one station off), 24 stations total
- PEPII and KEKB models
  - Models well characterized, costs will be extrapolated from existing commercial klystrons, semi-commercial HV supplies.

# **Related Systems**

- Controls & LLRF
  - In progress, models in development based on recent systems – J. Carwardine et al
- Vacuum
  - Klystron vacuum understood; no information yet on per-station cryo vacuum; commercial or custom commercial design – Contact TBD
- Racks
  - Anticipate 6-8 racks, some instrumentation racks & possibly all water cooled; commercially available as build to spec. – Contact R. Downing

WBS Status – Cost Methodology

- Draft top level WBS for all Areas developed
  - Need resource to develop next level of detail, begin adding cost data
- Costs will be developed in Excel format
  - Establish, document all cost basis, database for cost books
  - Enter into master top-level WBS sheets

# Working Decisions

- HLRF working decisions are documented
  - Tunnel size \*Station Footprint \*Penetrations– Modulator Power Source Xfmr \*Charging supply input voltage \*Rack Power \*Rack Subsystem – DC Emergency power \*Separate Klystron oil tank
    Klystron windows orientation \*Integrated WG and Cryomodule \*Cooling water & air loads.
- Changes affecting cost models will require agreement from all parties
  - Probably unimportant for cost accuracy required for Vancouver – Stick to BCD baselines and established understandings with tunnel, civil, accelerator POC's

# Additional Cost Study Briefings

- 5-10 min each on Cost Status, plans, resources
  - C. Jensen-- Modulators
  - S. Fukuda-- Klystrons & Distribution, DR's
  - M. Neubauer-- Klystrons & Distribution
  - J. Carwardine/B. Chase-- Controls & LLRF