

26 05 13 Medium-Voltage Cables	Crew	Daily Output	Labor Hours	Unit	Bare Mat.	Bare Labor	Bare Equip.	Bare Total	Total Incl. O&P
SHIELDED CABLE Splicing & terminations not included									
35 kV, grounded neutral, #1/0	2 Elec	3.40	4.706	C.L.F.	410	251		661	830
2/0	2 Elec	3.20	5	C.L.F.	485	266		751	935
4/0	2 Elec	2.80	5.714	C.L.F.	610	305		915	1,125
250 kcmil	3 Elec	3.90	6.154	C.L.F.	715	325		1,040	1,275
350 kcmil	3 Elec	3.30	7.273	C.L.F.	860	385		1,245	1,525
500 kcmil	3 Elec	3	8	C.L.F.	1,025	425		1,450	1,750
26 05 13 Medium-Voltage Cables									
CABLE TERMINATIONS, 5 kV to 35 kV									
Indoor, insulation diameter range .525" to 1.025"									
35 kV	1 Elec	5.60	1.429	Ea.	148	76		224	277
insulation diameter range .975" to 1.570"									
35 kV	1 Elec	5.30	1.509	Ea.	183	80.50		263.50	320
insulation diameter range 1.540" to 1.900"									
35 kV	1 Elec	5	1.600	Ea.	241	85		326	390