

# GDE Summary

A. Yamamoto, N. Walker, and Marc Ross  
ILC-GDE Project Managers

*KILC12-Closing Plenary , 12-04-26*



# Outline

- **GDE Technical update/progress, since LCWS11, Granada**
  - SCRF and Beam Test Facilities
    - Gradient yield, after Sept. 2011
    - Test facilities: FLASH, STF/QB, NML, and ATF,
    - Industrialization studies in contracts w/ RI, AES, MHI, Hitachi, Toshiba, and BN
  - CFS
    - Progress in two categories: Flat and Mountainous layout
    - Detector hall review
  - Accelerator System
    - Damping ring design
    - Target R&D
    - ML lattice and parameters
- **Technical Design Report**
  - Progress in writing and plan to complete it by Dec. 2012
- **Technical studies beyond TDR**
  - R&D: such as high-gradient, industrialization, target, and ...
  - Study: to be prepared for variety of energy requirements including upgrade up to 1 TeV



# Plan and Progress in SCRF/ATF

Year	07	2008	2009	2010	2011	2012
Phase	TDP-1			TDP-2		
Cavity Gradient in v. test to reach 35 MV/m	→ Yield 50%			→ Yield 90%		
Cavity-string to reach 31.5 MV/m, with one-cryomodule		Global effort for string assembly and test (DESY, FNAL, INFN, KEK)			We are here	
System Test with beam acceleration		FLASH (DESY) , NML (FNAL) STF2/ ATF (KEK)				
Preparation for Industrialization				Production Technology R&D		
Communication with industry:	2011-2012: Mass production studies in contract					




# Progress Integrated in Cavity Gradient Yield

Updated, Sept., 2011



Electropolished 9-cell cavities  
/KEK (combined) up-to-second successful test of  
cavities from established vendors

Plot courtesy  
Camille Ginsburg of FNAL






# Progress Integrated in Cavity Gradient Yield

Updated, April., 24, 2012




**Electropolished 9-cell cavities  
/KEK (combined) up-to-second successful test of  
cavities from established vendors**

Plot courtesy  
Camille Ginsburg of FNAL






# Yearly Progress in Cavity Gradient Yield as of April 24, 2012





# Yearly Progress in Cavity Gradient Yield as of April 24, 2012



# System Tests

## FLASH (DESY)


- TDP focus
- 7 CM  $\rightarrow$  1.2 GeV beam
- photon user facility

“9mA experiment”  
achieved  $\sim 1800$  bunches at  
9mA in 09.2009

$\Delta E/E_{\text{RMS}} \sim 0.5\%$  (@ 0.8 GeV)  
 $\sim 0.1\%$  within pulse

## NML (FNAL)

- Under construction
- Up to 6 cryomodules
- Operation: end 2012
- (3 CM)



## STF , ATF (KEK)

- “Quantum Beam” experiment 2011
- 1 CM with beam 2013
- (2 CM 2015)





Full  
systems  
integration  
testing






# FLASH 9mA Studies: beam operation close to cavity gradient limits (4.5mA/800us bunch trains)

Tailored cavity Loaded-Qs to cancel beam-loading induced gradient tilts



Operation at 380MeV on ACC67 (13 cavities)






The limiting cavity is within 5% of quench

- Flattened individual gradients to **<<1% p-p**
- Several cavities within 10% of quench
- 'Crash test': very rapid recovery of 800us / 4.5mA after beam trip
- Ramped up current from ~zero to 4.5mA with ACC67 gradients approaching quench
- 'Cavity gradient limiter' to dynamically prevent quenching without turning off the rf



# 9mA Studies: evaluating rf power overhead requirements (4.5mA/800us bunch trains)

- Klystron high voltage was reduced from 108KV to 86.5KV so that the rf output just saturated during the fill
- The required beam-on power ended up being ~7% below saturation





# STF Quantum-Beam experiment

KEK-STF

Quantum-Beam Accelerator

High-flux X-ray by Inverse-Compton scattering  
10mA electron beam (40MeV, 1 m s, 5 H z)  
4-mirror laser resonator cavity  
head-on collision with beam



photocathode RFgun

Capture cryomodule ( 2 SC cavities )

Goal : 10 mA



collision point  
(Laser, electron beam)

Target:  $1.3 \times 10^{10}$  photons/sec 1%bandwidth

2012. Feb : cool-down started,  
April : beam acceleration








# STF Quantum-Beam experiment

KEK-STF


Quantum-Beam Accelerator

Beam acceleration (40 MV) and  
transport for **1 ms**, **successful** !  
April, 2012




Target:  $1.3 \times 10^{10}$  photons/sec 1%bandwidth

2012. Feb : cool-down started,  
April : beam acceleration





# Beam Acceleration Test Plan at FNAL







# CM-2 Cold Test Coming Soon going to NML, today!!

- **Assembly is largely complete**
  - Leak checking, some wiring remains
- **Expect CM-2 to arrive at NML mid-April**
  - After CM-1 is removed and transported
  - Then bring CM-2 to NML
  - Expect  $> 30$  MV/m on average (7 cavities recorded  $> 35$  MV/m in vertical test)







# Accelerator System

- **BDS**
  - ATF recovery after “earth quake” in 2011
- **Damping Ring**
- **e+ source**
- **RTML and ML beam dynamics**



# ATF2 status after the recovery of the 3.11 earthquake

## Commissioning of 30 deg mode



$$\sigma_y^* = 201 \pm 4.4 \text{ (stat.) nm}$$

$$M_{\text{meas}} = 0.429 \pm 0.012 \text{ (stat.)}$$

From 10 stable consecutive scans  
30 deg, Feb 17, 2012  
(10 ( 10  $\beta_x^*$  x 10  $\beta_y^*$  optics )

largest  $M_{\text{meas}} = 0.522 \pm 0.042 \leftrightarrow \sigma_{y,\text{meas}} \sim 165 \text{ nm}$

2/17: 30 deg	$M$	$\Delta M$	$\sigma_y^*$	$\Delta \sigma_y^*$	avg $E_{\text{sig}} / \text{ICT}$ [GeV / 10 <sup>9</sup> e]
18:07	0.426	0.039	194.98	6.21	2.359
18:09	0.390	0.043	206.63	6.48	2.403
18:12	0.433	0.036	192.55	5.73	2.269
18:14	0.439	0.034	190.82	5.49	2.290
18:16	0.437	0.038	191.29	6.16	2.303
18:18	0.460	0.040	183.86	6.78	2.267
18:20	0.444	0.035	189.20	5.77	2.450
18:22	0.39	0.042	206.67	6.902	2.292
18:24	0.453	0.037	186.17	6.203	2.356
18:26	0.389	0.042	207.029	6.205	2.360


- $S/N : 4 - 5$
- Signal jitter  $\sim 22\%$
- BG fluc.  $\sim 15\%$
- stable beam current






# Damping Rings I


- DTC04 Lattice Evaluations
- Magnet Design & Layout Review
- Costing Meeting



J. Conway  
C. Spencer



DA with  
misalignments  
& field errors



Parameter	RMS
BPM – Differential resolution	2 $\mu\text{m}$
BPM – Absolute resolution	100 $\mu\text{m}$
BPM – Tilt	10 mrad
BPM button – Gain variation	1%
Quads + Sexts – Offset (H+V)	50 $\mu\text{m}$
Quads – Tilt	100 $\mu\text{rad}$
Dipole – Roll	100 $\mu\text{rad}$
Wiggler – Offset (V only)	200 $\mu\text{m}$
Wiggler - Roll	200 $\mu\text{rad}$


Ring  
Tolerances  
Evaluation  
for  $\epsilon_y = 2 \text{ pm}$   
using current  
LET Algos




# Damping Rings II

Pivi Talk

- EC Mitigations & Status
  - Vacuum System Design/Costing
    - SuperKEKB VCs in production with similar designs to ILC DR
- SuperKEKB Dipole Chamber*





DR Wiggler chamber concept with thermal spray clearing electrode – 1 VC for each wiggler pair.





## EC Build-up in Quads in Wiggler Straight

Electron cloud density ( $e/m^3$ )

Electron energies (eV)





Crittenden



+400V


EC Suppression by Wiggler Electrode

+100V






# New General Layout for Remote Target Replacement, Jia IHEP



# Water cooling and room temperature greatly simplifies the design



- Device sits in the vacuum
- All power and cooling connections move to the rim
  - Coils are kapton wound, hollow copper, water cooled
  - Plates are OFHC copper with water cooling pipes soldered in
  - Only metal in the high radiation areas
- Plates and coils stack and bolt together

**New OMD design,,  
Jeff Gronberg, LLNL**



# RTML & ML Beam Dynamics

- **RTML design** (A.Vivoli, N.Solyak, V.Kapin, Fermilab)
- **Main Linac lattice design** (V.Kapin, N.Solyak, Fermilab)
  - **(Almost) Complete.**
  - **No Problem**
- Comments to Main Linac Design from Beam Dynamics (K.Kubo KEK)
  - **Confirm present lattice choice is the best.**
  - **Remind requirements from beam dynamics.**
  - **No Objection**
- Status of RTML writing for TDR (prepared by N.Solyak but could not be presented)
  - **No Problem**





# ILC-TDR: Baseline Parameters

In TDR Part-2, Chapter 2, drafted by N. Walker

Centre-of-mass energy	$E_{CM}$	GeV	200	230	250	350	500
Luminosity pulse repetition rate		Hz	5	5	5	5	5
Positron production mode			10 Hz	10 Hz	10 Hz	nom.	nom.
Bunch population	$N$	$\times 10^{10}$	2	2	2	2	2
Number of bunches	$n_b$		1312	1312	1312	1312	1312
Linac bunch interval	$\Delta t_b$	ns	554	554	554	554	554
RMS bunch length	$\sigma_z$	$\mu m$	300	300	300	300	300
Normalized horizontal emittance at IP	$\gamma \epsilon_x$	$\mu m$	10	10	10	10	10
Normalized vertical emittance at IP	$\gamma \epsilon_y$	nm	35	35	35	35	35
Horizontal beta function at IP	$\beta_x^*$	mm	16	14	13	16	11
Horizontal beta function at IP	$\beta_y^*$	mm	0.34	0.38	0.41	0.34	0.48
RMS horizontal beam size at IP	$\sigma_x^*$	nm	904	789	729	684	474
RMS horizontal beam size at IP	$\sigma_y^*$	nm	7.8	7.7	7.7	5.9	5.9
Vertical disruption parameter	$D_y$		24.3	24.5	24.5	24.3	24.6
Fractional RMS energy loss to beamstrahlung	$\delta_{BS}$	%	0.65	0.83	0.97	1.9	4.5
Luminosity	$L$	$\times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$	0.56	0.67	0.75	1.0	1.8
Fraction of $L$ in top 1% $E_{CM}$	$L_{0.01}$	%	91	89	87	77	58
Electron polarisation	$P_-$	%	80	80	80	80	80
Positron polarisation	$P_+$	%	30	30	30	30	30
Electron relative energy spread at IP	$\Delta p/p$	%	0.20	0.19	0.19	0.16	0.13
Positron relative energy spread at IP	$\Delta p/p$	%	0.19	0.17	0.15	0.10	0.07




# Progress in CFS


- **Design and Costing for TDR nearly finished**
  - Asia and Americas
  - (Europe design / cost due in late May)
- **Completely new, more mature design than RDR**
- **Excellent Cost performance / Saving**
- **Adaptation to Japanese candidate sites started**
- **Draft TDR content reviewed**



# Detector Hall CFS Review



- **Review Questions:**
  - Criteria understood?
  - Design satisfy the criteria?
  - What are the cost-drivers?
  - What are the outstanding issues?
- **Presentations:**
  - **Alignment** requirements (special tunnels)
  - Underground **Assembly** schemes
  - **Cryogenic** systems
  - Cost roll-up
- **Report to be written.**







# Technical Design Report

2007

2011

2013\*



Reference Design Report

ILC Technical Progress Report  
("interim report")



AD&I

~250 pages

## Technical Design Report



TDR Part I:  
R&D




TDR Part II:  
Baseline  
Reference  
Report

The two parts are  
inherently linked



Executive  
Summary



Outreach  
Document

~300 pages

~50 pages

~25 pages


\* end of 2012 – formal publication early 2013



# Publication and Review

First-draft sections	<b>* 23 April *</b>
Complete edited draft	22 October (ILCWS 12)
Final draft (for PAC)	15 November
PAC review	15-16 December

Formal publication at  
**Lepton Photon Conf.**  
(SF, June 2013)



Expect international  
reviews:  
Both technical and cost  
(Q1-22 2013)



# Communication with Companies

Further study in contract in 2011-2012

	Date	Company	Place	Technical subject
1	2/8, 2011	<b>Hitachi</b>	Tokyo (JP)	Cavity/Cryomodule
2	2/8	<b>Toshiba</b>	Yokohama (JP)	Cavity/Cryomodule, SCM
3	2/9	<b>MHI</b>	Kobe (JP)	Cavity / Cryomodule
4	2/9	Tokyo Denkai	Tokyo (JP)	Material (Nb)
5	2/18	OTIC	NingXia (CN)	Material (Nb, NbTi, Ti)
6	(3/3), 9/14	Zanon	Via Vicenza (IT)	Cavity/Cryomodule
7	3/4,	<b>RI</b>	Koeln (DE)	Cavity
8	(3/14), 4/8	<b>AES</b>	Medford, NY (US)	Cavity
9	(3/15), 4/7	Niowave	Lansing, MI (US)	Cavity/Cryomodule
10	4/6	PAVAC	Vancouver (CA)	Cavity
11	4/25	ATI Wah-Chang	Albany, OR (US)	Material (Nb, Nb-Ti, Ti)
12	4/27	Plansee	Ruetz (AS)	Material (Nb, Nb-Ti, Ti)
13	5/24	SDMS	Sr. Romans (FR)	Cavity
14	7/6	Heraeus	Hanau (DE)	Material (Nb, Nb-Ti, Ti)
15	10/18	<b>Babcock-Noell</b>	Wurzburg (DE)	CM assembly study
16	11/14, 11/16	SST	Maisach (DE)	Electron Beam Welder



# Mass-Production Studies

in contracts

	Company	Mass production model	Contract funded/hosted by
Cavity	RI	100% (50%)	DESY
	AES	20 %	DOE/Fermilab
	MHI	20, 50, 100%	KEK
Quadrupole	Toshiba	100 %	KEK
CM and assembly	Hitachi	20, 50, 100%	KEK
	AES	25%	DOE/Fermilab
CM assembly	BN	100, 33 %	CERN


In parallel, EXFEL experience kindly informed by DESY, INDFN, CES/Saclay



# Technical Development beyond TDR

- **SCRF**
  - Higher Gradient in cavity toward 1 TeV
  - Industrialization and cost-saving technology
- **CFS**
  - Geological survey and/or study
  - Civil engineering study
- **Accelerator Systems**
  - e<sup>+</sup> source Target R&D, and undulator R&D
  - Preparing to be ready for 250 GeV ~1 TeV LC

# SCRF Cavity Gradient Progress



- Continued progress in SRF gradient : breakthrough of 45 MV/m in 1-cell, ~60 MV/m record; 45 MV/m in 9-cell
- GDE began in 2005: produce a design for ILC and coordinate worldwide R&D efforts
- New SRF Test Facilities in operation: STF at KEK and NML at Fermilab
- Upgrade of CEBAF to 12 GeV underway at Jefferson Lab (80 cavities)
- FLASH operation and construction of European XFEL underway (640 cavities)



# A 2-cell cavity w/ end-G reached $> 50 \text{ MV/m}$

## Target

\* Accelerate to 10 MeV

## Require

\*  $15 \text{ MV/m}$  / cavity at CW


Cavity : 3 x 2-cell cavities

Slide-Jack tuner and piezo tuner

5 coaxial HOM couplers  
for one cavity

Input coupler  
(double feed)  
 $167 \text{ kW/coupler}$


liq. He



To be installed in  
KEK cERL injection beam line

ERL 2cell Cavity #2 5th. V.T. Mar.06, 2012



[With Five HOM Pickup Antennas; Type-II(male pin)]  
EP-II( $5 \mu\text{m}$ ), Water flow(1.5hrs), FM\_20 2%(50C,30min),  
HPR(8MPa, ~6hrs), Dry overnight in HPR room







# *Cavity Fabrication at KEK is coming*





# Summary

- **ILC accelerator technology**
  - SCRF cavity gradient progressing toward 35 MV/m,
  - Beam test facility functioning to demonstrate the ILC accelerator requirements,
- **Technical Design Report (TDR)**
  - Contents being settled w/ flat and mountainous cases,
  - Draft being submitted by each author,
  - Final draft due LCWS-12, Oct., 2012
- **Further work beyond TDR**
  - Advanced R&D for 1 TeV upgrade capability,
  - Further study to be ready for various energy operation
- *Many thanks for the KILC12 organizer*



Ch	Sect Heading	Pages	Primary
	<b>PART I: ILC R&amp;D in the Technical Design Phase</b>	<b>280</b>	
1	Introduction	10	<a href="#">Walker</a>
2	Evolution of the ILC design in the Technical Design Pha	10	<a href="#">Walker</a>
3	Superconducting RF technology	95	<a href="#">Yamomoto</a>
4	Beam Test Facilities	70	<a href="#">[Editor]</a>
5	Accelerator Systems R&D	70	<a href="#">[Editor]</a>
6	Conventional Facilities and Siting Studies	10	<a href="#">Kuckler</a>
7	Post-TDR R&D	10	<a href="#">Ross</a>
8	Summary	5	<a href="#">Walker</a>
	<b>Part II: The ILC Baseline Reference</b>	<b>338</b>	
1	Introduction and overview	5	<a href="#">Paterson</a>
2	General parameters and layout	15	<a href="#">[Editor]</a>
3	SCRF Main Linacs	50	<a href="#">Yamomoto</a>
4	Electron source	10	<a href="#">Sheppard</a>
5	Positron source	20	<a href="#">Gai</a>
6	Damping Rings	25	<a href="#">Guiducci</a>
7	RTML	20	<a href="#">Solyak</a>
8	Beam Delivery System and MDI	25	<a href="#">Seryi</a>
9	Global Technical Systems	26	
10	Commissioning, Operations, and Availability	15	<a href="#">Ross</a>
11	Conventional Facilities and Siting	42	<a href="#">Kuchler</a>
12	Upgrade options	20	<a href="#">[Editor]</a>
13	Scope of post-TDR engineering (tech. risk assessment)	20	<a href="#">Ross</a>
14	Project Implementation Planning	20	<a href="#">Harrison</a>
15	Cost and Schedule	20	<a href="#">Dugan</a>
16	Summary	5	<a href="#">Walker</a>

# Logistics

There are too many chapters to spend 3hrs on each, so we will need to prioritize

Which authors are going to the meeting?



# Communication with Industry

## SC Cavity Manufacturers

	Date	Company	Place	Technical subject
1	2/8, 2011	Hitachi	Tokyo (JP)	Cavity/Cryomodule
2	2/8	Toshiba	Yokohana (JP)	Cavity/Cryomodule, SCM
3	2/9	MHI	Kobe (JP)	Cavity / Cryomodule
4	2/9	Tokyo Denkai	Tokyo (JP)	Material (Nb)
5	2/18	OTIC	NingXia (CN)	Material (Nb, NbTi, Ti)
6	(3/3), 9/14	Zanon	Via Vicenza (IT)	Cavity/Cryomodule
7	3/4,	RI	Koeln (DE)	Cavity
8	(3/14), 4/8	AES	Medford, NY (US)	Cavity
9	(3/15), 4/7	Niowave	Lansing, MI (US)	Cavity/Cryomodule
10	4/6	PAVAC	Vancouver (CA)	Cavity
11	4/25	ATI Wah-Chang	Albany, OR (US)	Material (Nb, Nb-Ti, Ti)
12	4/27	Plansee	Ruette (AS)	Material (Nb, Nb-Ti, Ti)
13	5/24	SDMS	Sr. Romans (FR)	Cavity
14	7/6	Heraeus	Hanau (DE)	Material (Nb, Nb-Ti, Ti)
15	10/18	Babcock-Noell	Wurzburg (DE)	CM assembly study
16	11/11	SST	Maisach (DE)	Electron Beam Welder

- **By Marc and Vic**
  - Design progress in FLAT and Mountaineous category
- **To be provided by Marc and Toshiaki**
  - Detector hall review



# TDR Deadlines

First-draft sections	* 22 April, - 4 days*
Complete edited draft	22 October (ILCWS 12)
Final draft (for PAC)	15 November
PAC review	13-14 December

Drop-dead deadline

203 Days (29 Weeks) .... AND COUNTING !!  
~ 20% submission, as of 26, April