


ILD in Mountain Site Hall


Karsten Buesser

09.03.2012


MDI CTG Webex



ILD in Maintenance Region (non-mountain site)



CMS Assembly




ILD Assembly

- CMS-type assembly for non-mountain sites:
 - Pre-assemble and test ILD components on surface as far as possible
 - Lower five yoke rings with pre-installed detector components
 - About one year of assembly underground
- Non-CMS-type assembly for mountain sites:
 - Part sizes are limited by access tunnel
 - Yoke rings need to be built underground
 - Sub-detectors mostly installed underground
 - Need more time (~3y) and more underground space


ILD Design

- Assumption: basic detector model will not change for mountain sites




Yoke Assembly

- Start with central ring on platform
- Space needed for: tools, scaffolding, surveying equipment




Yoke Assembly

- 200t crane coverage needed




Yoke Assembly

- Tooling needs still under study




Yoke Assembly

- Tolerances of the ring segments need to be better than 1 mm
- Laser surveying needed during full assembly
- Tools needed
 - 200t crane
 - chain hoists
 - tailored tools: beams etc.
 - hydraulics
 - surveyors
- Time estimate: 60 working days per ring




Coil Installation

- Coil can only be transported without its ancillaries (cold box, chimney)
- Functional test needs to be done underground after installation into central barrel yoke ring
 - very low fields, yoke will not be ready by then
 - test field mapping equipment
 - Takes ~4 months (incl. cool-down and warm-up)
- Final high field test when yoke is ready
 - incl. field map measurements




R. Stromhagen


AHCAL Installation



AHCAL Installation




AHCAL/ECAL Installation




Calorimeter Installation



- Special tooling needed:
support cradle, directly mounted to the coil
- Crane coverage
- Surveying equipment
- Time estimate for AHCAL barrel:
 - 180 working days
- ECAL barrel:
 - probably less
- Endcaps: ?




K. Gadov




TPC Installation





Japanese Hall Design (Status: 01/2012)


Y. Sugimoto



- Probably not enough space for detector assembly and regular maintenance


Maintenance Position (DESY Study)

- Changed hall model to enlarge alcoves in parking position (47m lateral space)




Larger Parking Position (DESY Study)

- Lateral space is needed to open the detector, remove QD0 magnets, inner detector, TPC
- Alternative: rotate the detector by 90 deg before opening
 - Almost impossible
 - need to disconnect cable chains and possibly cryo lines
 - warm-up the coil




Underground Construction Space (DESY Study)

- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (53m lateral space)
 - Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- Crane coverage: 200t in main hall, 100t in alcoves
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground




Underground Construction Space (DESY Study)

- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (53m lateral space)
 - Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- Crane coverage: 200t in main hall, 100t in alcoves
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground




Underground Construction Space (DESY Study)


- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (53m lateral space)
 - Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- Crane coverage: 200t in main hall, 100t in alcoves
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground




全体平面図: Plan view of EXP hall



ガレージ部断面(ILD) : in ILD Garage




ガレージ部断面(SiD) : in SiD Garage



CMS Surface Assembly Hall



CMS Surface Assembly Hall



CMS Surface Assembly Hall



Conclusion

- First attempt to define an assembly sequence for ILD in the mountain sites
- 3y+ underground assembly time seems feasible
 - Requires optimised underground conditions
- Current hall design under study with enlarged alcoves and longer hall

- Need to optimise the whole system detector/machine/hall w.r.t. assembly time schedule and cost!
- Need to understand trade-offs: space vs time