



ECAL End-Caps - structure and assembly


Denis Grondin

13.04.2012

ILD Regional Integration meeting @ LAL

PRELIMINARY

Preliminary reminders




ECAL Fully equipped End-cap weight : ~ 25.5 T

Current structure of End-Caps


Modular structure

2 End-Caps

Total of 24 modules - 4 x 3 modules each







Up to now, ECAL End-Cap is fastened on HCAL End-Cap inner face with rails




- Both Ecal End-Caps are to be fastened onto HCAL End-caps, hanging from it by rails
- Each End-Cap will be divided in 4 quarters composed of 3 modules each (12 modules in total).
- This subdivision is due to the fact that physics cracks are prevented with this geometry. Relative ease of implementation.
- Cooling system to be install on rear face prior to insertion.
- Symmetry of onboard services, dissymmetry of outboard ones.
- The insertion tooling will have to allow the handling and positioning of ~6,5 t quarters in the alcoves of the cavern (Spaces for detector assembly/services).

4 solutions to move End-Caps down into the cavern

Assembly on surface		Assembly in the pit (favorite)	
Full End-Cap on HCAL	Full End-Cap only <i>wrong</i> option/ final insertion	2x4 Quarters	2x12 Modules
 <ul style="list-style-type: none"> Mechanical - Interconnection done - Alignment done - Services connected (local) - Modules fully equipped ? - Sub detectors (slabs) are fully commissioned ? - Once below they can be connected to the outboard services 	 <p>Ex.: Lowering of one ATLAS muon small wheel into the cavern.</p>		 <p>pre-assembly of modules on surface</p>


Conception of specific handling and positioning tools

Rails and fastening system – Ex. Lifting beam of ALICE




Sliding with rollers
 **pushed on glide strips**

Platform supporting insertion tooling
 Positioning of ECAL quarters in front of HCAL End-Cap
 → **lateral space** needed for sliding

insertion tooling with orientation tuning, alignment and fastening systems
 Insertion of modules and/or quarters




Impact of alignment constraints on mounting
 Rails profile and position still to be validated !!!




Synoptic for integration

3 major options for integration


Assembly
on surface
**12 Modules
by quarters**



Assembly
On HCAL
12 Modules



Assembly
On HCAL
End-Cap
4 Quarters



ECAL End-Caps: weight and volume

Total Weight
1 EC

Fully equipped with slabs

25426 kg

ECAL End-cap D=4188		Dimensions							Rails	Services			
		Nb of modules	Volume / quarter			Volume / modules			Weight	Orientation	Weight	Weight	
			L (mm) _{/Y}	l (mm) _{/X}	H (mm) _{/Z}	L (mm) _{/Y}	l (mm) _{/X}	H (mm) _{/Z}	(kg)		(kg)	(kg)	
ECAL End-Cap (1)		12	4188	4188	185					25208		162	56
1.1	Quarter 1	3	2492	1695	185					6302	Horizontal / left	57	13
	Module 1.1					1828.85 (-563.4)	563.4	185	1585	Horizontal / left	8	4.5	
	Module 1.2					2394.25 (-563.4)	563.4	185	2164	Horizontal / left	22	4.5	
	Module 1.3					2492.2	563.4	185	2553	Horizontal / left	27	4	
1.2	Quarter 2	3	1695	2492	185					6302	Vertical / down	24	15
	Module 2.1					1828.85 (-563.4)	563.4	185	1585	Vertical / down	6	5	
	Module 2.2					2394.25 (-563.5)	563.4	185	2164	Vertical / down	9	5	
	Module 2.3					2492.2	563.4	185	2553	Vertical / down	9	5	
1.3	Quarter 3	3	2492	1695	185					6302	Horizontal / right	57	13
	Module 3.1					1828.85 (-563.4)	563.4	185	1585	Horizontal / right	8	4.5	
	Module 3.2					2394.25 (-563.5)	563.4	185	2164	Horizontal / right	22	4.5	
	Module 3.3					2492.2	563.4	185	2553	Horizontal / right	27	4	
1.4	Quarter 4	3	1695	2492	185					6302	Vertical / up	24	15
	Module 4.1					1828.85 (-563.4)	563.4	185	1585	Vertical / up	6	5	
	Module 4.2					2394.25 (-563.5)	563.4	185	2164	Vertical / up	9	5	
	Module 4.3					2492.2	563.4	185	2553	Vertical / up	9	5	

$$M_{\text{module}} = L \text{ (mm)} \times l_{\text{ext alveolus}} \text{ (mm)} \times \text{Nb colonne} \times 1.8184 \times 10^{-3} + M_{\text{rails}} + M_{\text{services}}$$

$$M_{\text{rails}} \sim 0.005 \text{ kg/mm}$$

$$M_{\text{services}} = \text{cooling exchanger CU} + \text{piping Stainless Steel without cabling !}$$

$$M_{\text{external services}} = 160 \text{ kg around EC / trough detectors (Stainless Steel)}$$

Assembly phase (1)

Assembly of modules and quarters in the assembly hall


1. Modules equipment and test

to be refined

Task	Description / constraint	tooling	FTE	Time	Assembly area	Comment
1	Handling of 1 (over 24) module.	Crane, table	2 T	1 week	20m ²	
2	Insertion of 45 slabs per modules. 1 Slab =10 to 25 kg alignment within alveoli = 500 μm over 2.5 m		2 T			
3	Electrical connections up to LDA boards		2 T			
4	Cooling blocs (3) up to Module edge, over LDA up to main distribution line position		2 T			
5	Tests (electronic and signal)		2 T	1 week		To be done in parallel

Weight per module: ~1.6 t to 2.6 t

Same processes repeated 4 times per group of 3 modules (equipment of 1 End-cap)




Assembly phase (2)

Assembly of modules and quarters in the assembly hall

2. Quarters assembly on mounting support frame


to be refined

Task	Description / constraint	tooling	FTE	Time	Assembly area	Comment
1	Handling of 3 modules. 1.6 t to 2.6 t on quarter support frame	crane, mounting jig and quarter support frame	2 T	1 week	25m ²	
2	Mechanical interconnection of the modules to complete one quarter					
3	Cooling pipes connections over the 3 modules.	Mounting jig for cooling pipes				
4	Electrical connections up to quarter edge	Mounting jig for wiring				
5	alignment of rails with template	Mounting jig for rails				
Total weight : ~ 6,5 t / quarter						



The assembly in quarter (2 ≠ configurations) will depend of:

- Integration process
- Maintenance scenario





ECAL General Cooling Integration

Specific need due to Leakless system

- Minimal height between cooling station (ground) and beam axis (h): 11 m
- Maximal distance between beam axis and cooling station (l) : 30 m
- Congestion of tubing + measurement between cooling station and detector : 0.5m²
- Separation wall between the cooling station and the pit (protection / magnetic field and radiation).
- Dimensions of the cooling station: length=> 3 m, width=> 2 m, height 2 m.






Overall thermalization foreseen

- Fluids Circulation + cabling
 - => passages for pipes outwardly of the detector
 - => Free space for connections
 - Step1: onboard pipes & cables connection
 - Step2: pipes & cables connection trough detectors






Cooling lines for ECAL
End-cap and Barrel

ECAL End-Cap Local Cooling Integration

Operation		Time /Unit	ETP	Installation of cooling pipes on modules/quarters – under rails	Time /EC	ETP
Integration on each of the 12 modules ...for cooling and services	 <p>Time Included in Assembly phase 1</p>	1 day	2		6 days (surface)	2 + 2 //
Quarter cooling integration	 <p>Time Included in Assembly phase 2</p>	1 day	2		2 days (cavern)	2 + 2 //
						




General cooling connection time to add ...

ECAL End-Cap General Cooling Integration



Task Description	FTE	TIME
Connection of leakless system to modules /quarters (pipes incoming by lower side of End-cap)	4	2 weeks
Full connection of 1 End-Cap: general EC integration + <u>pipng trough detectors to cooling station</u>	4	1 month

ECAL Cooling Integration – Impact / HCAL



Status: the detectors must be independents (thermal aspect).
 Reality => low power (3Kw) spread over large surfaces associated with a small space between the detectors (3 cm) => influence of air via important conduction => flux between detectors certain
 => Real T° of detector impossible to predict without global modelling;
 so no possibility to know if our detector will cool or heat detectors around


Conclusion
 Cooling front –end to remove the power of ECAL
 Low temperature gradient -> cooling system suitable for HCAL ?
 → extra thermal insulation / HCAL ? (no flux exchange with other detectors)

ECAL End-Caps: integration area

Construction sites dedicated to end caps (installation & cabling): alcoves n° 2 & 3

- Assembly spaces in the alcoves: ok
- The crane capacity in the alcoves (5t) is too small. The ECAL endcap quarters have a mass of **6,5t** and we need to be able to move them with a crane in the alcoves for insertion on HCAL End-Cap. 10t crane needed (EC+tooling)
- Alternative: cradle, but it has to be aligned (*raised*) to the proper height...

From Yasuhiro Sugimoto
Update April, 5th



Needed space near detector for Integration & maintenance

Minimum width = 7 m/beam line for integration
 Storage area : 1 quarter=> 10 m² / 12 modules=> 50 m²
 Assembly area: 25 m² / quarter - 20 m² / module
 Insertion on HCAL End-Cap on each side: per full quarters

PRELIMINARY

ECAL End-Caps: integration overview < 5 months / EC

N°	Major Tasks Description for 1 End-Cap <i>(Preliminary studies of the Ecal End-Cap assembly)</i>	FTE	TIME	Ressource name
1	ECAL End-Cap Base Moving Unit / Base Moving Frame / Quarter Mounting Frame Insertion tool, transport , installation, alignment	4	~ 1 month	crane 1 , crane 2
2 //	Rails: fixing (female parts) on the rear face of the HCAL End-Caps: Positioning / Alignment / Checking	3	~ 1 month	Specific tooling TBD
3	Quarter 1 (3 modules) assembly in the assembly hall, fully equipped, tested and aligned	6 //	4 weeks	quarter support frame 1, crane 1
	3 Modules Equipment and test (assembly of 1 of the 3modules in the assembly hall)	2	1 week x 3	
	Tests (electronic and signal) of the 3 constitutive modules	2 //	1 week x 3	
	Quarter assembly on mounting support frame	2	1 week	
	Transportation of quarter in mountain site (or modules only / space available for tooling approach on both sides of detector in cavern)	4	2 days	
4 //	Quarter 2 (3 modules) assembly in the assembly hall, fully equipped, tested and aligned ...	6 //	4 weeks	quarter support frame 2, crane 1
5	Quarter 3 (3 modules) assembly in the assembly hall, fully equipped, tested and aligned ...	6 //	4 weeks	quarter support frame 1, crane 1
6 //	Quarter 4 (3 modules) assembly in the assembly hall, fully equipped, tested and aligned ...	6 //	4 weeks	quarter support frame 2, crane 1
7	Integration of 1 Ecal End-Cap on HCAL End-Cap	4	1 month	crane 1 , crane 2 quarter support & MF
	Insertion of 4 Ecal End-Cap <u>quarters</u> on HCAL End-Cap (quarter on its support frame) Positioning of the quarter on specific sliding tool / Pre-alignment operations / Insertion	4	2 days x 4	crane 1 , crane 2 quarter support & MF
8	1 ECAL End-Cap general cooling integration	4	2 weeks	
9	Remove ECAL End-Cap Mounting Frame / Base Moving Frame / Quarter Mounting Frame...	4	1 week	crane 1 , crane 2

Main issue /mechanical quarter behavior during insertion on HCAL: Quarter Mounting Frame (To Be Studied)

In case of cavern : this is done in assembly hall Mountain site (in the cavern)