

ILD in Mountain Site Hall


Karsten Buesser


12.04.2012

ILD Regional Integration Meeting

Overview


- Machine group is finalising the design of the civil facilities for the TDR/DBD
- This is in the focus of the ILC management: cost drivers!
- Discussions between detector concepts (SiD/ILD) and ILC CFS group have been intensified since Granada
- Dedicated meeting in December at SLAC: final input from detector groups
- Started with the „non-mountain“ sites - hall design finalised
- Japanese site requirements are different
- Discussed ILD assembly at last integration meetings (Paris, Webex)
- CFS Baseline Technical Review Workshop at CERN on March 22-23
 - Discussions with GDE on cost issues!






Optimisation for
ILD requirements
important!


ILD in Maintenance Region (non-mountain site)



CMS Assembly



CMS Assembly



A. Hervé


YB0 landing in the CMS experiment hall

ILD Assembly

- CMS-type assembly for non-mountain sites:
 - Pre-assemble and test ILD components on surface as far as possible
 - Lower five yoke rings with pre-installed detector components
 - About one year of assembly underground
- Non-CMS-type assembly for mountain sites:
 - Part sizes are limited by access tunnel
 - Yoke rings need to be built underground
 - Sub-detectors mostly installed underground
 - Need more time (~3y) and more underground space


ILD Design

- Assumption: basic detector model will not change for mountain sites




Yoke Assembly - Barrel

- Start with central ring on platform
- Space needed for: tools, scaffolding, surveying equipment




Yoke Assembly - Barrel

- 200t crane coverage needed




Yoke Assembly - Barrel




Yoke Assembly - Barrel

- Tooling needs still under study




Yoke Assembly - Barrel



Yoke Assembly

R. Stromhagen


- Tolerances of the ring segments need to be better than 1 mm
- Laser surveying needed during full assembly
- Tools needed
 - 200t crane
 - chain hoists
 - tailored tools: beams etc.
 - hydraulics
 - surveyors
- Time estimate: 60 working days per ring



Endcaps: see R. Stromhagen's talk


Coil Installation

- Coil can only be transported without its ancillaries (cold box, chimney)
- Functional test needs to be done underground after installation into central barrel yoke ring
 - very low fields, yoke will not be ready by then
 - Takes >3 months (incl. cool-down and warm-up)
- Test of field mapping equipment is needed at the same time
 - ALEPH experience




R. Stromhagen


AHCAL Installation




AHCAL Installation



AHCAL/ECAL Installation




Endcap Calorimeter Installation




Calorimeter Installation

- Special tooling needed:
support cradle, directly mounted to the coil
- Crane coverage
- Surveying equipment
- Time estimate for AHCAL barrel:
 - 180 working days
- ECAL barrel:
 - probably less
- Endcaps: ?



K. Gadov




SDHCAL Installation




Barrel design : ILD integration

- Barrel with 5 wheels into the ILD





- Wheels are linked together
- Services installed then and connected between wheels



- Barrel ready to be connected put in front of the coil
- Insertion on the rails with tool


TPC Installation



- Critical path is defined by central detector construction:
 - central yoke ring, coil, barrel calorimeter, TPC, inner detector
- Will have three coexistent major „construction sites“ at the same time in the underground hall:
 - barrel part, both endcaps
 - consecutively: two other barrel yoke rings, QD0 pillar, forward calorimeter
- Time estimate: 3.25 years
- But: need sufficient underground space!
- There are remaining open questions:
 - how does the crane and transport capacity interfere with this plan?
 - when will the cryo services underground be ready (coil test)?
 - ...

Japanese Hall Design (Status 12/2011)


Y. Sugimoto



- Probably not enough space for detector assembly and regular maintenance


Maintenance Position (DESY Study)

- Changed hall model to enlarge alcoves in parking position (47m lateral space)
- maintenance only, more space needed if assembly takes place in alcoves




Larger Parking Position (DESY Study)

- Lateral space is needed to open the detector, remove QD0 magnets, inner detector, TPC
- Alternative: rotate the detector by 90 deg before opening
 - Almost impossible
 - need to disconnect cable chains and possibly cryo lines
 - warm-up the coil



Underground Construction Space (DESY Study)


- Three „construction sites“
- Platform (1): central yoke ring, coil, barrel detector
- Alcoves (2,3): endcaps: yoke, calorimeter
- Crane coverage:
 - 200t in main hall
 - 100t in alcoves



Underground Construction Space (DESY Study)

- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (>53m lateral space)
- Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground


R. Volkenborn



Underground Construction Space (DESY Study)

- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (>53m lateral space)
- Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground


R. Volkenborn




Underground Construction Space (DESY Study)

- Three underground „construction sites“ are minimum
 - Alcoves need to be enlarged (>53m lateral space)
- Fourth might be needed for YB+/- barrel yoke rings, QD0 pillars, etc.
- For comparison: CMS surface assembly hall : ~25m x ~90m
 - we need about the same - underground

R. Volkenborn



Japanese Hall Design (Status: 22.03.2012)




- Enlarged Alcoves
- 142 m long


G. Orukawa

Japanese Hall Design (Status: 22.03.2012)

G. Orukawa




Japanese Hall Design (Status: 22.03.2012)



- ◆ With 11m width access tunnel for SiD and ILD installation
- ◆ Two access tunnels are connected on the same side of cavern
- ◆ Access tunnels are connected at the same floor level of cavern's bottom floor
- ◆ Utility cavern is placed for utility (electric facilities, parking, various rooms...)
- ◆ Small access tunnels are connected to the garages for the pass
- ◆ Ventilation shaft is placed at utility cavern

Japanese Hall Design (Status: 22.03.2012)



- Alcove areas still too small (need >53m across)
- Loading zone and assembly area interfere
 - transportation of large items through the assembly zone difficult

An alternative plan of exp hall in mountain sites

2012/4/5

Yasuhiro Sugimoto


Response at CFS BTR

- GDE
 - Cavern is too large to keep cost containment
 - ILD
 - Cavern is too small to keep enough assembly area
- ➔ Design is modified to satisfy the both requirements


Key points

- Space between the garage and the beam line is used for the detector assembly
- The length of the cavern is reduced to 120m, which is same as the RDR
- Access tunnels are connected to both ends of the cavern to keep the strength of the cavern (90 degrees difference)
 - Rotating table for the detector solenoid may be necessary for installation
- Two crane girders per detector to make it possible to do two assembly works in parallel

Plan view




Assembly area




Assembly area

- Area 1 (Platform):20mx20m
 - Yoke assembly
 - Barrel detector installation/cabling
- Area 2/3 (Garage):20mx15m each
 - End cap CAL installation/cabling
- Area 4 (Beam line side): 20mx18m
 - Yoke assembly
 - Tentative platform should be constructed after solenoid transport
- Area 5 (Access tunnel side): 22mx12m
 - CAL assembly (modules→ring)
 - Tentative platform
- **Assembly area total ~ 20mx80m**
- Loading are ~ 22mx11m

Crane



Elevation view



My Status Summary

- We are converging on a detailed design for the Japanese underground hall
- There is pressure from the GDE to reduce complexity, i.e. cost
- First iteration on hall design was triggered by first assembly studies:
 - larger alcoves, 3-4 assembly areas in the hall
 - this has been presented at CFS BTR -> triggered cost discussion
- Yasuhiro has shown updated version that should have lower cost
- Clearly, we have to take the cost argument seriously
- Clearly, we need to find a solution for ILD in the mountain site!


My Status Summary (Cont.)

- I see some problems with the current proposal:
 - alcove areas are needed for the endcap installation, they need to be high enough and have 100t crane capacity (c.f. talk by R. Stromhagen)
 - Interference between loading zone and assembly area 1 is an issue: we need to share the crane capacity and the transport space
 - the assembly areas 4 and 5 need temporary platforms that must be able to carry the weight of up to two barrel yoke rings (~2 kt). At least the platform in area 4 needs to be disassembled before the detector could be moved into the beam. How do we do that?
 - How do we share transportation capacity in the access tunnel between SiD, ILD and the machine?
- We should be sure that we can assemble ILD in the available space now. We will never be able to ask for more space later....

Example: Installation Sequence of CMS (part.)

- Courtesy: CMS (A. Gaddi, H. Gerwig)


Lower YB+1 move to Far Z+



Design by CMS Integration group, April 2005.


G.W.Faber ETH-Z 32
LHCC IR April '05

Lower HB+ move to final position




Design by CMS Integration group, April 2005.

Lower HB+ move to final position




Design by CMS Integration group, April 2005.

Lower HB+ move to final position




Design by CMS Integration group, April 2005.

Lower YB0 move to final position




Design by CMS Integration group, April 2005.

Lower YB0 move to final position




Design by CMS Integration group, April 2005.

Move HB+ inside vacuum tank




Design by CMS Integration group, April 2005.

Move HB+ inside vacuum tank



Design by CMS Integration group, April 2005.


Lower HB- move to final position



Design by CMS Integration group, April 2005.

G.W.Faber ETH-Z 40
LHCC IR April '05


Lower HB- move to final position



Design by CMS Integration group, April 2005.

G.W.Faber ETH-Z 41
LHCC IR April '05


Move HB- inside vacuum tank



Design by CMS Integration group, April 2005.


G.W.Faber ETH-Z 42
LHCC IR April '05

Finish HB insertion start cradle removal



Design by CMS Integration group, April 2005.

Best: if we could do the same 3d simulation for ILD!




Design by CMS Integration group, April 2005.

CMS Surface Assembly Hall



CMS Surface Assembly Hall



CMS Surface Assembly Hall



Outlook

- There will be a review session at KILC12 for underground hall issues:
 - GDE Project Managers, MDI CTG, CFS group
- We should make sure that we make the case for the needs of the detectors
 - SiD is involved in the discussions, they are basically fine with the proposed design (modulo some details, e.g. height of alcoves)
- How do we proceed?