



SiD Workshop
Magnet DBD STATUS
SLAC


August 22, 2012


Wes Craddock and Marco Oriunno



RECENT CHANGES

- **FINAL CRYOSTAT ENVELOPE DIMENSIONS WERE SPECIFIED (Marty, Marco and Wes)**
- **A SOLIDEDGE Model of the Magnet is sufficiently complete to verify that specified dimensions provide enough room**
- **LIQUEFIER POSITION WAS MOVED TO THE DETECTOR**
- **QD0 2 K DISTRIBUTION BOXES WERE MOVED TO NEAR THE TOP OF THE DETECTOR**
- **AN ASSEMBLY PROCEDURE FOR THE MAGNET WAS WRITTEN**
- **FIRST PASS MAGNET DBD WRITTEN IN WORD**







ASSEMBLY PROCEDURE

- 1) Coil mandrels are precision machined with welding of seamless end rings and cooling loops. Cooling loops are extensively leak checked.
- 2) Solenoid modules are wound with each layer in alternating direction.
- 3) The four DID coil modules are wound on a 3 mm thick Al sheet that is mounted to machined cylinder. Internal coil to coil splices for each of the 4 modules are completed. A 5 mm sheet is attached to the OD of the DID coils.
- 4) DID coils are vacuum impregnated. This is a higher temperature resin than the solenoid resin.
- 5) DID coils are mechanically attached on top of solenoid cooling loops with screws to the solenoid mandrel.
- 6) Solenoid modules with attached DID coils are vacuum impregnated.
- 7) The two mating ends of the solenoid modules are precision machined.
- 8) Solenoid modules are stacked vertical and joined above ground at the detector site.
- 9) All 24 solenoid splices are completed above the DID. All DID module to module splices are completed
- 10) Axial tie rods are attached to the solenoid.
- 11) Inner and outer thermal shields are mounted to inner and outer vacuum shells.
- 12) Inner and outer vacuum shells are placed on the solenoid.
- 13) Vertical and radial tie rods are attached to the outer vacuum shell.
- 14) All internal plumbing and electrical connections are completed along with mounting of the thermal shield end plates. Piping extends a short distance past the chimney opening. Solenoid lead ends and DID lead ends extend through the vacuum shell current lead opening and are wrapped in a loop.
- 15) Top and bottom vacuum end plates are welded.
- 16) All tie rods are tightened.
- 17) The completed magnet assembly is rotated horizontal on a shaft parallel to the ground using the overhead crane and two pulling cables.
- 18) The magnet is moved to the detector cavern and lowered vertically into the bottom half of the magnet iron.
- 19) Current lead and cryogenic chimney pipe assembly are completed and welded.



REMAINING TASKS TO FINISH MAGNET DBD

- FINISH MAGNETIC 3D CALCULATIONS
Barrel/Door Spacer Plates + Penetrations
Get all forces and fringe fields
- FINISH MAGNETIC 2D CALCULATIONS
Coil Stress and Deflection
Fringe Fields
- MODIFY AND REDO THE CRYOGENIC FLOW DIAGRAM
- CRYO HEAT LOADS AND LINE SIZES TO CAVERN WALL
- FINISH SOLIDEDGE MODEL
- COSTS ?