



AHCAL Testbeams 2012-now

Oskar Hartbrich

CALICE spring meeting 2013, Hamburg March 21st 2013



Cern Testbeam Layer

- Four new HBUs for an active Engineering Prototype layer for CERN hadron testbeam
 - 576 channels
- 16 SPIROC2b ASICs (LLR) for the full layer
 - Autotrigger
 - Time stamping
 - External trigger validation
- Factor 8 in complexity compared to previous setup
 - Biggest system test yet
 - First Multi-HBU setup in a beam environment
- Hadron beam operation behind W-DHCAL $(3.8\lambda_0)$
 - Parasitic data taking (asynchronous)





Commissioning

- Map tiles to HBUs (grouped by bias voltage)
- Calibrate and configure bias DACs
 - Bias specifications provided by ITEP for homogenous MIP response (15pix/MIP)
 - ~20mV bias accuracy achieved after channel individual calibration
- Adjust preamplifiers to equalise channel gain after digitisation
 - Should lead to homogenous MIP response on ADC scale
- Configure autotrigger thresholds
 - Self triggered operation, data below threshold is lost
- MIP calibration
- TDC calibration



MIP Calibration - DESY Beam 2012

- MIP calibration in DESY-II electron testbeam
 - Single HBU at a time
- 2-4GeV electrons
 - Response similar to MIPs
- Each channel on every HBU scanned separately
 - Great time effort (10min/tile, ~100h)
 - Only possible because of shift volunteers (DESY, UHH, ITEP, BUW)
- ADC spectrum fitted with Landau-Gaussian convolution → MIP value



MIP Calibration Results

- External trigger validation demonstrated in testbeam setup
 - Autotrigger hits only accepted if validated by external trigger
 - Excellent noise suppression
- Fitted MIP positions show narrow distribution
 - Although broader than gain distribution
- Reference MIP calibration obtained for cross calibration and comparison with CERN data



CERN Setup

- DHCAL is set up in climate controlled tent
 - Stable temperature conditions
- Took Muon and Pion runs
 - 50GeV and 180GeV
- Varying beam rates during DHCAL operation
 - Mostly low rates (1-50Hz)
 - Needs good data quality monitoring and threshold adjustments
- One day of dedicated high rate, high energy Pion runs (1200Hz @ 180GeV)
- Digitised scintillator signal injected into two HBU channels for absolute timing reference
 - Heavily utilised in event building



CERN Data

- Very successful data taking at CERN!
- >400k Muons
- 420k reconstructed Pion events @ 180GeV
- 86k reconstructed Pion events @ 50GeV
- Very stable hardware operation
 - 3 hardware crashes in 11 days!





Data Quality

- Again: trigger threshold positions are crucial for taking good data
- SPIROC2b trigger behaviour is not trivial
- CERN Muon Data:
 - Good homogeneity of MIP positions
 - Thresholds well below ½MIP!
 - Excellent efficiency >95%
 - Good noise behaviour
 - External trigger validation!
 - Noise ~< 50Hz per HBU (<<signal rate)</p>
 - Even better for 180GeV Pions
- Data quality nicely under control





CERN Layer in DESY Beam

- January '13: Beam time for full CERN layer
 - TDC calibrations for CERN data
 - Also first tests for HBU stack
- Crosstalk problem on SPIROC2b
 - Loaded preamplifiers shift signal levels on whole chip
 - Showstopper for EM stack?
- 3GeV electrons on 6cm (\sim 3.5X₀) Fe absorber
- Reference amplitude from digitised scintillator trigger
- Self triggered operation (external validation)

 \rightarrow Environment as in May/June for EM Stack





Testbeam Ergebnis



- Slight negative correlation
 - Much weaker than in LED lab measurement (dashed line)
 - \rightarrow Effect mainly governed by signal rate
- Crosstalk negligible for EM stack operation!
- First "analysis" with new software framework

Summary and Outlook

Summary

- Successful commissioning of 576 channel AHCAL layer prototype
- Electron testbeam at DESY for full MIP calibration
 - Nice verification of commissioning
- Very successful data taking at CERN
 - High statistics and excellent data quality for 180GeV Pions
- TDC Calibration Testbeam in January
 - First tests for EM stack successful

Outlook

- Analysis of CERN data is in full operation
- Next setup: multi-layer prototype in DESY beam
 - EM showers in ILD absorber prototype
 - Most work focused on DAQ work for now

