




# Steps toward mass slab assembly

## Julien Bonis

P. Cornebise, C. Bourgeois, A. Gonnin, A. Thiebault, S. Pavy (until 3/2013)

## Background

- ASU interconnection study => A rapid and reliable method (lead by P. Cornebise).
- Test beam slab development and assembly knowledge.



Think up mass slab assembly methods and needs

*(Production rate, controls, storage, quality system....)*

## Steps toward slab mass assembly :

- **Step 1 : Coarse procedure for slab mass assembly**
  - Reception Controls, tests and storage.
  - Pre-assembly and upstream preparation.
  - Assembly : Separate in several stations for simple and available tools in steady work.
  - Packaging and storage.
- **Step 2 : Test and development of mass assembly methods (in progress).**  
*Detection of possible difficulties before validation.*  
*Under procedures redaction.*
- **Step 3 : Complete procedure for mass slab assembly.**
- **Step 4 : Initial study of industrial tools and organisation.**

# Step 1 : Coarse procedure for mass slab assembly


## ➤ Reception Controls, tests and storage.

*Reception controls and tests of ASU, adapt board, structure dimension....  
Dry storage for sensible parts.*

## ➤ Pre-assembly and upstream preparation

*=> Final assembly simplification.  
=> Less time constraint.*

- Interconnection Kapton glue on ASU.  Less parts to place precisely during assembly.



- Kapton HV glue in structure.
- Adapt board fixed in slab.
- Structure placed in half return tool with core below.


## ➤ **Assembly line.**

*Separate in several stations for simple and available standard tools in steady work.*

- *St1 : Electrically conductive glue put on HV Kapton.*
- *St2 : ASU setting out in slab.*
- *St3 : Interconnection.*
- *St4 : Controls of interconnection, wafer leakage current measure and functional test.*
- *St5 : Put on board and ASU fixing glue.*
- *St6 : Copper drain setting out in slab.*
- *St7 : Heat cure in damper.*


- *Slab Reversal*

- ...
- ...
- *Slab clamping.*



Stations of assembly line

Standard robots



## ➤ **Packaging and storage.**

*Dry conditions.*

....


## Step 2: Test and development of mass assembly methods.

### ➤ R and D assembly

*Dummy slab make up with inactive board and glass wafer (in progress).*

- Interconnection with 4 wafer inside ASU.
- Kapton comb Pre-assembly efficiency.
- Efficiency of ASU fixing in slab by electrically conductive glue before heat cure.
- Disassembled option.
- Repairable possibility.

*Dummy short slab*



**Interest for wafer gluing training**

### ➤ Automatic interconnection control.

*Lead by. P. Cornebise (See also talk).*

### ➤ Tools for interconnection Kapton brazing (=> automated process).

*Lead by P. Cornebise.*

*Cf.*