

---

# DESY Status

Sebastian Aderhold

With input by E. Elsen, A. Navitski, D. Reschke

1st LCC ILC Cavity Group Meeting


April 16, 2013

---

- > 800 cavities are required for the European XFEL
  - cavity gradient ~24 MV/m
- > 24 additional cavities will be purchased as part of the ILC-HiGrade programme (European Commission FP7) which was funded till 1/2012.
  - identical production to European XFEL except for He-Tank, which will be omitted to allow for further treatment
  - goal is to understand how to reach high gradients in industrially produced cavities
  - ILC specifies 35 MV/m in vertical test
  - if all 24 cavities were to perform excellently they could result in 3 world record cryomodules
- > The industrial contracts specify production procedure. They do not include performance specification
  - Some 10% of cavities may have to receive additional treatment
  - Quality assessment is partially funded by CRISP (European Commission FP7)



# Advanced Module Test Facility (AMTF)




Wave Guide Assembly and Test Facility



# SRF Infrastructure in AMTF


- > 2 cryostats
- > 6 mounting stations for inserts
- > Insert prepared to hold cavities with and without He-tank
- > moveable concrete shielding for radiation protection





Insert with shields being moved to cryostat



# First Results of XFEL Cavities: Vertical Acceptance Tests



- Vertical acceptance test done on 13 cavities equipped with He-tank and Higher Order Mode feedthroughs
  - 8 cavities meet specification w/o re-treatment
- Re-treatment by High Pressure Ultra-Pure Water (HPR) rinsing =>
  - 2 cavity successful done at DESY
  - 1 cavities in preparation
- 2 cavities with quench at 19 MV/m and 22 MV/m, resp.





Yield of max. and usable gradient based on 13 cav. for first pass of treatment; 12 cav. for 1.+2. pass of treatment

*Preliminary data; results are not published*

➔ **XFEL** order includes 24 cavities as a part of the ILC-HiGrade program:

- > Initially, serve as quality control (QC) sample for the XFEL
  - extracted regularly, ~one cavity/month: first cavity arrived!
  - after the normal acceptance test will be taken out of the production flow --> **R&D**
- > Delivered with full treatment but no helium tank
  - > maximize the data output from the test
- > Further handling within ILC-HiGrade/CRISP as feasibility study for ILC goal:
  - surface mapping from the 2nd cold RF test
  - optical inspection (OBACHT) and replica
  - Centrifugal Barrel Polishing
  - Local Grinding repair
- > Aim for 3 world record modules from the 24 ILC-HiGrade cavities


- > **Large amount** of cavities (also dressed) can be **inspected**: ILC-HiGrade, (European XFEL)
- > **Fully automated** (LabView) cavity inspection with Kyoto Camera System yields
  - 2790 pictures in ~8 hours: welding seems of equator (iris) every 4°(10°) + equator left/right
  - ~12 x 9 mm pictures (2488 x 2616 pixels, ~10 µm/pixel) in \*.bmp, \*.png and/or \*.jpg
- > Movable sled with cavity (axial posit. ~10 µm) and Kyoto camera (angular posit. ~0.01°),
- > Collision free movements assured by optical tests (**to be upgraded now**)
- > Fully **automatic** cavity **positioning**, **illumination**, and image **recording**
- > **Automatic** image **processing** and possibly defect **recognition**




- **Currently** all VT inserts @ DESY equipped with 8 OSTs to detect „second sound“
- **Upgrade** to 16 OSTs for the ILC-HiGrade cavity tests:
  - Better localization accuracy ( $< \text{cm}$ )
  - Allow additional R&D

## Required modification:

- ❖ New DAQ with more channels
- ❖ More feedthroughs on the cryomodule inserts
- ❖ Update of the evaluation software with better accounting of the cavity shape and wave propagation in Nb







- 100 m<sup>2</sup>
- 2 rooms
- to be ready around June 2013