



Superconducting RF cavity and its industrialization

加速器・物理合同 ILC夏の合宿2013
2013年7月23日
(富山 呉羽ハイツ)
佐伯 学行(KEK)

International Linear Collier (ILC)



Design in mountain area



e+, e- main linac

Energy : 250GeV + 250GeV

Length : 11km + 11km

of DRFS Klystron: 7280 total

of Cryomodules : 1680 total

of Cavities : 14560 total

ILC Cost Breakdown (RDR)




FIGURE 6.2-1. Distribution of the ILC value estimate by area system and common infrastructure, in ILC Units. The estimate for the experimental detectors for particle physics is not included. (The Conventional Facilities estimates have been averaged over the three regional site estimates.)

ILC Cost Breakdown (RDR)

TABLE 6.2-2

Distribution of the ILC Value Estimate by area system and common infrastructure, in ILC Units. The estimate for the experimental detectors for particle physics is not included. (The Conventional Facilities estimates have been averaged over the three regional site estimates.)

Area - M ILC Units	Total	Components	Conventional Facilities
Main Linac	3,894	2,723	1,172
DR	630	398	231
RTML	554	320	234
e ⁺ source	398	232	166
BDS	408	157	252
Common	369	229	140
Exp Hall	200	0	200
e ⁻ source	165	87	78
Sum	6,618	4,146	2,472

コストドライバー
かつ見積もりが
難しい。

最もコストがかかるライナック部分の量産が見積もり通りにいかず、コストが膨らむことがあれば、ILCの建設・完成は非常に困難となる。

(SB2009では、ダンピングリング周長を半分にし、トンネルを2本から1本にするなど、かなり大胆な設計変更をしたにも関わらず、コスト削減は13%にとどまった。つまりILCのコスト削減代はほとんどない。)

ILC(500GeV)の空洞生産台数の定義

クライオモジュールの台数(1.3GHz空洞を装荷するもの):総数1824台

6空洞クライオモジュール:4台(e⁺booster)

8空洞クライオモジュール:560台(Main Linac)+36台(RTML)+24台(e⁻source)
+18台(e⁺booster)+2台(e⁺keepalive)=640台

9空洞クライオモジュール:1120台(Main Linac)+60台(RTML)=1180台

使用する1.3GHz ILC空洞の総数=15,764台 (RDRの定義)

35MV/m以上の性能の空洞をクライオモジュールに使用すると仮定し、
15764台をすべて35MV/m以上とさせるためには9.9%多く生産しなければならない。

(ただし、これはRDRの定義ではない)

15764 x 1.099 = **17,325台の空洞生産が必要**

もし、日本が1/3の製造担当をすると、


超伝導空洞 17325台/3/(5年) = 1155台/年

(1155台/200日 = **6台/日**)

超電導空洞による加速器の歴史

プロジェクト	運転開始 /終了	RF周波数 MHz	セル数	ユニット総数	Effective Length m	Acc. Gradient MV/m	Total Voltage MV	コメント
TRISTAN KEK	1986/1995 1988/1995	509	5	32	48	5	200	Collider
HERA DESY	1990/2007	500	4	16	20	4	50	Collider
LEP/CERN LEP-II	1989/2000 1996/2000	352	4/NbCu	288	600	6	3400	Collider
CEBAF J-lab	1996~ 2008~	1500 1500	5 7	330 未定	165 増設	5→7.5 20	800→1200	recirculating
CESR Cornell	1997~	500	1	4	1.2	8	10	電流フロン ティア
JlabFEL	1998~	1500	7				150	
KEKB KEK	1998~	509	1	8	2	6	12	電流フロン ティア
SNS ORNL	2006~	805	6	33+48 Low- β /High- β	22+42	10(Low)/16(High)	892	陽子リニアック 1.3ms、60Hz
BEPC-II IHEP	2006~	500	1	1+1	0.25+0.25	1.6		Collider

TRISTAN @ KEK



TRISTANの超伝導空洞
ニオブ 508MHz 5セル空洞

世界で最初の大規模応用。
32台を製造して使用した。

Superconducting Linac

- Designed and built by Jefferson Laboratory
- SCL accelerates beam from 186 to 1000 MeV
 - Reached 1011 MeV
 - Run at 890 MeV most of the time
- 81 Niobium cavities in 23 cryomodules (33 medium .61 beta, 48 high .81 beta)
- Cavities are now operated at 2.1 K
- Until Spring 2007 mostly run at 4.5 K (can run up to 30 Hz, 1.3 msec RF pulse width)



Medium beta cavity




High beta cavity



ILCの空洞製造数は文字通り桁違い

加速空洞
多セル超伝導
空洞の総数

ハイテック装置
の大量生産
品質管理
コストダウン




Toward Industrialization

- Global status of Industries
 - Research Instruments (ACCEL) and Zanon in Europe
 - AES, Niowave, Roak, PAVAC in Americas
 - MHI, Hitachi, Toshiba, and others in Asia

Project Scope			Assuming 200 work-days/yr
SNS	~ 110	3years	< ~ 1 cavity / week
XFEL → ÷ 2 vendors	~760	2 years	380/yr : ~ 1.9 cavity/day → 0.95 /day/vendor
Project X	~360	4-5 years	72/yr : 1.8 cavity / week
ILC			
Single vendor model	~15,500 + spare	5 years	~3100/yr → 16/day ~3400/yr → 17/day
6 vender model (3 regions x 2)	same	same	→ ~ 570/yr → 2.8/day/vendor

SCRF Procurement/Manufacturing Model



Visiting Companies in Progress

(and further plan)

	Date	Company	Place	Technical subject
1	2/8	Hitachi	Tokyo (JP)	Cavity/Cryomodule
2	2/8	Toshiba	Yokohana (JP)	Cavity/Cryomodule, Magnet
3	2/9	MHI	Kobe (JP)	Cavity / (Cryomodule)
4	2/9	Tokyo-Denkai	Tokyo (JP)	Material (Nb)
5	2/18	OTIC	NingXia (CN)	Material (Nb, NbTi, Ti)
6	3/3	(Zanon) mtg at INFN	Verona (IT)	Cavity/(Cryomodule)
7	3/4	RI	Koeln (DE)	Cavity (Cryomodule)
8	3/14, (4/8)	AES	Medford, NY (US)	Cavity (Cryomodule)
9	3/15, (4/7)	Niowave	Lansing, MI (US)	Cavity/ (Cryomodule)
10	4/6	PAVAC	Vancouver (CA)	Cavity, EBW-machine
11	4/25	ATI Wah-Chang	Albany, OR (US)	Material (Nb, Nb-Ti, Ti)
12	4/27	Plansee	Ruette (AS)	Material (Nb, Nb-Ti, Ti)
13	5/24	SDMS	Sr. Romans (FR)	Cavity, Vessel, joint
14	7/6	Heraeus	Hanau (DE)	Material (Nb, Nb-Ti, Ti)
15	9/14	Zanon	Verona (IT)	Cryomodule
16	11/16	SST	Munchen (DE)	EBW-machine

世界の超伝導空洞性能（3極平均）

RDRでは、製造受け入れ性能 $>35\text{MV/m}$ で90%の歩留まり(Yield)を仮定している。




Progress Integrated in Cavity Gradient Yield

Updated, April., 24, 2012

Plot courtesy
Camille Ginsburg of FNAL




Electropolished 9-cell cavities
/KEK (combined) up-to-second successful test of
cavities from established vendors



Progress in SCRF Cavity Gradient

2nd pass yield - established vendors, standard process



Production yield:
94 % at > 28 MV/m,

Average gradient:
37.1 MV/m

reached (2012)

Issues of mass-production:
High Quality Assurance (QA)
Cost Reduction



ILCの技術開発を行っている世界の主な研究所

DESY/FLASH,
EURO-XFEL


INFN
SACLAY/XFEL

KEK/STF/ATF/CFF

FNAL/ILCTA, ANL
Cornell
JLAB
SLAC



FLASH@DESY




STF@KEK




ILCTA@FNAL

ILC Test Facilities at KEK




KEK Cavity Fabrication Facility



KEK Cavity
Fabrication
Facility


Slide by Hayano



Chemical
Room

Press Machine

Trimming
Machine



Inspection area

Plant clean room

Crane range


EBW delivery on April 12, 2011



12th April 2011

Main Machines in the facility

EBW



SST EBOCAM KS-110 – G150KM Chamber (Stainless Steel chamber)

Press



AMADA digital-survo-press SDE1522
150t, 50stroke/min, 225mmstroke

Trim



MORI VKL-253
Vertical CNC lathe



Tape-cut Ceremony on
July 13, 2011
for
EBW operation start.



Chemi-room¹⁹


Production procedure of 9-cell cavity for ILC

Dumbbell = EBW of two cups :




8 dumbbells are needed for one cavity


EBW assembly of all parts :



Welding of He tank :



KEK-0号機(試作機) 溶接作業



開先形状と溶接条件をKEKが管理して、
ジョブショップにて製作した部分

KEK内の空洞製造施設
にて溶接した部分




KEK内の空洞製造施設
にて溶接した部分

試作空洞の完成(2012年1月31日)


Configuration choice of cavity attitude and gun position

Direction of electron beam is vertical.




Setting cavity in horizontal way is rather complicated (KEK-00).

Direction of gravity.



Direction of electron beam is horizontal.







Setting cavity in vertical way is simple (KEK-01).

Stacking dumbbells is easy in the vertical configuration of cavity.




Better for mass-production.

Multi-dumbbell EBW at equator (KEK-01)




Complicated shapes of HOM couplers



HOM coupler



Complicated machining and EBW of parts is needed for fabrication of HOM couplers



HOM can



HOM antenna


Fabrication of HOM cup by deep-drawing for KEK-01

End-group shape is complicated and then there is a possibility of cost-reduction in fabrication.


Conventional method: Deep-drawing by multiple press-forming with annealing.

New method: Deep-drawing by single press-forming.

Nb sheet thickness: 2.8 mm



HOM cup ($\phi 48 \times 64$)




Collaboration with industry:
Shinohara Press Service Co. Ltd.



Trial to fabricate the freq. tuning tab by press-forming.
(Under study)

Fabrication of HOM antenna by water-jet cutting and press-forming for KEK-01



Conventional method: Machining
New method: Water-jet cutting
+ Press-forming



Water-jet cutting in a job shop



Collaboration with 



Press-forming


Result of low power test is OK. (Master thesis by F. Yasuda, Jan. 2013, the university of Tokyo, JAPAN)



Design of loader for multiple dumb-bells

Pumping time (~30 min.) and cooling time (~30 min.) are duplicated in EBW processes.


e- gun
on side



Proto-type of four-dumbbell loader

Multiple dumbbells are loaded inside the EBW chamber at once and the EBW of dumbbells will be done continuously after pumping down.

Design of 9-cell cavity fixture for EBW machine




Six-cavity
revolver fixture

Pumping time (~30 min.) and cooling time (~30 min.) are duplicated in EBW process. The time is reduced if multiple-seams are welded in one pumping cycle.



Proto-type of
revolver fixture

Japanese High-Pressure Gas safety act




One must fabricate cavities complying with **Japanese High-Pressure Gas (J-HPG) safety act** if we use the cavities in accelerators.

For cavities by vendors,
Manufacturer: KEK
Applicant: vendors




For cavity KEK-03 in CFF,
Manufacturer: KEK
Applicant: **KEK/CFF**



In case of ILC in Japan, a significant fraction of cavities might be imported from foreign vendors. KEK/CFF can guide them for the procedures of J-HPG safety act.

STF (Superconducting RF Test Facility)



4空洞のSTRING組み立て




EP facility at STF/KEK

Automatic
Operation Console

1st EP bed

9-cell cavity

EP acid: HF + H₂SO₄
Aluminum anode,
surface removal speed:
20μm/hour,
~18V ~270A ~30degC
(for 9-cell)
cavity rotation: 1 rpm



1st floor






EP solution
reservoir tank

New EP facility at KEK was constructed in 2008, instead of old Nomura EP facility.


EP process at STF-KEK

Heat exchanger

Temperature of electrolyte is controlled through heat exchanger by cooling/hot water



Surface treatment of 9-cell cavity (KEK-00) at STF/KEK



Bulk EP (100 μm), Degreasing (50 $^{\circ}\text{C}$, 30 min.), HPR (1.5 h), Annealing (4 h, 750 $^{\circ}\text{C}$), and final EP (20 μm)



HPR (7 hours)

Brushing




Brushing of beam-pipe and HOM antenna. Degreasing with detergent (FM-20 2%) in hot bath (50 $^{\circ}\text{C}$, 30 min.)

Estimation of cavity production plant

Slide by Hayano

KEK-MHI

Plant Simulation study using CFF housing area (53m x 30m)



Assuming Nb plates for cell, fabricated end-group parts are input, 200 working days/year, 2 shifts/day with 30 people times 2 shifts



Max. production rate will be ~530 cavities/year, ~2650 cavities for 5years.

Assuming that final treatment and vertical test will be done in other place.


電解研磨設備の例



Saclay Vertical-EP

新規施設

超伝導加速器利用促進化推進棟(新設)



2013年整備

革新的産学連携推進エリア


STF(既設)

STFトンネル(既設)



ATF

量子ビーム利用新機軸創出エリア

超伝導加速器利用促進化推進棟の機器配置図



4台空洞用 縦測定設



DESY AMTF

Accelerator technology - collaborative effort

Industrial study module assembly (M6 done, M8 autumn 2007)

Superferric magnet (CIEMAT)



2 more cryostats (TTF3/INFN) delivered




BPM (Saclay)




超電導空洞: 760台

Integrated HOM absorber




Length quantized $n \cdot \lambda/2$ (possibility of ERL)




Tuner w/piezo (Saclay)



Industrialization in preparation



LLRF development (collab. Warsaw/Lodz)



TTF3-type coupler
Industrialization launched (Orsay)



Civil Construction for the European XFEL



← 3.4km →



Civil Construction



Slide by H. Weise

3, 2011
Hans Weise, DESY

RI: 380 cavities / 2 year
Zanon: 380 cavities / 2 year
Total 760 cavities / 2 year

ストリング組立

DESY


Saclay



空洞製造




受入性能試験
いわゆる縦測定



DESY takes care of installation / dismounting of cavities into / from test insert
Transport to CEA in transport boxes as well

Assembly Buildings at Saclay



Village X-FEL

Clean
Romm

Assembly
Halls

Offices
Warehouse

Bât. 126 Nord
40x11 m²

Bât.126 Sud
30x17 m²


Bât. 124 Nord
25x15 m²

Cour
MA

©GoogleMap

Industrialisat
Cryomodule Assembly

Assembly Hall : Workstations






EURO-XFEL 空洞ストリング組立

クリーンルーム内にて組立

1.3GHz 9セル超伝導空洞
~760 cavities (>23.5MV/m)をRI社(旧ACCEL)
とZANON社が製造
2015年からLinac commissioning開始予定



Clean Room Workstations at Saclay



Clean Room constructed (Sept'09)



Saclay

5 Mar. 2012




業者に渡す作業手順書の作成を行うための、手順の確認作業を行っていた。


Saclay(March 2011)



Clean room and low-pressure rinsing system



Platform with many nozzles for Low-pressure rinsing system



High-pressure rinsing system for Spiral-2 cavity

Saclay

5 Mar. 2012



Full production (1 cryomodule/week)は、来年の1月頃になるだろうとのこと。


Saclay(March 2011)



Cold-mass carrier with electric motor with wireless-controller



Saclay (March 2011)



7 March 2011 at Saclay

PXFEL 2.1 (DESY >>> Saclay >>> transportation to DESY within a few weeks)


SaclayにおけるXFEL Cryomodule組み立てスケジュール

Phase 1: Preparation of Infrastructure and Tooling
2008 → April 2010

Phase 2: Training and Commissioning at Saclay with
XFEL Prototype Modules (PXFEL2 and PXFEL3)
May 2010 → mid-2011
including Call for Tender for Assembly Contract by end 2010

Phase 3: XFEL module assembly by ind^{ial}. contractor
mid-2011 → mid-2014

DESY (March 2011)




Construction of Accelerator Module Test Facility (AMTF) hall is on going.



Three cryomodule test stands.


Accelerator Module Test Facility (AMTF) Including Single Cavity Tests



- Warm cryogenic piping 10/2010
- ISO- and UH Vacuum equipment 10/2010
- Vacuum compressors commissioning 11/2010
- cryo components (LHe sub cooler & He storage tank main transfer line & vertical cryostats) are late – fall 2011


- **Commissioning**
 - vertical tests late fall 2011
 - horizontal tests end 2011

Acc. Module Test Facility (AMTF) DESY / March 2011




Construction of Accelerator Module Test Facility (AMTF) hall is on going.

EURO-XFEL Injector (Mar. 2011)



Spring 2011


EURO-XFEL Injector (Mar. 2011)




Construction of Injector hall is ongoing.

EURO-XFEL Injector


Feb 2013



DESY (March 2011)




End of SRF linac. Entrance of tunnel boring machines.



End of SRF linac

DESY (March 2011)





DESY is in this direction




Construction of experimental halls is ongoing.

DESY (March 2012)




DESY (March 2012)

8 Mar. 2012




DESY (March 2012)



DESY (March 2012)

8 Mar. 2012



CERN's Experience from LHC Cryostating and Test




Bringing industry to the laboratory
Cryostat assembly by industry on CERN site



Producing in-house with industrial methods
Cryogenic magnet test station at CERN



- Initial Configuration-1



- Strong alignment with ILC technologies
- Initial Configuration Document-1 V1.1 released March 2009
 - Accompanying cost estimate ~\$1.5B

Project X Linac Configuration








Figure III-3 : Layout and component counts for the initial Project X linac configuration

North American Cavity Vendors and laboratories



- **Advanced Energy Systems (AES), Inc.**
Medford, New York
<http://www.aesys.net/>
- **Niowave, Inc.**
Lansing, Michigan
<http://www.niowaveinc.com/>
- **C.F. Roark Welding & Engineering Co., Inc.**
Brownsburg, Indiana
<http://www.roarkwelding.com/>
- **Pavac Industries, Inc.**
Richmond, British Columbia
<http://www.pavac.com>

AES has complete production capability on-site
10 nine-cells delivered; 6 more in April, 20 more ordered (ARRA)



Cryomodule activities at FNAL



CM1 String Assembly



MP9 Clean Room



Final Assembly



CM1



Move to NML



CM1 installed




Dressing cavities for CM2



FNAL S1 global Cavities @ KEK

Summary

- ILCのコストは、約半分がmain linacのコストである。main linacの主componentである超伝導空洞の生産が見積もり通りに行えるかがILC建設において重要。
- 空洞の生産台数
XFEL: 760台/2年
Project X: 360台/5年
ILC: 17000台/5年 桁違いの生産台数
- しかし、6 vendor model を仮定すれば、factor 2 – 3 の規模拡張でILCに対応できる。
既に 9 vendors が存在している。
各vendorは、factor 2 程度の規模拡張は問題なく可能。
- Hub-laboratories の施設も同様に拡張が必要。
EU: DESY + Saclay + CERN
USA : FNAL + Jlab
Asia : KEK


Hub laboratories が多少の規模拡張を行えばILCの量産に対応可能！
- KEK(CFF)を核にして、日本におけるILC加速器の量産化の研究が進んでいる。
- KEK(CFF)において、高圧ガス保安法に準拠した空洞の製作を計画。
その延長線上に、国内における空洞製造の多ベンダー化の促進、ILCにおける外国空洞の高圧ガス保安法準拠の実績作りがある。